Corporate Identity Number: U24100MH1968PTC014142

Registered Office: E Block, Voltas Premises, T B Kadam Marg, Chinchpokli, Mumbai 400 033, India
Tel: +91 22 6661 4444 • Fax: +91 22 6661 4452 • E-mail: trilsec@tatarealty.in

Date: 18/12/2023

To.

Regional Officer, Navi Mumbai, Maharashtra Pollution Control Board, Raigad Bhavan, 7th floor Sector – 11, C.B.D Belapur, Navi Mumbai. Maharashtra.

Sub

: Submission of six-monthly compliance status report as per terms & Conditions stipulated in Environmental clearance letter for the proposed 'Intellion IT Park', at Plot nos. 23, 23(pt), 24 & 24(pt), TTC Industrial Area, Thane-Belapur Road, Mahape MIDC, Mahape, Navi Mumbai. Maharashtra.'

Ref. No.

: Environment clearance no. SEIAA-EC-0000002300, dated: 15/01/2020.

Respected Sir/Madam,

In reference to the above-mentioned letter from your office, we would like to submit the Current status of our construction work and point-wise compliance status to various Stipulations laid down by the Ministry in its clearance letter SEIAA-EC-0000002300, dated: 15/01/2020 along with the necessary annexure.

This compliance report is submitted for the period from April 2023 to September 2023.

This is for your kind consideration and records.

Kindly acknowledge the same.

Thanking You,

Enel

For, Industrial Minerals & Chemical CO. Pvt. Ltd.

Authorized Signatory

: Part A: Current status of construction work.

Part B: Point-wise compliance status.

Datasheet & Annexures.

Copy to Regional Office, MoEF & CC, Nagpur.

Department of Environment, Mantralaya, Mumbai.

Regional Office, CPCB, Pune

Corporate Identity Number: U24100MH1968PTC014142

Registered Office: E Block, Voltas Premises, T B Kadam Marg, Chinchpokli, Mumbai 400 033, India Tel: +91 22 6661 4444 • Fax: +91 22 6661 4452 • E-mail: trilsec@tatarealty.in

Date: 18/12/2023

To.

Member Secretary, State Level Environmental Impact Assessment Authority (SEIAA),

217, Department OF Environment, Government of Maharashtra,

2nd Floor, Annex Building, Mantralaya,

Mumbai - 400 032. Maharashtra.

Sub

: Submission of six-monthly compliance status report as per terms & Conditions stipulated in Environmental clearance letter for the proposed 'Intellion IT Park', at Plot nos. 23, 23(pt), 24 & 24(pt), TTC Industrial Area, Thane-Belapur Road, Mahape MIDC, Mahape, Navi Mumbai. Maharashtra.'

Ref. No.

: Environment clearance no. SEIAA-EC-0000002300, dated: 15/01/2020.

Respected Sir/Madam,

In reference to the above-mentioned letter from your office, we would like to submit the Current status of our construction work and point-wise compliance status to various Stipulations laid down by the Ministry in its clearance letter SEIAA-EC-0000002300, dated: 15/01/2020 along with the necessary annexure.

This compliance report is submitted for the period from April 2023 to September 2023.

This is for your kind consideration and records.

Kindly acknowledge the same.

Thanking You,

For, Industrial Minerals & Chemical CO. Pvt. Ltd.

Authorized Signatory

Encl:

: Part A: Current status of construction work.

Part B: Point-wise compliance status.

Datasheet & Annexures.

Copy to Regional Office, MoEF & CC, Nagpur.

Regional Office, MPCB, CBD Belapur, Navi Mumbai.

Regional Office, CPCB, Pune

Corporate Identity Number: U24100MH1968PTC014142

Registered Office: E Block, Voltas Premises, T B Kadam Marg, Chinchpokli, Mumbai 400 033, India Tel: +91 22 6661 4444 • Fax: +91 22 6661 4452 • E-mail: trilsec@tatarealty.in

Date: 18/12/2023

To.

Ministry of Environment, Forests & Climate Change, Integrated Regional Offices,

Ground Floor, East Wing, New Secretariat Building, Civil Lines, Nagpur – 440 001. Maharashtra.

Sub

: Submission of six-monthly compliance status report as per terms & Conditions stipulated in Environmental clearance letter for the proposed 'Intellion IT Park', at Plot nos. 23, 23(pt), 24 & 24(pt), TTC Industrial Area, Thane-Belapur Road, Mahape MIDC, Mahape, Navi Mumbai. Maharashtra.'

Ref. No.

: Environment clearance no. SEIAA-EC-0000002300, dated: 15/01/2020.

Respected Sir/Madam,

In reference to the above-mentioned letter from your office, we would like to submit the Current status of our construction work and point-wise compliance status to various Stipulations laid down by the Ministry in its clearance letter SEIAA-EC-0000002300, dated: 15/01/2020 along with the necessary annexure.

This compliance report is submitted for the period from April 2023 to September 2023.

This is for your kind consideration and records.

Kindly acknowledge the same.

Thanking You,

For, Industrial Minerals & Chemical CO. Pvt. Ltd.

Authorized Signatory

Encl : Part A: Current status of construction work.

Part B: Point-wise compliance status.

Datasheet & Annexures.

Copy to Regional Office, MPCB, CBD, Belapur, Navi Mumbai.

Department of Environment, Mantralaya, Mumbai.

Regional Office, CPCB, Pune

Corporate Identity Number: U24100MH1968PTC014142

Registered Office: E Block, Voltas Premises, T B Kadam Marg, Chinchpokli, Mumbai 400 033, India Tel: +91 22 6661 4444 • Fax: +91 22 6661 4452 • E-mail: trilsec@tatarealty.in

Date: 18/12/2023

To.

Regional Directorate, Pune, Central Pollution Control Board, (Ministry of Environment, Forest & Climate Change), Govt. of India, Survey no. 110, Dhankude Multipurpose Hall, Baner Road, Baner, Pune – 411 045. Maharashtra.

Sub

: Submission of six-monthly compliance status report as per terms & Conditions stipulated in Environmental clearance letter for the proposed 'Intellion IT Park', at Plot nos. 23, 23(pt), 24 & 24(pt), TTC Industrial Area, Thane-Belapur Road, Mahape MIDC, Mahape, Navi Mumbai. Maharashtra.'

Ref. No.

: Environment clearance no. SEIAA-EC-0000002300, dated: 15/01/2020.

Respected Sir/Madam,

In reference to the above-mentioned letter from your office, we would like to submit the Current status of our construction work and point-wise compliance status to various Stipulations laid down by the Ministry in its clearance letter SEIAA-EC-0000002300, dated: 15/01/2020 along with the necessary annexure.

This compliance report is submitted for the period from April 2023 to September 2023.

This is for your kind consideration and records.

Kindly acknowledge the same.

Thanking You,

Encl

For, Industrial Minerals & Chemical CQ. Pvt. Ltd.

Authorized Signatory

: Part A: Current status of construction work.

Part B: Point-wise compliance status.

Datasheet & Annexures.

Copy to Regional Office, MPCB, CBD, Belapur, Navi Mumbai.

Department of Environment, Mantralaya, Mumbai.

Regional Office, MoEF & CC, Nagpur.

CIN: U24100MH1968PTC014142

Registered Office: E Block, Voltas Premises, T B Kadam Marg, Chinchpokli, Mumbai 400 033 Tel: +91 22 6661 4444 • Fax: 91 22 6661 4452 • E-mail: trilsec@tata.com

INDEX

SI. No.	PARTICULARS
1.	Part A: Current status of work
2.	Part B: Point wise compliance
3.	Datasheet
4.	Annexures
Annexure – 01	Approved Layout Plan
Annexure – 02	Acknowledgment copies of NHSRCL application
Annexure – 03	Civil Aviation certificate (Height clearance)
Annexure – 04	Fire NOC
Annexure – 05	Acknowledgment copies of TCFS application
Annexure – 06	Thane Creek Flamingo Sanctuary NOC
Annexure – 07	CER Plan
Annexure – 08	Acknowledgement copy of CER Plan
Annexure – 09	Commencement certificates
Annexure – 10	Consent to Establish
Annexure – 11	Workers Health Report
Annexure – 12	Environmental monitoring reports
Annexure – 13	PUC certificate
Annexure – 14	Environmental clearance
Annexure – 15	Advertisement copy

CIN: U24100MH1968PTC014142

Registered Office: E Block, Voltas Premises, T B Kadam Marg, Chinchpokli, Mumbai 400 033 Tel: +91 22 6661 4444 • Fax: 91 22 6661 4452 • E-mail: trilsec@tata.com

: PART A:

Current Status of Work

Current Status of Construction	Τ:	Current status of construction work completed as of September
		2023 is 38,480 Sq. meters.
		• 1 st , 2 nd , 3 rd , 4 th , 5 th and 6 th Slab RCC works 100% Completed.
		 7th Slab RCC works 84% completed and 8th Slab RCC works 67% completed.
		 Blockwork and plaster work in progress at Ground + 4 Parking floors.
		 MEP works in progress at Ground + 4 parking floors.
Date of commencement (Actual and/or planned)	:	27/12/2021 (Actual) Site preparation work started on 27/12/2021 based on commencement certificate received.
Date of completion (Actual and/or planned)	:	January 2027 (Planned)

CIN: U24100MH1968PTC014142

Registered Office: E Block, Voltas Premises, T B Kadam Marg, Chinchpokli, Mumbai 400 033 Tel: +91 22 6661 4444 • Fax: 91 22 6661 4452 • E-mail: trilsec@tata.com

: PART B:

Compliance status of conditions stipulated in Environmental clearance letter granted for the proposed 'Intellion IT Park', at plot no. 23, 23(pt), 24 & 24(pt), TTC Industrial Area, Thane-Belapur Road, Mahape MIDC, Mahape, Navi Mumbai. Maharashtra by SEIAA, Govt. of Maharashtra vide Environment clearance no. SEIAA-EC-0000002300, dated: 15/01/2020 are as follows.

SI. No.	Stipulated clearance condition	Compliance status
Specific	Conditions:	
i.	PP to submit Approved plan.	❖ Approved plan is attached as Annexure – 1.
ii.	PP to obtain the NOC from the National High Speed Rail Corporation Ltd. (NHSRCL), if required.	 Applied to National High Speed Rail Corporation Ltd. (NHSRCL) vide letter dated: 12/12/2019 to grant their NOC. Please refer Annexure – 2 for Acknowledgment copy of application.
iii.	PP to upload the civil aviation NOC.	 Airports Authority of India issued Civil Aviation (Height Clearance) NOC for the project vide letter no. SNCR/WEST/B/062218/315236, dated: 10/08/2018. Please refer Annexure – 3 for Civil Aviation.
iv.	PP to upload the CFO NOC. PP to abide the all conditions laid in the CFO NOC dated: 25/09/2019.	 Chief Fire Officer & Fire Advisor, MIDC, Mumbai issued Fire NOC for the project vide letter no. MIDC/Fire/D-15182, dated: 25/09/2019. Please refer Annexure – 4 for Fire NOC. We will ensure to abide all the conditions laid in the CFO NOC.
V.	PP to ensure that RG should be intact even during future development also.	 We will ensure that RG area admeasuring 19,996.99 Sq. meters will be intact during future development also. Out of 2,900 Sq. meters RG area has been developed (Nursery area 1,500 in Sq. meters & Easement area 1,400 in Sq. meters outside of project area, area under MIDC Authority) 15 nos of tress are newly planted, and 43 trees are transplanted.
vi.	The PP to get NOC from competent authority with reference to Thane Creek Flamingo Sanctuary, if the project site falls within 10 Kms radius from the said sanctuary boundary. The planning authority to	Our project is situated in 4.00 Kms (Aerial Distance) from Thane Creek Flamingo Sanctuary. We have applied for the NOC vide letter dated: 12/12/2019 with reference to the

CIN: U24100MH1968PTC014142

SI.		
No.	Stipulated clearance condition	Compliance status
	ensure fulfilment of this condition before granting CC.	same. ❖ Please refer Annexure – 5 for Acknowledgement copy. ❖ NOC received from Office of the Divisional Forest Officer, Kurla, Mumbai for Wildlife NOC with reference to Thane Creek Flamingo Sanctuary vide letter no. 2415/2019-20, dated: 28/02/2020. ❖ Please refer Annexure – 6 for NOC received from Forest Department.
vii.	PP to submit CER prescribed by MoEF & CC circular dated: 01/05/2018 relevant to the area and people around the project or Environment Department may direct PP to undertake CER work in identified area as identified by Environment Department.	We hereby commit to provide the cost Rs. 4.50 Crores (1.5 % of project cost) towards the CER activity.
viii.	PP to ensure that CER plan gets approved from Municipal Commissioner / District Collector.	 We will ensure the CER plan gets approved from Municipal Commissioner / District Collector. We have submitted CER activities details to The District Collector, Thane Collector Office, Thane vide letter dated: 07/01/2019. Please refer Annexure - 8 for Acknowledgement copy of CER.
ix.	PP shall comply with standard EC conditions mentioned in the Office Memorandum issued by MoEF & CC vide F. No. 22-34/2018-IA.III, dated: 04/01/2019.	Noted and adhere to.
x.	SEIAA decided to grant EC for: FSI area: 38,208.74 Sq. meter Non-FSI area: 26,825.01 Sq. meter and Total BUA area: 65,033.75 Sq. meter (Plan Approved no. EE/SPA/23, 23(pt), 24, 24(pt)/D35970/2019, date: 10/10/2019)	
Genera	l Conditions:	
i	E-waste shall be disposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2016.	vendor as per E-waste (Management and Handling) Rules, 2016.
ii	The Occupancy Certificate shall be issued by the Local Planning Authority to the project only after ensuring sustained availability of drinking water, connectivity of sewer line to the project site and	

CIN: U24100MH1968PTC014142

SI.		<u>. </u>
No.	Stipulated clearance condition	Compliance status
	proper disposal of treated water as per	
	environmental norms.	
iii	This environmental clearance is issued subject to obtaining NOC from Forestry & Wild life angle including clearance from the standing committee of the National Board for Wild life as if applicable & this environment clearance does not necessarily imply that Forestry & Wild life clearance granted to the project which will be considered separately on	 per Final Notification reg. ESZ of SGNP published by MoEF & CC u/no. S.O.3645 (E), dated: 05/12/2016 as our project site is not affected by the ESZ belt. NOC received from Office of the Divisional Forest Officer, Kurla, Mumbai for Wildlife NOC
	merit.	with reference to Thane Creek Flamingo Sanctuary vide letter no. 2415/2019-20, dated: 28/02/2020.
iv	PP has to abide by the conditions stipulated by SEAC & SEIAA.	Agreed to comply with.
V	The height, Construction built up area of proposed construction shall be in accordance with the existing FSI/FAR norms of the urban local body & it should ensure the same along with survey number before Approving layout plan & before according commencement certificate to proposed work. Plan approving authority should also ensure the zoning permissibility for the proposed project as per the approved development plan of the area.	 Maharashtra. Special panning authority, MIDC approved the building plan vide dated: 11/10/2019. Executive Engineer & Special Planning Authority, MIDC Division no. II, Mahape issued
vi	If applicable Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.	MPCB granted consent to establish for the project vide consent no. Format1.0/CAC- CELL/UAN No. 0000085051/CE-2009000093,

CIN: U24100MH1968PTC014142

SI.		
No.	Stipulated clearance condition	Compliance status
vii	All required sanitary and hygienic measures should be in place before starting construction activities and to be maintained throughout the construction phase.	 All necessary facilities have been provided on site for construction workers. 60 nos of temporary rooms in 3 sections have been provided for 337 nos of residential workers at project site, adequate MIDC pipeline water provided for drinking & domestic purpose, 17 nos of toilets with septic tank & 17 nos of bathrooms have been provided at the labour camp. Municipal solid waste generated at labour camp is being handed over to local body on daily basis. Periodical medical checkup facilities have been provided to construction workers. Proper housekeeping & regular pest is being carried out. Please refer Annexure – 11 for Workers Health Reports.
viii	Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.	 Reports. All necessary facilities have been provided on site for construction workers. 60 nos of temporary rooms in 3 sections have been provided for 337 nos of residential workers at project site, adequate MIDC pipeline water provided for drinking & domestic purpose, 17 nos of toilets with septic tank & 17 nos of bathrooms have been provided at the labour camp. Municipal solid waste generated at labour camp is being handed over to local body on daily basis. Periodical medical checkup facilities have been provided to construction workers. Proper housekeeping & regular pest is being carried out.
ix	The solid waste generated should be properly collected and segregated dry/inert solid waste should be disposed-off to the approved sites for land filling after recovering recyclable material.	Part of excavated earth material is being reused for back feeling and plot leveling within the project site and remaining will be disposed to authorized landfill site as per local body
	5 5 11,111 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	approval.
х	Disposal of muck during construction phase should not create any adverse effect on the neighboring communities and be disposed taking the necessary	Part of excavated earth material is being reused for back feeling and plot leveling within the project site and remaining will be disposed to

CIN: U24100MH1968PTC014142

SI.	Stipulated clearance condition	Compliance status
No.	•	·
	precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.	authorized landfill site as per local body approval.
Xi	Arrangement shall be made that waste water and storm water do not get mixed.	 STP of capacity 295 KLD with MBR technology will be provided for the treatment of waste water. Also, separate storm water drains will be provided so that wastewater and storm water do not get mixed.
Xii	All the topsoil excavated during construction activities should be stored for use in horticulture / landscape development within the project site.	The project site is in industrial area prior to this project. Hence, the fertile topsoil generation is negligible.
xiii	Additional soil for leveling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.	❖ Part of excavated earth material is being reused for back feeling and plot leveling within the project site and remaining will be disposed to authorized landfill site as per local body approval.
Xiv	Green Belt Development shall be carried out considering CPCB guidelines including selection of plant	 ❖ We will ensure that RG area admeasuring 19,996.99 Sq. meters will be intact during future development also. ❖ Out of 2,900 Sq. meters RG area has been developed (Nursery area 1,500 in Sq. meters & Easement area 1,400 in Sq. meters outside of project area, area under MIDC Authority) ❖ 15 nos of tress are newly planted, and 43 trees are transplanted.
XV	Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.	 ❖ The use of ground water is prohibited under MIDC TTC area and no extraction of ground water for construction as well in operation purpose; also, we are not planning to withdraw ground water for any purpose in future. ❖ Groundwater accumulation was monitored in boreholes during and after completion of drilling activities, level of the groundwater table was observed at depth between 0.62 to 2.80 meter below exiting ground level in the boreholes. Seasonal and annual fluctuations in ground water levels can be expected to occur. ❖ Soil quality is being monitored. ❖ Please refer Annexure – 12 for Environmental Monitoring reports.

CIN: U24100MH1968PTC014142

SI.	Stipulated clearance condition	Compliance status
No.	Supulated clearance condition	Comphanice status
xvi	Construction spoils, including bituminous material and other hazardous materials must not be allowed to contaminate watercourses and the dumpsites for such material must be secured so that they should not leach into the ground water.	construction.
xvii	Any hazardous waste generated during construction phase should be disposed-off as per applicable rules and norms with necessary approvals of the MPCB.	No generation of hazardous waste during construction.
xviii	The diesel generator sets to be used during construction phase should be low Sulphur diesel type and should conform to Environments (Protection) Rules prescribed for air and noise emission standards.	DG set of capacity 320 kVA has been provided for construction purpose.
xix	The diesel required for operating DG sets shall be stored in underground tanks and if required, clearance from concern authority shall be taken.	DG set of capacity 320 kVA has been provided for construction purpose.
xx	Vehicles hired for bringing construction material to the site should be in good condition and should have a pollution check certificate and should conform to applicable air and noise emission standards and should be operated only during nonpeak hours.	 Vehicles with valid PUC certificate is being allowed during construction to enter the project site. Vehicles operated only during non-peak hours. PUC records is being maintained at security gate. Please refer Annexure – 13 for PUC Certificate.
xxi	Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.	 Ambient air and Noise levels monitoring is being carried out. Please refer Annexure – 12 for Environmental Monitoring reports.
xxii	Fly ash should be used as building material in the construction as per the provisions of Fly Ash Notification of September 1999 and amended as on 27th August, 2003. (The above condition is applicable only if the project site is located within the 100Km of Thermal Power Stations).	Cement containing Fly Ash of 2,643.00 MT is being used in building construction.
xxiii	Ready mixed concrete must be used in building construction.	 Ready Mixed Concrete is being used in building construction. OPC 53 grade cement is being used in building construction.

CIN: U24100MH1968PTC014142

SI.		
No.	Stipulated clearance condition	Compliance status
xxiv	Storm water control and its re-use as per CGWB and BIS standards for various applications.	 Storm water drains will be provided. Storm water collected through the storm water drains of adequate capacity will be discharged into the external drain. Rainwater from terrace area will be collected in 02 nos of Rain water harvesting tank of total capacity 200 KL will be provided.
xxv	Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices referred.	Ready Mixed Concrete is being used in building construction.
xxvi	The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.	 ❖ The use of ground water is prohibited under MIDC TTC area and no extraction of ground water for construction as well in operation purpose; also, we are not planning to withdraw ground water for any purpose in future. ❖ Groundwater accumulation was monitored in boreholes during and after completion of drilling activities, level of the groundwater table was observed at depth between 0.62 to 2.80 meter below exiting ground level in the boreholes. Seasonal and annual fluctuations in ground water levels can be expected to occur. ❖ Soil quality is being monitored. ❖ Please refer Annexure – 12 for Environmental Monitoring reports.
xxvii	The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Discharge of this unused treated affluent, if any should be discharge in the sewer line. Treated effluent emanating from STP shall be recycled/refused to the maximum extent possible. Discharge of this unused treated affluent, if any should be discharge in the sewer line. Treatment of 100% gray water by decentralized treatment should be done. Necessary measures should be made to mitigate the odor problem from STP.	 STP of capacity 295 KLD with MBR technology will be provided for the treatment of waste water. Treated sewage will be reused for flushing & gardening to reduce freshwater demand.
xxviii	Permission to draw ground water and construction of basement if any shall be obtained from the competent Authority prior to	❖ The use of ground water is prohibited under MIDC TTC area and no extraction of ground water for construction purposes also we are

CIN: U24100MH1968PTC014142

SI.		
No.	Stipulated clearance condition	Compliance status
xxix	construction/operation of the project Separation of gray and black water should be done	not planning to withdraw ground water for any purpose in future. Hence, permission from CGWA is not applicable. Dual plumbing system will be provided.
	by the use of dual plumbing line for separation of gray and black water.	
xxx	Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor-based control.	Low flow fixtures will be provided for toilets and showers.
xxxi	Use of glass may be reduced up to 40% to reduce the electricity consumption and load on air conditioning. If necessary, use high quality double glass with special reflective coating in windows.	High quality double glazed and high- performance glasses will be provided in building to ensure reduction in electricity consumption.
xxxii	Roof should meet prescriptive requirement as per Energy Conservation Building Code by using appropriate thermal insulation material to fulfill requirement.	❖ Agreed to comply with.
xxxiii	Energy conservation measures like installation of CFLs /TFLs for the lighting the areas outside the building should be integral part of the project design and should be in place before project commissioning. Use CFLs and TFLs should be properly collected and disposed-off/sent for recycling as per the prevailing guidelines/rules of the regulatory authority to avoid mercury contamination. Use of solar panels may be done to the extent possible like installing solar streetlights, common solar water heaters system. Project proponent should install, after checking feasibility, solar plus hybrid non-conventional energy source as source of energy.	Following Energy conservation measures will be implemented. ❖ Use of LED lights for internal lighting. ❖ Use of LED lights for external lighting. ❖ Use of energy efficient pumps as per ECBC Guidelines. ❖ Use of high COP chiller as per ECBC Guidelines. ❖ Use of low losses transformers as per ECBC Guidelines. ❖ Solar PV cells with installed capacity of 285 KW.
xxxiv	Diesel power generating sets proposed as source of backup power for elevators and common area illumination during operation phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low Sulphur diesel. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.	❖ CPCB approved enclosed type 3 nos of DG sets of capacity 1500 KVA each will be provided and will only be used in case of power failure.

CIN: U24100MH1968PTC014142

SI.	Chinulated eleganese condition	Comulianes status
No.	Stipulated clearance condition	Compliance status
xxxv	Noise should be controlled to ensure that it does not exceed the prescribed standards. During nighttime the noise levels measured at the boundary of the building shall be restricted to the permissible levels to comply with the prevalent regulations.	 We will ensure that RG area admeasuring 19,996.99 Sq. meters will be intact during future development also. Out of 2,900 Sq. meters RG area has been developed (Nursery area 1,500 in Sq. meters & Easement area 1,400 in Sq. meters outside of project area, area under MIDC Authority) 15 nos of tress are newly planted, and 43 trees are transplanted. Also, CPCB approved and acoustic enclose type DG sets have been provided.
xxxvi	Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized, and no public space should be utilized.	 Public road and public areas are not being used for project activity purpose and are free for smooth traffic movement. Provision is being made for adequate parking facilities within the project site.
xxxvii	Opaque wall should meet prescriptive requirement as per Energy Conservation Building Code, which is proposed to be mandatory for all air-conditioned spaces while it is aspiration for non-air-conditioned spaces by use of appropriate thermal insulation material to fulfill requirement.	Agreed to comply with.
xxxviii	The building should have adequate distance between them to allow movement of fresh air and passage of natural light, air and ventilation.	❖ Agreed to comply with.
xxxix	Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings.	Regular supervision of the above measures is being monitored by Project Manager & Mr. Ravi Prakash Sharma, (EHS) Officer and Mr. Yuvraj Sulke, (Safety Manager) for Nyati Engineers & Consultants Pvt. Ltd. (contractor)
хI	Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining Env clearance.	 Obtained Environmental clearance from SEIAA, Govt. of Maharashtra vide EC letter no. SEIAA-EC-0000002300, dated: 15/01/2020. Pease refer Annexure – 14 for Environmental Clearance.
Xli	Six monthly monitoring reports should be submitted to the RO MoEF, Bhopal with copy to this department and MPCB.	Six monthly monitoring reports are being submitted.
Xlii	Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. As agreed during the SEIAA meeting, PP to explore possibility	 STP of capacity 295 KLD with MBR technology will be provided for the treatment of waste water. Treated sewage will be used for flushing &

CIN: U24100MH1968PTC014142

Stipulated clearance condition	Compliance status
of utilizing excess treated water in the adjacent area for gardening before discharging it into sewer line No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement in Para 2. Prior certification from appropriate authority shall be obtained.	 gardening to reduce fresh water demand. ❖ OWC will be providing of capacity 750 Kgs/day automatic heater based to treat biodegradable waste. ❖ We will ensure that RG area admeasuring 19,996.99 Sq. meters will be intact during future development also. ❖ Out of 2,900 Sq. meters RG area has been developed (Nursery area 1,500 in Sq. meters & Easement area 1,400 in Sq. meters outside of project area, area under MIDC Authority) ❖ 15 nos of tress are newly planted, and 43 trees are transplanted.
Wet garbage should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. Local authority should ensure this.	OWC will be providing of capacity 750 KG/day automatic heater based to treat biodegradable waste.
Local body should ensure that no occupation certification is issued prior to operation of STP/MSW site etc. with due permission of MPCB.	 ❖ STP of capacity 295 KLD with MBR technology will be provided for the treatment of waste water. ❖ Treated sewage will be used for flushing & gardening to reduce fresh water demand. ❖ OWC will be providing of capacity 750 Kgs/day automatic heater based to treat biodegradable waste. ❖ We will ensure that RG area admeasuring 19,996.99 Sq. meters will be intact during future development also. ❖ Out of 2,900 Sq. meters RG area has been developed (Nursery area 1,500 in Sq. meters & Easement area 1,400 in Sq. meters outside of project area, area under MIDC Authority) ❖ 15 nos of tress are newly planted, and 43 trees are transplanted.
A complete set of all the documents submitted to Department should be forwarded to the Local authority and MPCB.	 A complete set of all the documents has been submitted to MPCB with the consent to establish application.
In the case of any change(s) in the scope of the project, the project would require a fresh appraisal by this Department.	Noted.
	of utilizing excess treated water in the adjacent area for gardening before discharging it into sewer line No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement in Para 2. Prior certification from appropriate authority shall be obtained. Wet garbage should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. Local authority should ensure this. Local body should ensure that no occupation certification is issued prior to operation of STP/MSW site etc. with due permission of MPCB. A complete set of all the documents submitted to Department should be forwarded to the Local authority and MPCB. In the case of any change(s) in the scope of the project, the project would require a fresh appraisal

CIN: U24100MH1968PTC014142

SI. No.	Stipulated clearance condition	Compliance status
Xlvii	A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.	 A separate Environment Management Cell with qualified staff has been appointed for implementation of the stipulated Environmental safeguards under Project Manager & Mr. Ravi Prakash Sharma, (EHS) Officer. Also, Mr. Yuvraj Sulke, (Safety Manager) for Nyati Engineers & Consultants Pvt. Ltd. (contractor)
Xlviii	Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. This cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes and year-wise expenditure should reported to the MPCB.	Separate funds have been allocated for implementation of Environmental Protection Measures; During construction phase; ❖ Rs. 10.43 Lakhs have been allocated for the entire construction period. During operation phase; ❖ Capital cost: Rs. 392.98 Lakhs and ❖ O & M cost: Rs. 15.82 Lakhs / Annum.
Xlix	The project management shall advertise at least in two local newspapers widely circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at Website at http://ec.maharashtra.gov.in.	 After getting Environmental clearance for the project, we published public notice in local Marathi (Navshakti) & English (The Free Press Journal) newspapers. Pease refer Annexure – 15 for Advertisement Copy.
ı	Project management should submit half yearly compliance reports in respect of the stipulated prior environment clearance terms and conditions in hard & soft copies to the MPCB & this department, on 1 st June & 1st December of each calendar year.	 Submitting six monthly compliance reports to; RO, MPCB, CBD, Belapur. RO, CPCB, Pune. RO, MoEF & CC, Nagpur. Environment Department, Mantralaya.
li	A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.	❖ A copy of the Environmental clearance letter is submitted to MIDC.

CIN: U24100MH1968PTC014142

SI.	T				
No.	Stipulated clearance condition	Compliance status			
lii	The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM. SO2, NOx (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company.	Six monthly compliance status reports are being submitted periodically and also criteria of pollutant levels will be displayed at the main gate of project site.			
liii	The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.	 Submitting six monthly compliance reports to; RO, MPCB, CBD, Belapur. RO, CPCB, Pune. RO, MoEF & CC, Nagpur. Environment Department, Mantralaya. 			
lix	The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the RO of MoEF by e-mail.	Environmental Statement (Form-V) for the FY 2022-23 has been submitted on MPCB Web Portal.			
4.	The environmental clearance is being issued without prejudice to the action initiated under EP Act or any court case pending in the court of law and it does not mean that project proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP Act.	Noted.			

CIN: U24100MH1968PTC014142

SI.	Stinulated clearance condition	Compliance status
No.	Stipulated clearance condition	Compliance status
5.	In case of submission of false document and non-compliance of stipulated conditions, Authority/Environment Department will revoke or suspend the Environmental Clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.	Noted.
6.	The Environment department reserves the right to add any stringent condition or to revoke the clearance if conditions stipulated are not implemented to the satisfaction of the department or for that matter, for any other administrative reason.	Noted.
7.	Validity of Environment Clearance: The environmental clearance accorded shall be valid as per EIA Notification, 2006, and amendments by MoEF & CC Notification dated 29th April, 2015.	Noted.
8.	In case of any deviation or alteration in the project proposed from those submitted to this department for clearance, a fresh reference should be made to the department to assess the adequacy of the condition (s) imposed and to incorporate additional environmental protection measures required, if any.	Noted.
9.	The above stipulations would be enforced among others under the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and rules there under, Hazardous Wastes (Management and Handling) Rules, 1989 and its amendments, the public Liability Insurance Act, 1991 and its amendments.	Noted.
10.	Any appeal against this environmental clearance shall lie with the National Green Tribunal (Western Zone Bench, Pune), New Administrative Building, 1stFloor, D-, Wing, Opposite Council Hall, Pune, if preferred, within 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.	❖ Noted.

CIN: U24100MH1968PTC014142

Registered Office: E Block, Voltas Premises, T B Kadam Marg, Chinchpokli, Mumbai 400 033 Tel: +91 22 6661 4444 • Fax: 91 22 6661 4452 • E-mail: trilsec@tata.com

Compliance as per Monitoring the Implementation of Environmental Safeguards Ministry of

Environment, Forests & Climate Change Regional Office (WCZ), Nagpur

Monitoring Report

DATA SHEET

1.	Project type: River - valley/ Mining / Industry / Thermal / Nuclear / Other (specify)			Construction Project.		
2.	Name of the project		:	Proposed 'Intellion IT Park, at plot no. 23, 23(pt), 24 & 24(pt), TTC Industrial Area, Thane-Belapur Road, Mahape MIDC, Mahape, Navi Mumbai. Maharashtra.		
3.	Clearance letter (s) / OM No. and Date		:	Obtained Environmental clearance from SEIAA, Govt. of Maharashtra vide EC letter no. SEIAA-EC- 0000002300, dated: 15/01/2020.		
4.	Locat	tion				
	a.	District (s)	:	Thane.		
	b.	State (s)	:	Maharashtra.		
	C.	Location		Ghansoli, Navi Mumbai.		
	d.	Latitude/ Longitude	:	Latitude : 19° 06 ' 59.45" N		
				Longitude: 73° 00'42.47" E		
5.	Address for correspondence					
	a. Address of Concerned Project Chief : Engineer (with pin code & Telephone / telex / fax numbers)		:	Mr. Sandeep Kolge, (Project Manager) M/s. Industrial Minerals & Chemical Company Pvt. Ltd. Proposed 'Intellion IT Park, at plot no. 23, 23(pt), 24 & 24(pt), TTC Industrial Area, Thane-Belapur Road, Mahape MIDC, Mahape, Navi Mumbai. Maharashtra. Email ID: sandeepkolge@tatarealty.in, Contact no: 9820991449		
	b.	Address of Executive Project: Engineer/Manager (with pin code / Fax numbers)	:	Mr. Saikumar Khot, (Project Engineer) M/s. Industrial Minerals & Chemical Company Pvt. Ltd. Proposed 'Intellion IT Park, at plot no. 23, 23(pt), 24 & 24(pt), TTC Industrial Area, Thane-Belapur Road, Mahape MIDC, Mahape, Navi Mumbai. Maharashtra. Email ID: saikumarkhot@tatarealty.in, Contact no: 9869207189		

CIN: U24100MH1968PTC014142


6.	. Salient features					
	a.	of the project	:	 FSI area: 38,208.74 Sq. meters Non-FSI area: 26,825.01 Sq. meters Total BUA area: 65,033.75 Sq. meters 		
	b.	of the environmental management plans	••	Separate funds have been allocated for implementation of Environmental Protection Measures; During construction phase; ❖ Rs. 10.43 Lakhs have been allocated for the entire construction period. During operation phase; ❖ Capital cost: Rs. 392.98 Lakhs and ❖ O & M cost: Rs. 15.82 Lakhs / Annum.		
7.	Break	cup of the project area				
	a.	submergence area forest & non-forest	:	Not Applicable. Project comes under Mahape MIDC, TTC Industrial		
	b.	Others	:	area, Navi Mumbai.		
8.	with dwell both	enumeration of Those losing houses/ ling units Only agricultural land only, Dwelling units & agricultural Land & less laborers / artisan.	tural land only,			
	a.	SC, ST/Adivasis	:	Not Applicable.		
	b.	Others (Please indicate whether these Figures are based on any scientific and systematic survey carried out Or only provisional figures, it a Survey is carried out give details And years of survey)	:	Not Applicable.		
9.	Finan	cial details				
	a.	Project cost as originally planned an reference:	d s	subsequent revised estimates and the year of price		
	1.	Total Cost of the Project	:	Rs. 3000,000,000/-		
	b.	Allocation made for environ-mental management plans with item wise and year wise Break-up.	:	Separate funds have been allocated for implementation of Environmental Protection Measures; During construction phase; ❖ Rs. 10.43 Lakhs have been allocated for the entire construction period.		
				During operation phase; ❖ Capital cost: Rs. 392.98 Lakhs and ❖ O & M cost: Rs. 15.82 Lakhs / Annum.		

CIN: U24100MH1968PTC014142

	c.	Benefit cost ratio / Internal rate of	:			
		Return and the year of assessment.				
	d.	Whether (c) includes the Cost of	:			
		environmental management as shown				
		in the above.				
	e.	Actual expenditure incurred on the	:	Rs. 70.08 Cr.		
		project so far.				
	f.	Actual expenditure incurred on the	:	Rs. 0.79 Cr.		
		environmental management plans so				
		far				
10.	Fore	st land requirement				
	a.	The status of approval for diversion of	:	Not Applicable.		
		forest land for non-forestry use.				
	b.	The status of clearing felling	:	Not Applicable.		
	c.	The status of compensatory	:	Not Applicable.		
		afforestation, it any				
	d.	Comments on the viability &	:	Not Applicable.		
		sustainability of compensatory				
		afforestation program in the light of				
		actual field experience so far.				
11	The	tatus of close falling in one forest succession	_	Nist Assistantia		
11.		status of clear felling in non-forest areas	:	Not Applicable.		
	1	as submergence area of reservoir,				
		oach roads), it any with quantitative mation.				
	IIIIOI	mation.				
12.	Statu	us of construction	:	Current status of construction work completed as of		
				September 2023 is 38,480 Sq. meters.		
				• 1 st , 2 nd , 3 rd , 4 th , 5 th and 6 th Slab RCC works		
				100% Completed.		
				• 7 th Slab RCC works 84% completed and 8 th Slab		
				RCC works 67% completed.		
				 Blockwork and plaster work in progress at 		
				Ground + 4 Parking floors.		
				MEP works in progress at Ground + 4 parking		
				floors.		

CIN: U24100MH1968PTC014142

		Data of annual and		27/12/2021 (Astroll)
	a.	Date of commencement	:	27/12/2021 (Actual)
		(Actual and/or planned)		
				Site preparation work started on 27/12/2021 based on
				commencement certificate received.
	b.	Date of completion		January 2027 (Planned)
	J.		•	January 2027 (Flaimeu)
		(Actual and/or planned)		
13.	Reaso	ons for the delay if the Project is yet to	:	
	start.			
14.	Dates	s of site visits		
14.	Dates	of site visits		
			_	
	a.	The dates on which the project was	:	
		monitored by the Regional Office on		
		previous occasions, if any.		
}	b.	Date of site visit for this monitoring		
	J.	_	•	
		report.		
15.	Detai	ls of correspondence with Project	:	
	autho	prities for obtaining Action		
	nlans	/information on Status of compliance		
	-	feguards Other than the routine letters		
		_		
	tor Lo	ogistic support for site visits.		
	(The first monitoring report may contain the			
	details of all the Letters issued so far, but the			
		reports may cover only the Letters		
	issue	d subsequently.)		




TYPICAL - 1, 2, 4, 5, 6, 8 FLOOR PLAN



Polygon	Area
A-Block	5033.60
L1	6.69
L2	6.69
L3	6.69
L4	6.69
L5	6.69
L6	6.69
L7	6.69
L8	6.69
L9	7.50
L10	7.50
V1	3.48
V2	2.92
V3	3.48
V4	2.92
V5	0.80
V6	0.35
V7	1.28
V8	0.96
V9	0.80
V10	1.12
V10 V11	0.96
V12	7.60
V13	22.08
V14	22.08
V14 V15	1.12
V15 V16	1.12
V17	
V17 V18	0.96 1.36
V19	
	0.76
V20	0.90
V21	1.08
V22	0.90
V23	1.28
V24	0.96
V25	0.80
V26	2.84
V27	2.84
SS1	10.58
SS2	9.40
SS3	71.99
SS4	71.99
LL1	43.92
LL2	10.25
LL3	10.25
S1	28.60
S2	29.82
S3	29.82
Total	4560.57





OWNER'S NAME	<u>:</u>				OWNER'S SIGN:
M/S. Industrial	Minerals 8	Chemica	Co.Pvt.L	.td	
, , ,					
PROJECT:					
Plot No. : 23an	d24		Survey	No. :	
Ward : Than	е		Village	: -	
INDUSTRIAL ARE	EA: T.T.C.				
ARCHITECT:	ARCHITECT'S SIG				
Bhaskar Sambh Plot-29, 3rd Floor					
to:	JOB NO.	DRG.NO.	SCALE	DRAWN E	BY CHECKED B
N					
	INWARD I	/521/201 56522	DATE	17-09-2019	
V					


STAMP OF APPROVAL

Digitally signed by Maruti S Kalkutaki
DN: c=IN, o=Government Of
Maharashtra, ou=Maharashtra Industrial
Development Corporation,
postalCode=400710, st=Maharashtra,
2.5.4.20=0b26d65d66766c78254f655232
e7bf41d358b6b50b8d394cb815f78ee5a
7f536,
2.5.4.45=032100281587D47BA1475D865
AF5B63889DEB4527D210A364B0128E2D

A6EFE5AEAD387,

serialNumber=e6228485b2c6184491b58 784f78ca1de0837059ceef2d9acd3f861f6 909e6a20, cn=Maruti S Kalkutaki Date: 2019.10.11 16:51:04 +05'30'

BUILDING: A (BUILDING)



OWNER'S NAME:

MIS, Industrial Minerals & Chemical Co,Pvt,Ltd
...

PROJECT:

Plot No.: 23and24 Survey No.:
Ward: Thane Village:
INDUSTRIAL AREA: T.T.C.
ARCHITECTS SIGN
Blaskar Sambhshiv Yamsanwar
Plot-29, 3rd Floor, Amba Bhavan, Sion Circle, Sion (E)

JOB NO. DRG,NO. SCALE DRAWN BY CHECKED BY
1:100

INWARD NO SWC144521201 DATE 17-09-2019

KEY NO.: *§ SHEET NO. 8 /12

This is a system generated drawing as per the soft copy submitted by the Architect/ License Engineer

STAMP OF APPROVAL

Digitally signed by Maruti S Kalkutaki
DN: c=IN, o=Government Of Maharashtra,

ou=Maharashtra Industrial Development

Corporation, postalCode=400710,

6a20, cn=Maruti S Kalkutaki Date: 2019.10.11 16:52:20 +05'30'

BUILDING: A (BUILDING)

st=Maharashtra,
2.5.4.20=0b26d65d66766c78254f655232e7
bf41d358b6b50b8d394cb815f78ee5a7f536,
2.5.4.45=032100281587D47BA1475D865AF
5B63889DEB4527D210A364B0128E2DA6EF
E5AEAD387,
serialNumber=e6228485b2c6184491b5878
4f78ca1de0837059ceef2d9acd3f861f6909e
6a20_cp=Maruti_S_Kalkutaki

CIN: U24100MH1968PTC014142

Registered Office: E Block, Voltas Premises, T B Kadam Marg, Chinchpokli, Mumbai 400 033 Tel: +91 22 6661 4444 • Fax: 91 22 6661 4452 • E-mail: trilsec@tata.com

12th December 2019.

To, UPS Singh - Chief Project Manager National High-Speed Rail Corporation Ltd 1105 & 1106, 11th Floor, Universal Majestic, P.L. Lokhande Marg, Chembur West, Mumbai-400043

Subject: Mumbai – Ahmedabad National High-Speed Rail Corridor Project passing through our land situated at plot no.23, 23 (pt), 24 and 24 (pt), TTC Industrial Area, Mahape MIDC.

Ref: Correspondence letters:

- 1. Possession receipt dated 7th October 2019 for handing over of land
- 2. MIDC approved plan dated 10th October 2019

Dear Sir,

- Industrial Minerals and Chemical Company Pvt. Ltd., (IMCC), is a private limited company having its registered office at "E" Block, Voltas Premises, T B Kadam Road, Chinchpokali, Mumbai 400 033 whose present shareholding is held by Tata Realty and Infrastructure Limited and Actis Treit Holdings No. 2 (Singapore) Private Limited.
- 2. IMCC is the lessee of all those pieces or parcels of land owned by Maharashtra Industrial and Development Corporation ("MIDC") bearing Plot Nos.23, 23 (Part), 24 and 24 (Part), all situated at Village Savali, Taluka Thane, MIDC Trans Thane Creek Zone, Navi Mumbai, hereinafter collectively referred to as "the said Property"
- 3. We are in receipt of letter from NHSRCL dated 5th March 2019 requesting to handover land for the development of Bullet train. Accordingly, we have handed over the land to NHSRCL on 7th October 2019.
- 4. MIDC has approved the first building plan on 10th October 2019 for the development of IT Park.
- Apart from the Building approvals, one of the crucial approvals for the Project is to obtain Environment Clearance. During the hearing scheduled before SEAC – II on 14th November 2019, it was suggested by the Committee to obtain <u>NOC</u> from NHSRCL.

6. In lieu of the same, we hereby attach the following:



- a. Approved Building plan from MIDC
- b. MOM issued by SEAC II for the 120th Meeting held on 14th November 2019.

We request for an appointment to appraise you the details of the Project.

Thanking You,

Yours faithfully,

For Industrial Minerals and Chemical Co. Pvt Limited

Chemica/

Authorized Signatory

Encl: as above



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

Industrial Minerals and Chemical Company Pvt. Ltd.

3rd Floor, Amba Bhavan, Plot No. 29, Sion Circle, Sion (E), Mumbai 400 022 Mumbai Maharashtra 400022 Date: 10-08-2018

Valid Upto: 09-08-2026

No Objection Certificate for Height Clearance

- 1. This NOC is issued by Airports Authority of India (AAI) in pursuance of responsibility conferred by and as per the provisions of Govt. of India (Ministry of Civil Aviation) order GSR751 (E) dated 30th Sep. 2015 for Safe and Regular Aircraft Operations.
- 2. This office has no objection to the construction of the proposed structure as per the following details:

SNCR/WEST/B/062218/315236
B. S. Yamsanwar
Plot No. 23, 23 (Pt), 24, 24 (Pt),TTC Industrial Area/ MIDC/ Mahape,Navi Mumbai,Maharashtra
73 00 31.79-19 06 54.61, 73 00 33.35-19 06 50.40, 73 00 35.36-19 06 51.01, 73 00 36.00-19 06 49.03, 73 00 44.80-19 06 59.90, 73 01 00.77-19 07 02.96, 73 01 02.86-19 06 54.13
20.975 M ~
162.97M _

- *As provided by applicant
- 3. This NOC is subject to the terms and conditions as given below:
- a. Permissible Top elevation has been issued on the basis of Site coordinates and Site Elevation submitted by Applicant. AAI neither owns the responsibility nor authenticates the correctness of the site coordinates & site elevation provided by the applicant. If at any stage it is established that the actual data is different, this NOC will stand null and void and action will be taken as per law. The office in-charge of the concerned aerodrome may initiate action under the Aircraft (Demolition of Obstruction caused by Buildings and Trees etc.) Rules, 1994"
- b. The Site coordinates as provided by the applicant in the NOC application has been plotted on the street view map and satellite map as shown in ANNEXURE. Applicant/Owner ensure that the plotted coordinates corresponds to his/her site.In case of any discrepancy, Designated Officer shall be requested for cancellation of the NOC
- c. The Structure height (including any superstructure) shall be calculated by subtracting the Site elevation in AMSL from the Permissible Top Elevation in AMSL i.e. Maximum Structure Height = Permissible Top Elevation minus (-) Site Elevation.
- d. The issue of the 'NOC' is further subject to the provisions of Section 9-A of the Indian Aircraft Act, 1934 and any notifications issued there under from time to time including the Aircraft (Demolition of Obstruction caused by Buildings and Trees etc.) Rules, 1994.

क्षेत्रीय मुख्यालय पश्चिमी क्षेत्र पोर्टा केबिंस, नई एयरपोर्ट कॉलोनी, हनुमान रोड के सामने, विलेपारले ईस्ट मुंबई- 400099 दूरभाष संख्या : 91-22-28300606

Regional headquarter Western, Region, Porta Cabins, New Airport Colony, Opposite Hanuman Road, Vile Parle East
Mumbai-400099 Tel. no. 91-22-28300606



भारतीय विमानपत्तन प्राधिकरण AIRPORTS AUTHORITY OF INDIA

- e. No radio/TV Antenna, lighting arresters, staircase, Mumtee, Overhead water tank and attachments of fixtures of any kind shall project above the Permissible Top Elevation of 162.97M, as indicated in para 2.
- f. Only use of oil fired or electric fired furnace is permissible, within 8 KM of the Aerodrome Reference Point,
- g. The certificate is valid for a period of 8 years from the date of its issue. One time revalidation without assessment may be allowed. provided construction work has commenced, subject to the condition that such request shall be made within the validity period of the NOC and the delay is due to circumstances which are beyond the control of the developer.
- h. No light or a combination of lights which by reason of its intensity, configuration or colour may cause confusion with the aeronautical ground lights of the Airport shall be installed at the site at any time, during or after the construction of the building. No activity shall be allowed which may affect the safe operations of flights
- i. The applicant will not complain/claim compensation against aircraft noise, vibrations, damages etc. caused by aircraft operations at or in the vicinity of the airport.
- j. Day markings & night lighting with secondary power supply shall be provided as per the guidelines specified in chapter 6 and appendix 6 of Civil Aviation Requirement Series B Part I Section 4, available on DGCA India website: www.dgca.nic.in
- k. The applicant is responsible to obtain all other statutory clearances from the concerned authorities including the approval of building plans. This NOC for height clearances is to ensure the safe and regular aircraft operations and shall not be used as document for any other purpose/claim whatsoever, including ownership of land etc.
- 1. This NOC has been issued w.r.t. the Civil Airports. Applicant needs to seek separate NOC from Defence, if the site lies within their jurisdiction.
- m. In case of any discrepancy/interpretation of NOC letter, English version shall be valid.
- n. In case of any dispute w.r.t site elevation and/or AGL height, top elevation in AMSL shall prevail.

Chairman NOC Committee

Region Name: WEST

Address: General Manager

Airports Authority of India, Regional Headquarter, Western Region, Opp. Parsiwada, Sahar Road, Vale

Parle (E) MUMBAI-400099

Email ID: nocwr@aai.aero

Contact No: 022-28300656

भारतीय विमानपत्तन प्राधिकरण/ Airports Authority of India मुम्बई / Mumbai - 400 099

Name / Designation / Sign with Date 10/08/18

Verified By:

Prepared By:

Distance From Nearest Airport And Bearing

Airport Name	Distance (Meters) from Bearing (Degree) the Nearest Runway			
Juhu	18528.98	84.11		
Navi Mumbai	14467.49	334.77		
Santa Cruz	15262.7	80.42		

Street view



Satellite View



June 22 2018

0 0.03 0.04 0.04 0.2 mm as year 0.2

MAHARASHTRA INDUSTRIAL DEVELOPMENT CORPORATION

(A Government of Maharashtra Undertaking)

: "Udyog Sarthi", Mahakali Caves Road, **HEAD OFFICE**

Andheri (E), Mumbai - 400 093.

Tele: (022) 26870052/54/27/73 Fax: (022) 26871587

PRINCIPAL OFFICE: 4,4 (A), 12th Floor, World Trade Centre, Complex-1,

Cuffe Parade, Mumbai - 400 005

Tele: (022) 22151451/52/53 Fax: (022) 22188203

No, MIDC/Fire/D-15182 Date: 25/09/2019

M/s, Industrial Minerals & Chemical Co. Pvt. Ltd., Plot No: 23, 23 (PT.), 24 & 24 (PT.) MIDC TTC Indl. Area.

Sub: Grant of "Provisional No-Objection Certificate" to your

proposed construction on Plot No, 23, 23 (PT.), 24 & 24 (PT.) at

MIDC, TTC Indl. Area.

Your application vide no; SWC/14/521/20190909/656522. Ref:

Dear Sir.

This has reference to the above this office has "No Objection (Provisional)" for your proposed construction of IT building on plot no. 23, 23 (PT.), 24 & 24 (PT.) at MIDC, TTC Indl. Area. The details of the constructions as per the drawing submitted by you are as mapped under your BPAMS application. The plot area of the co. is 192320.00 Sq mtr. The proposed built up area is 38208.74 Sq. Mtr. The height of the proposed structure is 51.20 mtr. The area wise details of each floor are as under:-

Floor Name	Proposed FSI Area Ind.	Stair	Lift	Lift Lobby
Eighth Floor (Office Area)	4560.58	88.24	68.50	64.42
Seventh Floor (Office Area)	4271.39	88.24	68.50	64.42
Sixth Floor (Office Area)	4560.58	88.24	68.50	64.42
Fifth Floor (Office Area)	4560.58	88.24	68.50	64.42
Fourth Floor (Office Area)	4560.58	88.24	68.50	64.42
Third Floor (Office Area)	4271.39	88.24	68.50	64.42
Second Floor (Office Area)	4560.58	88.24	68.50	64.42
First Floor (Office Area)	4560.58	88.24	68.50	64.42
Podium4 Floor (Parking Area) Free of FSI	59.40	0.00	0.00	0.00
Podium3 Floor (Parking Area) Free of FSI	59.40	0.00	0.00	0.00
Podium2 Floor (Parking Area) Free of FSI	59.33	0.00	0.00	0.00
Podium1 Floor (Parking Area) Free of FSI	24.67	0.00	0.00	0.00
Stilt Floor (Restaurant, Gymnasium, Pump				
Room, Elec Panel Room, Transformer Room &	2099.72	58.42	81.07	54.17
Substation and other Utilities)				
Grand Total :	38208.74	764.34	629.10	569.52

• The occupant load should not exceed in any case as prescribed in Table - 3 of NBC 2016 part IV.

This N.O.C. is valid subject to fulfillment of the following conditions:

- The plans of the proposed Construction of building adhering to the D.C. Rules of MIDC & National Building Code-2016 where necessary) should be approved by The Deputy Engineer, Mahape Sub-Division-I (Special Planning Authority).
- The drainage completion certificate & Occupation certificate should be obtained from Deputy Engineer, MIDC Mahape Sub-Division-I, The B.C.C. & D.C.C. shall be issued subject to "Final NO-Objection Certificate" from fire department.
- 3. Under Section 3 of Maharashtra Fire Prevention and Life Safety Measures Act, 2006 (hereinafter referred to as "said Act") The applicant (developer, owner, occupier by whatever name called) shall comply with all the Fire and Life Safety measures adhering to National Building Code of India, 2016 and as

- amended from time to time failing which it shall be treated as a violation of the said Act.
- 4. As per the provision as under: 10 of the said Act. No person other than the License Agency shall carry out the work of providing Fire Prevention and Life Safety Measures or performing. Such other related activities required to be carried out in any place or building or part thereof: A list of License Agency is available on Maharashtra Fire Services website www.mahafireservice.gov.in. No Licensed Agency or any other person claiming to be such Licensed Agency shall give a certificate under sub-section (3) of section 3 regarding the compliance of the fire prevention and life safety measures or maintenance thereof in good repair and efficient condition, without there being actual such compliance or maintenance.
- 5. **Under Section 11 of the said Act,** the fire service fees shall be assessed and the same shall be payable after serving the notice to that effect or prior to issue of the building completion certificate or occupancy certificate whichever is earlier.
- 6. **Under Section 45 of the said Act**, the owner/occupier or developer shall appoint Fire Officer/Officers and staff for taking adequate Fire and Life Safety Measures, qualifications and experience of such persons be got approved from the Chief Fire Officer & Fire Advisor, MIDC Fire Services.
- 7. Though certain conditions are stipulated from the said Act and the National Building Code of India, it is obligatory on part of the applicant that is developer, builder, occupier, owner, tenant, by what so ever named called to abide with the provisions of the said Act failing which it shall be actionable under the provisions of said act.
- 8. Proper roads in the premises should be provided for easy mobility of the Fire Brigade Appliance & Marginal spaces around the building should be kept free from obstructions & open to sky at all the time. Minimum marginal spaces should be confirming with **Table No.10 of D.C. Rules of MIDC, 2009.** The load bearing capacity of internal roads shall not be less than **45 Tons.**
- 9. All portable fire fighting equipments installed at various locations as per local hazard such as Co2-DCP, Foam as per **IS: 15683**, & it must be strictly confirming to relevant IS specification. It is recommended for every 100 Sq. Meter one fire extinguisher should be provided for electrical installation Co2 extinguisher of 4.5 Kg should be provided.
- 10. All the firefighting equipment shall be well maintained and should be easily accessible in case of emergency.
- 11. Emergency Telephone numbers like "Police", "Fire Brigade", "Hospital", "Doctors", and "Responsible persons of the office" should be displayed in Fire Control Room, Security Office and in Reception area.
- 12. It shall be ensured that security staff & every employee of the office, security are trained in handling **firefighting equipment & in fire fighting.**
- 13. The Fire Exit Drill or Evacuation Drill should be plan and instruction should be given to the staff minimum **four times in a year** and drill should be carried out **twice in a year**.
- 14. Cautionary boards such as "DANGER", "NO SMOKING", "EXIT", "FIRE ESCAPE", "EXTINGUISHER", "FIRE HYDRANT" etc. should be displayed on the strategic location to guide the occupants in case of emergency. The signs should be of florescent type and should glow in dark.
- 15. "On-Site" & "Off-Site" emergency plan shall be prepared & mock drills shall be conducted twice a year & instructions to every employee shall be given once in three months.
- 16. The use of combustible surface finishes on walls (including facade of the building) and ceiling affects the safety of the occupants of the building. Such finishes tend to spread the fire and even though the structural elements may be adequately fire resistant, serious danger to life may result. It is therefore, essential to have adequate precautions to minimize spread of flame on wall, façade of building and ceiling surfaces.
- 17. The finishing materials used for various purposes and décor shall be such that it shall not generate toxic fumes / smoke.
- 18. Automatic smoke venting facilities shall be provided for safe use of exits in windowless buildings.

- 19. Natural draft smoke venting shall utilize roof vents in walls at or near the ceiling level, such vents shall be normally open, or, if closed, shall be designed for automatic opening in case of fire, by release of smoke sensitive devices.
- 20. Where smoke venting facilities are installed for purposes of exit safety, these shall be adequate to prevent dangerous accumulation of smoke during the period of time necessary to evacuate the area served, using available exit facilities with a margin of safety to allow for unforeseen contingencies.
- 21. The fluorescent glow signs like "Staircase", "Extinguisher", "Fire Escape" "Hydrant Point", Manual Call Point" "Exit", "Lift" shall be installed on strategic locations in all common areas of the building like passages, Corridors etc.
- 22. Fire evacuation orders & exit map shall be provided in every floor & in lobbies of the buildings.
- 23. LPG banks should not be stored on upper floor for cooking etc. The kitchen for commercial purpose on uppers floors is not permitted.
- 24. The Glassing and facade other Glasses should have at least one hour fire resistance and should be UL approved and in accordance with NFPA requirements.
- 25. The glass faced should be protected with coating film so that in case of breaking of glass the glass can remain in it's place for some hours before replacement. This will reduce the risk of injuries to occupants and fire & rescue personal. In the event of blast the shock wave created which creates the damage to glass faced the use of film will help to reduce the damages due to glass breaking.
- 26. This being a very special type of building if any additional recommendations to be added or deleted depending upon the need of the fire safety requirement of buildings.
- 27. The Chief Fire Officer & Fire Advisor, M.I.D.C. reserves all right to modify the fire safety recommendations and it shall be responsibility of company authorities to maintained close liaison with fire department.
- 28. A high rise building during construction shall be provided with the following fire protection measures, which shall be maintained in good working condition at all times:
- 29. Dry riser of minimum 100 m.m. dia. Pipe with hydrant outlets on the floors constructed with a fire service inlet.
- 30. The use of combustible surface finishes on walls (including facade of the building) and ceiling affects the safety of the occupants of the building. Such finishes tend to spread the fire and even though the structural elements may be adequately fire resistant, serious danger to life may result. It is therefore, essential to have adequate precautions to minimize spread of flame on wall, façade of building and ceiling surfaces.
- 31. The finishing materials used for various purposes and décor shall be such that it shall not generate toxic fumes / smoke.
- 32. Automatic smoke venting facilities shall be provided for safe use of exits in windowless buildings.
- 33. Natural draft smoke venting shall utilize roof vents in walls at or near the ceiling level, such vents shall be normally open, or, if closed, shall be designed for automatic opening in case of fire, by release of smoke sensitive devices.
- 34. Where smoke venting facilities are installed for purposes of exit safety, these shall be adequate to prevent dangerous accumulation of smoke during the period of time necessary to evacuate the area served, using available exit facilities with a margin of safety to allow for unforeseen contingencies.
- 35. If the building or part of building is Sub-leased, sold to some other company then the prospective buyer / sub-leased must obtain "No Objection Certificate" form this office before occupying the building / floors. You are hereby informed to incorporate suitable clause to that effect in sub-lees agreement or agreement for sale.
- 36. Pressurization should be provided to the all the staircases and Lift Shaft's & Lift lobbies of the building. The mechanism for the pressurization shall act automatically with the fire alarm/ sprinkler system and it shall be possible to operate this mechanically also.

37. In future if the Company intends to carry out any expansion of the building, an approval of this department must be obtained before commencing proposed construction for revision of the Fire Fighting System recommendation as higher capacity of Pumps and Static water tank may be prescribed.

Standard Specifications and Regulations to be followed: -

- a. D.C. Rules of MIDC & Part-3 & 4 National Building Code: 2016,
- b. **IS: 3844** for installation and maintenance of internal fire hydrants and hose reels on premises.
- c. **IS: 2189** for selection, installation and maintenance of automatic fire detection and alarm system.
- d. **IS:** 15683 for selection, installation and maintenance of portable first aid fire extinguishers.
- e. IS: 9583: 1981 Emergency lighting units.
- f. IS 12456: 1988 Code of practice for fire protection of electronic data processing installation.
- g. IS 4963: 1987 Recommendations for buildings and facilities for physically handicapped.
- h. IS 3614 (Part I):1966 Specification for fire check doors.

Other Important Codes & Standards:-

- 1. <u>Code of practice for Fire Safety Buildings IS-1642 for Details of</u> Construction.
- 2. Code of Practice of Fire Safety of Buildings IS-1643- Exposure Hazard.
- 3. <u>Code of Practice of Fire Safety of Buildings IS-1644 Exit requirement and Personal Hazard.</u>
- 4. <u>IS: 15105 Design and installation of fixed automatic sprinkler fire</u> extinguishing system.
- 5. IS 9668: 1990 Code of practice for provision and maintenance of water supplies and fire fighting.
- 6. <u>IS 2175 : 1988 Specification for heat sensitive fire detectors for use in automatic fire alarm system.</u>
- 7. <u>IS 11360 : 1985 Specification for smoke detectors for use in automatic electrical fire alarm system.</u>
- 8. <u>IS 9457 : 1980 Safety colours and safety signs.</u>
- 9. IS 12349: 1988 Fire protection Safety sign
- 10. IS 12407: Graphic symbols for fire protection plan.

FIRE PREVENTION Passive Fire protection required.

Requirement and Provision: - The following passive fire protection systems will have to be followed and installed for the Life Safety of the building as per Part 3 & 4 of National Building Code 2005:-

Sr. No.	Clause Number	Description.
1.	Clause NO: 3.3.1 & 3.3.2	Fire Test General Requirement: Element / Component shall have the requisite fire resistance performance when tested in accordance with the accepted standards.
2.	Clause NO: C-9	Compartmentation: The building shall be suitably compartmentalized so that the fire & smoke remain confined to the area where the fire incident has occurred & does not spread to other part of the building.
3.	Clause NO: 4.10.5	Smoke Extraction System: The exhaust system may be continued, provided the construction of the ductwork & fans is such that it will not be rendered inoperable by hot gases & smoke & there is no danger of spread of smoke to other floors via the path of extraction system.
4.	Clause NO: 3.4.12.3	Smoke management: Where smoke venting facilities are installed for the purpose of exit safety these shall be adequate to prevent dangerous accumulation of smoke during the period of time necessary to evacuate the area served using available exit facilities, with margin of safety to allow for unforeseen contingencies.
5.	Clause NO: C-1.17	Fire rated ducts: Where the ducts passes through fire

	1	
		walls, the opening around the duct shall be sealed with fire resisting materials having the fire resistant rating of the compartment. Where the duct crosses the compartment which is fire rated for same fire rating. Depending on the services passing around the duct work, which may be affected in case of fire temperatures rising, the ducts shall be insulated
6.	Clause NO: C-1.12	Cable ducts: The electric distribution cables/wiring shall be laid in separate duct. The duct shall be sealed at every floor with non-combustible material having the same fire resistance as the fire rating of the duct.
7.	Clause NO: C-1.12 e	Fire rated ceilings: The exhaust system may be continued, provided the construction of the ductwork & fans is such that it will not be rendered inoperable by hot gases & smoke & there is no danger of spread of smoke to other floors via the path of extraction system.
8.	Clause NO: 3.3.3	Steel protection: Load bearing steel beams & columns of building having total covered area of 500Sq.Mtrs. and above shall be protected against failure collapse of structure in case of fire. This could be achieved by using appropriate methodology using suitable fire rated materials as per the accepted standards.
9.	Clause NO: 4.13	Fire escape enclosure: Fire towers shall be constructed of walls with a 2 hours fire rating without openings other than the exit doorway, with platforms, landings & balconies with the same fire rating of 2 Hours.
10.	Clause NO: C-1.4	Glazing: If glazing or glass bricks are used in a stair case shall have fire rating of minimum 2 hours.
11.	Clause NO: 3.4.19	Glazing: If glass is used as a façade for building it shall have minimum 1 hour fire rating.
12.	Clause NO: 3.4.8.3	Fire stopping: Every vertical opening between the floors of a building shall be suitably enclosed or protected as necessary to provide reasonable safety to the occupants while using the means of egress by preventing spread of fire, smoke or fumes through vertical openings from floor to floor, which will allow the occupants to complete their safe use of means of egress.
13.	Clause NO: 3.4.8.4	Fire Stopping: Openings in the walls or floors which are provided for the passage of all building services like cables, electrical wiring & telephone cables etc. Shall be protected by the enclosure in the form of Ducts/shafts with a fire resistance of not less than 2 Hours.
14.	Clause NO: C-1.9	Fire stopping service ducts & shafts: Service ducts & shafts shall be enclosed by walls of 2 hours & doors of 1 hour fire rating. All such ducts/shafts shall be properly sealed & fire stopped at all floors.
15.	Clause NO: C-1.12	Fire stopping cable ducts penetration: The electrical distribution cables/wiring shall be laid in separate duct. The duct shall be sealed at every floor with non-combustible materials having the same fire resistance as the fire rating of the cable duct.

Active Fire protection required for I.T. Building

Sr. No.	FIRE FIGHTING INSTALLATION	Requirements	Provision	Remarks
1.	Portable Fire	Required in	IS: 15683 &	Portable Fire Extinguisher should
	Extinguishers	all buildings	2190.	be installed confirming to IS 15683
		on each floor.		& other I.S. codes
2.	Hose Reel	Required at	At Various	On each floor in the Staircase
		prominent	strategic	landing for Fire Fighting. The first

Sr. No.	FIRE FIGHTING INSTALLATION	Requirements	Provision	Remarks
		places.	Locations.	aid hose reel shall be connected directly to riser/down comer main and diameter of the hose reel shall not be less than 19mm confirming to IS 884:1985
3.	Wet Risers & Down Comers	Required in entire Bldg.	In all staircases & fire escape staircases	Required to provide in the Staircase and Fire Escape Staircase. Landing of Valve should be installed confirming to IS:5290 .
4.	Court Yard Hydrant or Ring hydrant system around the building.	Required around the proposed building.	Hydrant point Delivery Hose Standard Bra 2871. The dis not be more	nlet connection should be provided. s should be provided with 2 Nos. of e confirming to IS-636 along with nch (Universal) confirming to IS-stance between 2 Hydrants should than 30 Mtrs. The guidelines Ilowed as per IS 3844:1989 & IS
5.	Manually Operated Fire Alarm System	Required in entire building	At every floor on strategic location	Manually Operated Fire Alarm should be provided; it should be connected to alternate power supply.
6.	Underground Static Storage Tank	Requ 2,00,000	0 liters	This water storage should be exclusively for Fire Fighting.
7.	Terrace Level Tank	Req 20,000	j uired D Ltrs.	For wet riser cum down comer. On each terrace of building
8.	Fire Pump	1 No. 4500 lp driven star 2 No. 180 lp driven joo 900 lpm eled Booster Pur terrace	ain pumps m Diesel nd by pump om electric ckey pump ctric driven np on every e tank.	Fire Fighting pumps shall be well maintained. A separate arrangement of pumping should be done for sprinkler system. All the fire pumps must be centrifugal pumps only
9.	Automatic smoke Detection System & Fire alarm system.	Required in ent all flo (If false contexceeding 800) above false System should	oors eiling voids mm of height Detection	Standards and guidelines given in IS-11360-1985 specification for Smoke Detectors for use in Automatic Electrical Fire Alarm system & IS 2189:2008 Selection, Installation and Maintenance of Automatic Fire-Detection and Alarm System should be followed.
10.	Automatic Sprinkler system.	Required in entire building at all floors and Fire Pump Room (If false ceiling voids exceeding 800mm of height above false ceiling sprinkler should be provided)		Separate Pumping arrangement should be provided for the Sprinkler system. Guidelines are given in IS 15105 Design and installation of Fixed Automatic sprinkler fire Extinguishing system
11.	Fire Doors	Required for all staircases. it should be self-closing Fire Doors should be proof all the statement of all the statement of		of 2 hrs. Fire Resistance Rating ovided in all buildings at the entrance aircases on all floors. Certification Competent Authority shall be submitted to this office for record.
12.	Manual Call Point	Required in Manual Call P		Point should be provided at aces in all buildings
13.	Emergency Lights	1		vacuation in case of emergency. e power backup.
14.	PA System with Talk Back Facility	Required	To guide the	occupants in case of emergency.

Sr. No.	FIRE FIGHTING INSTALLATION	Requirements	Provision	Remarks	
15.	Auto D.G. Backup	Required	Required for all fire safety systems.		
16.	Pressurization	Required	In all staircase	e, Lobbies & Lift shaft in entire Bldg.	
17.	Sign Indicators for all fire safety, safe evacuation of occupants in case of emergency signs	Required at Prominent Places.	Sign indicators should be provided at prominent places as per the guidelines given in IS:9457 for Safety colour and Safety IS:12349 for Fire Protection Safety Signs IS: 12407 for Graphics symbols for Fire Protection Plan.		
18.	Fire Brigade Con Static Water Tank Hydrant System		Required at the	ne Main Gate and on fire water tank	

***Guidelines for Refuge Area:-

Refuge Area: Horizontal Exits/Refuge Area: -

A horizontal exit shall be through a fire door of 120 min rating in a fire resistance wall. Horizontal exit require separation with the refuge area or adjoining compartment through 120 min fire barrier. The adjoining compartment of the horizontal exit should allow unlocked and ease of egress and exits for the occupants using defend in place strategy.

- Requirements of horizontal exits are as under:
- a) Width of horizontal exit doorway shall be suitable to meet the occupant load factor for egress.
- b) Doors in horizontal exits shall be openable at all times from both sides.
- c) All doors shall swing in the direction of exit travel. For horizontal exits, if a double leaf door is used, the right hand door leaf shall swing in the direction of exit travel.
- d) Refuge area shall be provided in buildings of height more than 24 m. Refuge area provided shall be planned to accommodate the occupants of two consecutive floors (this shall consider occupants of the floor where refuge is provided and occupants of floor above) by considering area of 0.3 m² per person for the calculated number of occupants and shall include additionally to accommodate one wheelchair space of an area of 0.9m² for every 200 occupants, portion thereof, based on the occupant load served by the area of refuge or a minimum of 15 m², whichever is higher, shall be provided as under:
- 1) The refuge area shall be provided on the periphery of the floor and open to air at least on one side protected with suitable railings.
- 2) Refuge area(s) shall be provided at/or immediately above 24 m and thereafter at every 15 m or so.
 - The above refuge area requirement for D-6 occupancy requirement shall however be in accordance with 6.4.2.2.
- e) A prominent sign bearing the words 'REFUGE AREA' shall be installed at entry of the refuge area, having height of letters of minimum 75 mm and also containing information about the location of refuge areas on the floors above and below this floor. The same signage shall also be conspicuously located within the refuge area.
- f) Each refuge area shall be ventilated and provided with first aid box, fire extinguishers, public address speaker, fire man talk back, and adequate emergency lighting as well as drinking water facility.
- g) Refuge areas shall be approachable from the space they serve by an accessible means of egress.
- h) Refuge areas shall connect to firefighting shaft (comprising fireman's lift, lobby and staircase) without having the occupants requiring to return to the building spaces through which travel to the area of refuge occurred.
- The refuge area shall always be kept clear. No storage of combustible products and materials, electrical and mechanical equipment, etc. shall be allowed in such areas.

- Refuge area shall be provided with adequate drainage facility to maintain efficient storm water disposal.
- k) Entire refuge area shall be provided with sprinklers.
- Where there is difference in level between connected areas for horizontal exits, ramps of slope not steeper than 1 in 12 shall be provided (and steps should be avoided).

NOTE – Refuge area provided in excess of the requirements shall be counted towards FAR.

High rise apartment buildings with apartments having balcony, need not be provided with refuge area; however apartment buildings without balcony shall provide refuge area as given above. Refuge area for apartment buildings of height above 60 m while having balconies shall be provided at 60 m and thereafter at every 30 m. The refuge area shall be an area equivalent to 0.3 m² per person for accommodating occupants of two consecutive floors, where occupant load shall be derived on basis of 12.5 m² of gross floor area and additionally 0.9 m² for accommodating wheel chair requirement or shall be 15 m², whichever is higher.

GUIDELINES FOR INTERNAL STAIRWAYS as per NBC 2016:

- Stairways shall be constructed of non-combustible materials throughout. Hollow combustible construction shall not be permitted. Width of Staircase should be 1.5
 M.
- b) No Gas piping shall be laid down in the stairway.
- c) Internal staircase shall be constructed as a self-contained unit with at least one side adjacent to an external walls and shall be completely enclosed.
- d) Internal staircase shall not be arranged around lift shaft unless the later is entirely enclosed by material of fire resistance rating as that for type of construction itself.
- e) The access to main staircase shall be gained through at least half-an-hour fire resisting automatic closing doors, placed in the enclosing walls of the staircase. They shall be swing type doors opening in the direction of the escape.
- f) No living space, store or other space, involving fire risk, shall open directly in to staircase.
- g) The external exit door of a staircase enclosure at ground level shall open directly to the open space or should be accessible without passing through any door other than a door provided to form a draught lobby.
- h) The exit signs with arrows indicating the escape routes shall be provided at a height of 1.5 m. from the floor level on the wall and shall painted with fluorescent paint. All exit signs should be flush with the wall and so designed that no mechanical damage to them can result from the removing furniture, material or any other equipment.
- i) Exits shall be so located that it will not be necessary to travel more than 30 Mtrs. from any point to reach the nearest exit.

Staircase Design requirement:

- 1. The minimum headroom in a passage under the landing of a staircase and under the staircases shall be **2.2 Mtrs.**
- 2. Access to main staircase shall be through a fire / smoke check door of a minimum 2 hours fire resistance rating.
- 3. No living space, store or other fire risk shall open directly in to the staircases. The main and external staircases shall be continuous from ground floor to the terrace level.
- 4. No electrical shafts, A/c ducts or gas pipe etc. shall pass through or open in the staircases. Lifts shall not open in staircases.
- 5. The width of the staircase shall not be less than **1.5 Mtrs.**
- 6. All the staircases shall be provided with mechanical Pressurization devices, which will inject the air in to staircase, lobbies or corridors to raise their pressure slightly above the pressure in adjacent parts of the building so the entry of toxic gases or smoke in to the escape routes is prevented.

Staircase Enclosures:-

The external enclosing walls of the staircase shall be of the brick or the RCC construction having the fire resistance of not less than two hours. All enclosed staircases shall have access through self-closing door of one hour fire resistance. These shall be single swing doors opening in the direction of escape. The door shall be fitted with the check action door closers.

- 2. The staircase enclosures on the external wall of the building shall be ventilated to the atmosphere at each landing.
- 3. Permanent vent at the top equal to the 5% of the cross section area of the enclosure and openable sashes at each floor level with area equal to 1 to 15% of the cross sectional area of the enclosure on external shall be provided. The roof of the shaft shall be at least 1 meter above the surrounding roof. There shall be no glazing or the glass bricks in any internal closing wall of staircase. If the staircase is in the core of the building and cannot be ventilated at each landing a positive pressure of 5 mm w.g. by an electrically operated blower/ blowers shall be maintained.
- 4. The mechanism for pressurizing the staircase shaft shall be so installed that the same shall operate automatically on fire alarm system/ sprinkler system and be provided with manual operation facilities.

FIRE ESCAPE: (ENCLOSED TYPE) SHALL COMPLY THE FOLLOWING: -

- 1. <u>Travel Distance should be maintained as per the guidelines given in D.C. Rules of MIDC.</u> Exits and staircase guidelines should be followed as per MIDC's DC Rules and National Building Code-2016.
- 2. Fire escape constructed of M.S. angles, wood or glass is not permitted.
- 3. Opening of the Fire Escape Staircase should be from outside.
- 4. Fire Escape staircase should be enclosed type. These should always be kept in sound operable condition .
- 5. Fire Escape Staircase shall be directly connected to the ground.
- 6. Entrance to the Fire Staircase shall be separate and remote from the internal staircase.
- 7. Care shall be taken to ensure that no wall opening or window opens on to or close to Fire Escape Stairs.
- 8. The route to the external staircase shall be free of obstructions at all times.
- 9. The Fire Escape stairs shall be constructed of non-combustible materials, and any doorway leading to it shall have the required fire resistance.
- 10. No Staircase, used as a fire escape, shall be inclined at an angel greater than 45 of from the horizontal
- 11. The width of the staircase should as given in DC Rules of MIDC. The other detailed provision for exits in accordance with National building code 2016.
- 12. Fire Staircase shall have straight flight not less than **150 c.m. wide** with 20 c.m. treads and risers not more than 19 c.m. The number of risers shall be limited to 15 per flight.
- 13. Handrails shall be of a height not less than 100 c.m. and not exceeding 120 c.m.
- 14. All the staircase doors on every floor shall be provided with two hours fire resistive doors having panic bars at both the sides.

FIRE PROTECTION REQUIREMENTS FOR LIFTS:

(Fire Protection Requirements of Lifts in High Rise Buildings) For Building of Height 15 m and Above

Following requirements over and above those specified in 6 and 8 and in Part 4 'Fire and Life Safety' of the Code are applicable to all lifts provided in buildings having height more than 15 m:

- a) All materials of constructions in load bearing elements, stairways and corridors and facades shall be non-combustible.
- b) The interior finishing materials shall be of very low flame spread type.
- c) Walls of the lift shall have a fire rating of 120 min. The lift well shall have a vent at the top, of area not less than 0.2 m² per lift.
- d) Landing doors Lift landing doors shall be imperforate. Collapsible doors shall not be permitted. Lift landing doors provided in the lift enclosure shall have a minimum fire resistance rating of 60 min.
- e) Lift car door Lift car doors shall be imperforate. Collapsible car doors shall not be permitted.
- f) Telephone or other communication facilities shall be provided in the lift car and the lift main lobby. Communication system for lifts shall also be connected to the fire control room of the building if provided. For lifts for use by persons with disabilities, the facilities shall be provided in accordance with 13 of Part 3 'Development Control Rules and General Building Requirements' of the Code.

- g) Photo luminescent safety signs shall be posted and maintained on every floor at or near the lift indicating that in case of fire, occupants shall use the stairs unless instructed otherwise. The sign shall have the plan of the respective floor showing location of the stairways. The plan shall also indicate the direction to and maintained on every floor of buildings open to and used by the public shall comply with the requirements of accessible signage given in 13 of Part 3 'Development Control Rules and General Building Requirements' of the Code.
- h) All lifts (fireman's lifts/non fireman's lifts) shall be provided with Phase I operation and per 7.1.1(k)(x) (grounding operation).
- j) The grounding operation may be initiated by individual switches for lifts or a common switch for a group of lifts or by a signal from fire alarm system of the building if available.
- k) Fireman lift The fireman's lift is provided in a building for the purpose of aiding firefighters in evacuating trapped persons in the building and to take a equipments for fighting fire to upper levels with minimum delay. Some lifts out of all the lifts shall be identified as fireman's lifts.
 - The number of required fireman's lifts and their locations in a building will vary depending on the size, design, complexity of the building. Some considerations are as follows:
 - 1) There shall be at least one fireman's lift per building.
 - 2) If there are multiple wings in the building, there shall be at least one fireman's lift per wing.
 - 3) If there are multiple banks of lifts in the building there shall be at least one fireman's lift per bank of lift.
 - 4) If the building height is up to 60 m and it is zoned height-wise and it does not have single fireman's lift serving every floor of the building, then there shall be at least one fireman's lift per zone which shall serve the main level/fire access level and shall serve all the landings in the respective zone.
 - 5) If the building height is more than 60 m and it does not have any single fireman's lift serving all the floors, that is, it has all lifts serving only respective zones, the fireman's lift shall be provided in each zone separately, serving all landings in respective zone, with transfer landing transferring from one zone to another.

Considering all the above, the fireman's lift(s) shall be identified on the building plan and duly displayed in Fire Command Centre.

To be effective in firefighting operation, the fireman's lift shall have following requirements:

- i) The fireman's lift may be used by the occupants in normal times.
- ii) The fireman's lift shall be provided with a fireman's switch. The switch shall be a two position (ON/OFF) switch fixed at the evacuation floor (normally main entrance floor) for enabling the lift to be put into fireman's mode. The switch shall be situated in a glass-fronted box with suitable label and fixed adjacent to the lift at the entrance level. When the switch is on, landing call-points shall become inoperative and the lift shall be on the car control only or on a priority control device. When the switch is off, the lift will return to normal working.
- iii) The fireman's lift shall be provided with an audio and visual signal in the car.
- iv) The fireman's lift shall have a floor area of minimum 1.43 m². It shall have loading capacity of not less than 544 kg (8 persons lift).
- v) The fireman's lift shall be provided with power operated (automatic) doors of minimum 0.8 m width.
- vi) The speed of the fireman's lift shall be 1.0 m/s or more such that it can reach the top floor from main floor/ firefighting access level within 1 min. In case the building is zoned, the fireman's lift shall operate from the lowest served landing to the topmost served landing in 1 min.
- vii) Reliable alternative source of power supply should be provided for all fireman lifts through a manually/automatically operated changeover switch. The route of wiring shall be safe from fire.

- viii)Suitable arrangements such as providing slope in the floor of lift lobby shall be made at all the landings to prevent water used during firefighting from entering the lift shafts.
- ix) The words 'Fireman Lift' shall be conspicuously displayed in fluorescent pain on the lift landing.
- x) Operational requirement of fireman's lift- The lift shall be provided with the following operational control, Phase I and Phase II.

Phase I - Return to evacuation floor -

- Shall start when the fireman's switch at the evacuation floor is turned to the 'ON' position or the signal from smoke detector (if provided by the Building Management System is on. All lifts controlled by this switch shall cancel all existing car calls and separate from landing calls and no landing or car calls shall be registered. The audio and visual signal shall be turned on. All heat and smoke sensitive door reopening devices shall be rendered inoperative.
- If the lift is travelling towards the evacuation floor, it shall continue driving to that floor.
- If the lift is travelling away from the evacuation floor, it shall reverse its direction at the nearest possible floor without opening its door and return non-stop to the evacuation floor.
- If the lift is standing at a floor other than the evacuation floor, it shall close the doors and start travelling non-stop to the evacuation floor.
- When at the evacuation floor, the lift shall park with doors open.
- The continuous audio signal is turned off after this return drive.

Note – If the building is designed for alternative evacuation floor, in case of fire at main floor the lifts shall park at the alternative evacuation floor with doors open.

Phase II - Operation of the lift shall be as defined below -

- The phase 2 is started after phase 1, if the fireman's switch is 'ON'.
- If the lifts are grounded by the smoke detector signal, for phase II to begin it shall be necessary to turn the fireman's switch 'ON'.
- The lift does not respond to landing call but registered car calls. All heat and smoke sensitive door reopening devices are rendering inoperative.
- When the car call button is pressed, the doors start closing. If the button is released before the doors are fully closed, they re-open. The car call is registered only when the doors are fully closed. After registering a car call the lift starts driving to the call. If more than one car call is registered, only the nearest call is answered and the remaining call will be cancelled at the fire stop.
- At the floor the doors are opened by pushing the door open button. If the button is released before the doors are fully open, they re-close.
- The lift returns to normal service when it stands at the evacuation floor with doors open and the switch is turned 'OFF' thereafter.
- The operation of fireman's lift shall be by means of a full set of push buttons in the car. Other operating systems shall be rendering inoperative.

Building of Height 60 m and above

The following requirements over and above those specified in guidelines mentioned in **Building of Height 15 m and above** are applicable to the lifts and lift enclosures provided in buildings having height more than 60 m.

- a) Fireman's lifts Following additional requirements apply to all fireman's lifts in the building.
 - 1) The fireman's lift shall have loading capacity of not less than 1000 kg and floor area not less than 2.35 m².
 - 2) Electrical equipment within the fireman's lift well and on the car, located within 1.0 m of any wall containing a landing door, shall be protected from dripping and splashing water or provided with enclosures classified to at least IPX3 according to good practice [8-5A(9)].
 - 3) The electrical switchgear placed less than 1 m above lift pit floor shall be protected to IP 67 as per to good practice [8-5A(9)]. The socket outlet and lowest lamp shall also be located at least 0.5 m above the highest permissible water level in the pit.
 - 4) Suitable means shall be provided in the lift pit to ensure that water will not rise above the level of the fully compressed car buffer.

- 5) Means shall be provided to prevent the water level in the pit from reaching equipment which could create an malfunction of the fireman's lift.
- 6) Alternative source of power supply shall be provided for all fireman's lifts through automatically operated changeover electric supply, it shall automatically trip over to alternative supply. The route of wiring shall be safe from fire.
- b) There shall be Fire Command Centre (FCC) and/or Building Management System (BMS) room in the building CCTV cameras shall be fixed in the lift lobbies and the display screen(s) shall be placed in the FCC or BMS room.

FIRE FIGHTING SHAFT (FIRE TOWER) :-

- An enclosed shaft having protected area of 120 min fire resistance rating comprising protected lobby, staircase and fireman's lift, connected directly to exit discharge or through exit passageway with 120 min fire resistance wall at the level of exit discharge to exit discharge.
- These shall also serve the purpose of exit requirement / strategy for the occupants.
- The respective floors shall be approachable from fire-fighting shaft enabling the fire fighters to access the floor and also enabling the fire fighters to assist in evacuation through fireman's lift.
- The firefighting shaft shall be equipped with 120 min fire doors.
- The firefighting shaft shall be equipped with firemen talk back, wet riser and landing valve in its lobby, to fight fire by fire fighters

Staircase and Corridor Lightings:

- a) The staircase and corridor lighting shall be on separate service and shall be independently connected so as it could be operated by one switch installation on the ground floor easily accessible to firefighting staff at any time irrespective of the position of the individual control of the light points, if any. It should be of miniature circuit breaker type of switch so as to avoid replacement of fuse in case of crisis.
- b) Staircase and corridor lighting shall also be connected to alternate source of supply. The alternative source of supply may be provided by battery continuously trickle charged from the electric mains.
- c) Suitable arrangements shall be made by installing double throw switches to ensure that the lighting installed in the staircase and the corridor do not get connected to the sources of supply simultaneously. Double throw switch shall be installed in the service room for terminating the stand by supply.
- d) Emergency lights shall be provided in the staircase/corridor.
- e) All wires & other accessories used for emergency lights shall have fire retardant property.
- f) A stand-by electric generator shall be installed to supply power to staircase and corridor lighting circuits, fire lifts, the stand-by fire pump, pressurization fans & blowers, smoke extraction and damper system in case of failure of normal electric supply. The generator shall be capable of taking starting current of all the machines & circuits stated above simultaneously. If the stand-by pump is driven by diesel engine, the generator supply need not be connected to the stand-by pump or parallel HV/LV supply from a separate substation shall be provided with appropriate transformer for emergency. If this arrangement is provided then the arrangement of generator is not mandatory.

Emergency and Escape Lighting:-

- 1. Emergency lighting shall be powered from a source independent of that supplying the normal lighting.
- 2. Escape lighting shall be capable of
 - A) Indicating clearly and unambiguously the escape routes.
 - B) Providing adequate illumination along such routes to allow safe movement of persons towards and through the exits.
 - C) Ensuring that fire alarm call points and firefighting equipment's provided along the escape routes can be readily located.
- 3. The horizontal luminance at floor level on the centerline of an escape route shall be not less than 10 lux. In addition, for escape routes up to 2 m wide, 50 percent of the route width shall be lit to a minimum of 5 lux.

- 4. The emergency lighting shall be provided to be put on within 1 s of the failure of the normal lighting supply.
- 5. Escape lighting luminaries should be sited to cover the following locations
 - a) Near each intersection of corridors
 - b) At each exit door
 - c) Near each change of direction in the escape rout
 - d) Near each staircase so that each flight of staircase receives direct light.
 - e) Near any other change of floor level.
 - f) Outside each final exit and close to it
 - g) Near each fire alarm call point.
 - h) Near firefighting equipment, and
 - i) To illuminate exit and safety signs as required by the fire department.
- 6. Emergency lighting systems shall be designed to ensure that a fault or failure in any one luminaire does not further reduce the effectiveness of the system.
- 7. The luminaries shall be mounted as low as possible but at least 2 m above the floor level.
- 8. Signs are required at all exits, emergency exits and escape routes, which should comply with the graphic requirements of the relevant Indian Standard.
- 9. Emergency lighting luminaries and their fittings shall be of nonflammable type.
- 10. It is essential that the wiring and installation of the emergency lighting system are of high quality so as to ensure their perfect serviceability at all times.
- 11. The emergency lighting system shall be capable of continuous operation for a minimum duration of 1 hour and 30 minutes even for the smallest premises.
- 12. The emergency lighting system shall be well maintained by periodical inspections and tests so as to ensure their perfect serviceability at all times.

Illumination of Means of Exit :-

Staircase and corridor lights shall confirm to the following:-

- a) The staircase and corridor lighting shall be on separate circuit and shall be independently connected so that it could be operated by one switch installation on the ground floor easily accessible to firefighting staff at any time irrespective of the position of the individual control of the light points, if any. It should be of miniature circuit breaker type of switch so as to avoid replacement of fuse in case of crises.
- b) Staircase and corridor lighting shall also be connected to alternative supply. The alternative source of supply may be provided by battery continuously trickle charged from the electric mains; and
- c) Suitable arrangements shall be made by installing double throw switches to ensure that the lighting installed in the staircase and the corridor does not get connected to two sources of supply simultaneously. Double throw switch shall be installed in the service room for terminating the sand by supply.

Exit Requirement:

- 1. An exit may be doorway, corridor, Passageway(s) to an internal staircase, or external staircase, or to a verandah or terrace(s), which have access to the street, or to the roof of a building or a refuge area. An exit may also include a horizontal exit landing to an adjoining building at the same level.
- 2. Every exit, exit access or exit discharge shall be continuously maintained free of all obstructions or impediments to full use in the case of fire or other emergency.
- 3. Exits shall be clearly visible and the route to reach the exits shall be clearly marked and signs posted to guide the occupants of the floor concerned. Signs shall be illuminated and wired to an independent electric circuit on an alternative source of supply.
- 4. To prevent spread of fire and smoke, fire doors with 2 hours fire resistance shall be provided at appropriate places along the escape routes and particularly at the entrance to lift lobby and stair well where a 'funnel or flue effect' may be created inducing an upward spread of fire.
- 5. All exits shall provide continuous means of egress to the exterior of a building or to an exterior open spaces leading to the street.
- 6. Exits shall be so arranged that they may be reached without passing through another occupied unit.

Glass Facade

- 1. If the glass cladding is used / provided to the building the glass used for the cladding must be toughened glass.
- The use of combustible surface finishes on walls (including facade of the building) and ceiling affects the safety of the occupants of the building. Such finishes tend to spread the fire and even though the structural elements may be adequately fire resistant, serious danger to life may result. It is therefore, essential to have adequate precautions to minimize spread of flame on wall, façade of building and ceiling surfaces.
- 3. The finishing materials used for various purposes and décor shall be such that it shall not generate toxic fumes / smoke.
- 4. Automatic smoke venting facilities shall be provided for safe use of exits in windowless buildings.
- 5. Natural draft smoke venting shall utilize roof vents in walls at or near the ceiling level, such vents shall be normally open, or, if closed, shall be designed for automatic opening in case of fire, by release of smoke sensitive devices.
- 6. Where smoke venting facilities are installed for purposes of exit safety, these shall be adequate to prevent dangerous accumulation of smoke during the period of time necessary to evacuate the area served, using available exit facilities with a margin of safety to allow for unforeseen contingencies.

GLAZING:-

The glazing shall be in accordance with Part 6 'Structural Design, Section 8 Glass and Glazing' of the Code. The entire glazing assembly shall be rated to that type of construction as given in Table 1. This shall be applicable along with other provisions of this Part related to respective uses as specified therein. The use of glass shall not be permitted for enclosures of exits and exit passageway.

Glass facade shall be in accordance with the following:

- a) For fully sprinklered building having fire separation of 9 m or more, tempered glass in a non-combustible assembly, with ability to hold the glass in place, shall be provided. It shall be ensured that sprinklers are located within 600 mm of the glass facade providing full coverage to the glass.
 - **NOTE-** In case of all other buildings, fire resistance rating of glass facade shall be in accordance with Table 1.
- b) All gaps between floor-slabs and facade assembly shall be sealed at all levels by approved fire resistance sealant material of equal rating as that of floor slab to prevent fire and smoke propagation from one floor to another.
- c) Openable panels shall be provided on each floor and shall be spaced not more than 10 m apart measured along the external wall from centre-to-centre of the access openings. Such openings shall be operable at a height between 1.2 m and 1.5 m from the floor, and shall be in the form of openable panels (fire access panels) of size not less than 1000 mm X 100 mm opening outwards. The wordings, 'FIRE OPENABLE PANEL OPEN IN CASE OF FIRE, DO NOT OBSTRUCT'of at least 25 mm letter height shall be marked on the internal side. Such panel shall be suitably distributed on each floor based on occupant concentration. These shall not be limited to cubicle areas and shall be also located in common areas/corridors to facilitate access by the building occupants and fire personnel for smoke exhaust in times of distress.

Smoke Control of Exits :-

- a) In building design, compartmentation plays a vital part in limiting the spread of fire and smoke. The design should ensure avoidance of spread of smoke to adjacent spaces through the various leakage openings in the compartment enclosure, such as cracks, openings around pipes ducts, airflow grills and doors. In the absence of proper sealing of all these openings, smoke and toxic gases will obstruct the free movement of occupants of the building through the exits. Pressurization of staircases is of great importance for the exclusion of smoke and toxic gases from the protected exit.
- b) Pressurization is a method adopted for protecting the exits from ingress of smoke, especially in high-rise buildings. In pressurization, air is injected into the staircases, lobbies, etc., as applicable, to raise their pressure slightly above the pressure in adjacent parts of the buildings. As a result, ingress of smoke or toxic

gases into the exits will be prevented. The pressurization of staircases and lift lobbies shall be adopted as given in Table 6. The pressure difference for staircases shall be 50 Pa. Pressure difference for lobbies (or corridors) shall be between 25 Pa and 30 Pa. Further, the pressure differential for enclosed staircase adjacent to such lobby (or corridors) shall be 50 Pa. For enclosed staircases adjacent to non-pressurized lobby (or corridors), the pressure differential shall be 50 Pa.

Pressurization of Staircases and Lift Lobbies

(Clause 4.4.2.5 (b) and E-2)

Sr.	Component		Height of Building		
No.		Less than 15 m	15 m to 30 m	More than 30	
(1)	(2)	(3)	(4)	(5)	
i)	Internal staircases not with	Pressurized	Pressurized	Pressurized	
	external wall	except for			
		residential			
		buildings (A-2			
		and A-4)			
ii)	Internal staircase with	Pressurized	Naturally	Cross-ventilated	
	external wall	except for	ventilated or	or Pressurized	
		residential	Pressurized		
		buildings (A-2			
		and A-4) or			
		Naturally			
		ventilated			
iii)	Lift lobby	Not required at		Cross-ventilated	
		ground and	ventilated or	or Pressurized ¹⁾	
		above.	Pressurized ¹⁾		
		However lift			
		lobby			
		segregation and			
		pressurization is			
		required for lift			
		commuting from			
		ground to			
NOTEC		basement			

NOTES:

- 1. The natural ventilation requirement of the staircase shall be, achieved through opening at each landing, of an area 0.5 m² in the external wall. A cross ventilated staircase shall have 2 such openings in opposite/adjacent walls or the same shall be cross-ventilated through the corridor.
- 2. Enclosed staircase leading to more than one basement shall be pressurized.
- 1) Lift lobby with fire doors (120 min) at all levels with pressurization of 25-30 PA is required. However, if lift lobby cannot be provided at any of the levels in air conditioned buildings or in internal spaces where funnel/flue effect may be created, lift hoistway shall be pressurized at 50 Pa. For building greater than 30 m, multiple point injection air inlets to maintain desired pressurization level shall be provided. If the lift lobby, lift and staircase are part of firefighting shaft, lift lobby necessary has to be pressurized in such case, unless naturally ventilated.
- c) Equipment and ductwork for staircase pressurization shall be in accordance with one of the following:
 - 1) Directly connected to the stairway by ductwork enclosed in non-combustible construction.
 - 2) If ducts used to pressurize the system are passed through shafts and grills are provided at each level, it shall be ensured that hot gases and smoke from the building cannot ingress into the staircases under any circumstances.
- d) The normal air conditioning system and the pressurization system shall be designed and interfaced to meet the requirements of emergency services. When the emergency pressurization is brought into action, the following changes in the normal air conditioning system shall be effected:
 - 1) Any re-circulation of air shall be stopped and all exhaust air vented to atmosphere.
 - 2) Any air supply to the spaces/areas other than exits shall be stopped.
 - 3) The exhaust system may be continued provided
 - The positions of the extraction grills permit a general air flow away from the means of egress;

- ii) The construction of the ductwork and fans is such that, it will not be rendered inoperable by hot gases and smoke; and
- iii) There is no danger of spread of smoke to other floors by the path of the extraction system which can be ensured by keeping the extraction fans running.
- e) For pressurized stair enclosure systems, the activation of the systems shall be initiated by signalling from fire alarm panel.
- f) Pressurization system shall be integrated and supervised with the automatic/manual fire alarm system for actuation.
- g) Wherever pressurized staircase is to be connected to unpressurized area, the two areas shall be segregated by 120 min fire resistant wall.
- h) Fresh air intake for pressurization shall be away (at least 4 m) from any of the exhaust outlets/grille.

Smoke Control:

Smoke Exhaust and Pressurization of Areas above Ground -

Corridors in exit access (exit access corridor) are created for meeting the requirement of use, privacy and layout in various occupancies. These are most often noted in hospitality, health care occupancies and sleeping accommodations. corridors of guest rooms and indoor patient department/areas having patients lacking self-preservation and for sleeping accommodations such as apartments, custodial, penal and mental institutions, etc., shall be provided with 60 min fire resistance wall and 20 min self-closing fire doors along with all fire stop sealing of penetrations. Smoke exhaust system having make-up air and exhaust air system or alternatively pressurization system with supply air system for these exit access corridors shall be required. Smoke exhaust system having make-up and exhaust air system shall also be required for theatres/auditoria. Such smoke exhaust system shall also be required for large lobbies and which have exit through staircase leading to exit discharge. This would enable eased exit of people through smoke controlled area to exit discharge. All exit passageway (from exit to exit discharge) shall be pressurized or naturally ventilated. The mechanical pressurization system shall be automatic in action with manual controls in addition. All such exit passageway shall be maintained with integrity for safe means of egress and evacuation. Doors provided in such exit passageway shall be fire rated doors of 120 min rating. Smoke exhaust system where provided, for above areas and occupancies shall have a minimum of 12 air changes per hour smoke exhaust mechanism. Pressurization system where provided shall have a minimum pressure differential of 25-30 Pa in relationship to other areas. The smoke exhaust fans in the mechanical ventilation system shall be fire rated, that is, 250°C for 120 min. naturally cross-ventilated corridors or corridors with operable windows, such smoke exhaust system or pressurization system will not be required.

Smoke Exhaust and Pressurization of Areas below Ground -

Each basement shall be separately ventilated. Vents with cross-sectional area (aggregate) not less than 2.5 percent of the floor area spread evenly round the perimeter of the basement shall be provided in the form of grills, or breakable stall board lights or pavement lights or by way of shafts. Alternatively, a system of mechanical ventilation system may be provided with following requirements:

- a) Mechanical ventilation system shall be designed to permit 12 air changes per hour in case of fire or distress call. However, for normal operation, air changes schedule shall be as given in Part 8 'Building Services, Section 3 Air Conditioning, Heating and Mechanical Ventilation' of the Code.
- b) In multi-level basements, independent air intake and smoke exhaust shafts (masonry or reinforced concrete) for respective basement level and compartments therein shall be planned with its make-up air and exhaust air fans located on the respective level and in the respective compartment. Alternatively, in multi-level basements, common intake masonry (or reinforced cement concrete) shaft may serve respective compartments aligned at all basement levels. Similarly, common smoke exhaust/outlet masonry (or reinforced cement concrete) shafts may also be planned to serve such compartments at all basement levels. Al supply air and exhaust air fans on respective levels shall be installed in fire resisting room of 120 min. Exhaust fans at the respective levels shall be provided with back draft damper connection to the common smoke exhaust shaft ensuring complete

- isolation and compartmentation of floor isolation to eliminate spread of fire and smoke to the other compartments/floors.
- c) Due consideration shall be taken for ensuring proper drainage of such shafts to avoid insanitation condition. Inlets and extracts may be terminated at ground level with shall board or pavement lights as before. Stall board and pavement lights should be in positions easily accessible to the fire brigade and clearly marked 'AIR INLET' or 'SMOKE OUTLET' with an indication of area served at or near the opening.
- d) Smoke from any fire in the basement shall not obstruct any exit serving the ground and upper floors of the building.
- e) The smoke exhaust fans in the mechanical ventilation system shall be fire rated, that is, 250°c for 120 min.
- f) The smoke ventilation of the basement car parking areas shall be through provision of supply and exhaust air ducts duly installed with its supports and connected to supply air and exhaust fans. Alternatively, a system of impulse fans (jet fans) may be used for meeting the requirement of smoke ventilation complying with the following:
 - 1) Structural aspects of beams and other down stands/services shall be taken care of in the planning and provisions of the jet fans.
 - 2) Fans shall be fire rated, that is, 250°C for 120 min.
 - 3) Fans shall be adequately supported to enable operations for the duration as above.
 - 4) Power supply panels for the fans shall be located in fire safe zone to ensure continuity of power supply.
 - 5) Power supply cabling shall meet circuit integrity requirement in accordance with accepted standard [4(13)].

The smoke extraction system shall operate on actuation of flow switch actuation of sprinkler system. In addition, a local and/or remote 'manual start-stop control/switch' shall be provided for operations by the fire fighters. Visual indication of the operation status of the fans shall also be provided with the remote control. No system relating to smoke ventilation shall be allowed to interface or cross the transformer area, electrical switchboard, electrical rooms or exits. Smoke exhaust system having make-up air and exhaust air system for areas other than car parking shall be required for common areas and exit access corridor in basements/underground structures and shall be completely separate and independents of car parking areas and other mechanical areas. Supply air shall not be less than 5 m from any exhaust discharge openings.

CAR PARKING FACILITIES: GENERAL

- a) Where both parking and repair operations are conducted in the same building, the entire building shall comply with the requirements for group G occupancies, unless the parking and repair sections are effectively separated by separation walls of 120 min.
- b) Floor surface shall be non-combustible, sloping towards drains to remove accumulation of water.
- c) Those parts of parking structures located within, immediately above or below, attached to, or less than 3 m away from a building used for any other purpose shall be separated by fire resistant walls and floors having fire resistance rating not less than 120 min. This shall exclude those incidental spaces which are occupied by cashier, attendant booth or those spaces used for toilets, with a total area not exceeding 200 m².
- d) Vehicle ramps shall not be considered as exists unless pedestrian facilities provided.
- e) Other occupancies like fuel dispensing, shall not be allowed in the building. Car repair facilities, if provided, shall be separated by 120 min fire resistance construction.
- f) In addition to fire protection requirements as per table 7, appropriate fire detection and suppressions systems shall be provided for the protection of hydraulic oil tank and pumps located below ground level for operation of car lifts.
- g) Means of egress shall meet the requirements specified

OPEN PARKING STRUCTURES (INCLUDING MULTY-LEVEL PARKING AND STILT PARKING)

a) The term of open parking structure specifies the degree to which the structures exterior walls must have openings. Parking structures that meet the definition of

- the term open parking structure provide sufficient area in exterior walls to vent the products of combustion to a greater degree than enclosed parking structure.
- b) A parking structure having each parking level wall openings open to the atmosphere, for an area of not less than 0.4 m² for each linear meter of its exterior perimeter shall be constructed as open parking structure. Such openings shall be distributed over 40 percent of the building perimeter or uniformly over two opposing sides. Interior wall lines shall be at least 20 percent open, with openings distributed to provide ventilation, else, the structure shall be deemed as enclosed parking structures.
 - NOTE: A car park located at the stilt level of a building (not open to sky) can be considered an open or an unenclosed car park if any part of the car park is within 30 m of a permanent natural ventilation opening and any one of the following is complied with towards the permanent natural ventilation requirement:
 - 50 percent of the car park perimeter shall be open to permanent natural ventilation.
 - ii. At least 75 percent of car park perimeter is having the 50 percent natural ventilation opening.
- c) All stilt parking are required to be provided with sprinkler system where such buildings are required to be sprinklered.
- d) Open parking structures are not required to be provided with compartmentation.
- e) Open car parking (open to sky) within building complex having fire hydrant systems shall also need to be protected with yard hydrant installation system in accordance with good practice. [4(29)].

ENCLOSED PARKING STRUCTURES

- a) Those car parking structures which are enclosed on all sides and on top, not falling within the definition of open car parking [see **H-3** (b)] and also those situated in the basements shall be known as enclosed car parking structures.
- b) All sprinklers in car parking shall be standard response type with minimum K-Factor of 80, area coverage of 9 m2 and designed as per good practice [4(20)].
- c) For the basement car parking, compartmentation can be achieved, with fire barrier or with water curtain nozzle (K-23) or with combination thereof. Automatic deluge system comprising deluge valve, piping, nozzles, etc shall be used to zone the compartment in case of water curtain system. In case of water curtain, existing water storage shall be supplemented by water demand for water curtain nozzles for 60 min considering the largest compartments perimeter out of all compartments of car parking in any of the basements.
- d) The water supply for the water curtain nozzles shall be through independent electric pump of adequate capacity (flow and head) with piping/riser for the water supply to the nozzles.
- e) The water curtain shall be operated by the actuation of flow switch actuating sprinkler system.
- f) For smoke ventilation requirement of car parking.
- g) All fire exit doors from the car parking to exits shall be painted green and shall display exit signage.

Automated Car Parking Utilizing Mechanical or Computerized /Robotic Means

- a) Automated car parking structure can be of open parking type or enclosed types.
- b) Automated car parking facilities pose more hazard compared to manual parking due to following reasons:-
 - 1) High density of cars due to close stacking-one over another.
 - 2) Lack of provision on fire separation/compartmentation-horizontal or vertical leading to rapid fire spread.
 - 3) Non availability of any person to notice/control the fire in initial stages.
 - 4) Limited access to firefighting personnel.
 - 5) Extensive height and depth involved with highly combustible load.
- c) Fire escape staircases, at least 1250 mm wide shall be provided at appropriate locations so that no place is more than 45 m from the nearest staircase. Horizontal walkways, at least 1000 mm wide for access to all the areas shall be provided at every parking level.
- d) Travel distance and means of egress shall be governed by the respective sections of this code.
- e) The hazardous areas like DG sets, transformers, HT/LT panels for the parking lot shall be suitably segregated from the other areas as per requirements given this

code and all such areas shall be protected by suitable automatic fire suppressions systems.

SERVICE DUCTS / REFUGE CHUTE:

- Service duct shall be enclosed by walls and door, if any, of two hours fire rating.
 If ducts are larger than 10 Sq. Meters the floor should seal them, but provided
 suitable opening for the pipes to pass through, with the gaps sealed.
- 2. A vent opening at the top of the service shaft shall be provided between one fourth and one half of the area of the shaft. Refuge chutes shall have an outlet at least of wall of noncombustible material with fire resistance of not less than two hours. They shall not be located within the staircase enclosure or service shafts or air conditioning shafts. Inspection panel and door shall be tight fitting with one hour fire resistance; the chutes should be as far away as possible from exits.
- 3. Refuge Chutes shall not be provided in staircase walls and A/C shaft etc.

ELECTRICAL SERVICES:

- 1. For the requirements regarding installations from the point of view of Fire Safety, guidelines should be followed as mentioned in IS Standard :1646 Code of practice for Fire safety Buildings : Electrical Installations.
- 2. The electric distribution cables/wiring shall be laid in separate duct. The duct shall be sealed at every alternate floor with non-combustible materials having same fire resistance as that of the duct.
- 3. Water mains, telephone lines, intercom lines, gas pipes or any other service lines shall not be laid in the duct of electric cables.
- 4. Separate circuits for water pumps, staircase & corridor lighting shall be provided directly from the main switch gear panel and these circuits shall be laid in separate conduit pipes so that fire in one circuit will not affect the others.
- 5. The inspection panel doors and any other opening in the shaft shall be provided with <u>air tight doors having fire resistance of not less than 2hrs.</u>
- **6.** Medium & low voltage wiring running in shaft and within fall ceiling shall run in metal conduit.
- 7. An independent & well-ventilated service room shall be provided on the ground floor with direct access from outside or from the corridor for the purpose of termination of electric supply. The doors provided for the service room shall have fire resistance of not less than two hours.

Electrical services shall conform to the following: (High Rise building)

- a) The electric distribution cables/wiring shall be laid in a separate duct. The duct shall be sealed at every floor with non-combustible materials having the same fire resistance as that of the duct. Low and medium voltage wiring running in shaft and in false ceiling shall run in separate conduits;
- b) Water mains, telephone lines, intercom lines, gas pipes or any other service line shall not be laid in the duct for electrical cables; use of bus ducts/solid rising mains instead of cables is preferred;
- c) Separate circuits for firefighting pumps, lifts, staircases and corridor lighting and blowers for pressurizing system shall be provided directly from the main switch gear panel and these circuits shall be laid in separate conduit pipes, so that fire in one circuit will not affect the others. Such circuits shall be protected at origin by an automatic circuit breaker with its no-volt coil removed. Master switches controlling essential service circuits shall be clearly labeled;
- d) The inspection panel doors and any other opening in the shaft shall be provided with air-tight fire doors having fire resistance of not less than 2 h;
- e) Medium and low voltage wiring running in shafts, and within false ceiling shall run in metal conduit. Any 230 V wiring for lighting or other services, above false ceiling, shall have 660 V grade insulation. The false ceiling, including all fixtures used for its suspension, shall be of non-combustible material and shall provide adequate fire resistance to the ceiling in order to prevent spread of fire across ceiling reference may be made to good practice.
- f) An independent and well ventilated service room shall be provided on the ground level or first basement with direct access from outside or from the corridor for the purpose of termination of electric supply from the licensees' service and alternative supply cables. The doors provided for the service room shall have fire resistance of not less than 2 h;

- g) If the licensees agree to provide meters on upper floors, the licensees' cables shall be segregated from consumers' cables by providing a partition in the duct. Meter rooms on upper floors shall not open into stair case enclosures and shall be ventilated directly to open air outside; and
- h) Suitable circuit breakers shall be provided at the appropriate points.

Guidelines for Substation/Transformers

- Areas in substation shall not be used as storage/dump areas or for other utility purposes other than those required for the functioning of the substation.
- The substation area should be adequately ventilated.
- An independent, ventilated or air conditioned MV panel room shall be provided on the ground level or first basement. This room shall be provided with access from outside (or through exit passageway accessible from outside). The MV panel room shall be provided with fire resistant walls and doors of fire resistance of not less than 120 min.
- If the licensees agree to provide meters on upper floors, the licensee's cables shall be segregated from consumers cables by providing a partition in the shaft.
- Meter rooms on upper floors shall not open into staircase enclosures and should be ventilated directly to open air outside or in electrical room of 120 min fire resistant walls.
- Electrical MV main distribution panel and lift panels shall be provided with CO2/inert gas flooding system for all panel compartments with a cylinder located beside the panel.

Oil filled substation

- A substation or a switch-station with oil filled equipment shall be limited to be installed in utility building or in outdoor location. Such substation/utility building shall be at least 7 m away from the adjoining building(s).
- Substation equipment (exceeding oil capacity of 2 000 litre) in utility building shall have fire rated baffle walls of 240 min rating constructed between such equipment, raised to at least 600 mm above the height of the equipment (including height of oil conservators) and exceeding 300 mm on each side of the equipment.
- All transformers where capacity exceeds 10 MVA shall be protected by high velocity water spray systems or nitrogen injection system.

Dry type substation

- Transformers located inside a building shall be of dry type and all substation/switch room walls, ceiling, floor, opening including doors shall have a fire resistance rating of 120 min.
- Access to the substation shall be provided from the nearest fire exit/exit staircase for the purpose of electrical isolation.

In addition to the above, all provision under the D.C. Rules of MIDC and N.B.C. shall be strictly adhered, also if any change in activity or Proposed expansion or Subletting of Plot or Transfer of Plot, NOC from this department is essential.

This is a **Provisional No Objection Certificate.** After providing the above fire prevention and protection system and after compliance of above recommendations inspection of the premises & fire prevention & protection arrangements will be carried out by this department and after satisfactory compliance "Final No Objection Certificate" will be issued. <u>This "Provisional No-Objection Certificate" will be treated valid for the period of one year from the date of issue.</u>

Note; This Provisional No Objection Certificate is granted for FSI – 1.0 Only. In future if you intend to go for extension of your building after obtaining permission for Additional FSI. You are hereby informed to provide clear marginal spaces around the building considering additional FSI & proportionate height of the proposed building. (As per D. C. Rule Table No, 10) Due to any constraint, if the marginal spaces are not maintained as per table 2 (Clause No; 8.2.3.1) of N.B.C part III & as per D C Rule Table No, 10, it will be obligatory on your part to consume the FSI without affecting the marginal spaces as prescribed in the rules or the National Building Code thereof.

Details of "Fire Protection Fund Fees" are as follow:

		Total Amount	Advance "Fire	Balance "Fire
			Protection Fund fees"	Protection Fund
			paid by M/s. Industrial	fees" needs to be
			Minerals & Chemical	recovered by SPA
			Co. Pvt. Ltd. vide	
			receipt no.	
			MCH/6936/2019	
			Dt.09/09/2019	
(i)		(ii)	(iii)	(iv)
Initial	"Fire			
Protection	Fund	Rs. 10,09,632.00 /-	Rs. 6,78,467.50 /-	Rs. 3,31,164.50 /-
fees"				
Additional	"Fire			
Protection	Fund	Rs. 1,05,27,513.50 /-	Rs. 91,32,822.00 /-	Rs. 13,94,691.50 /-
fees"				
Total		Rs. 1,15,37,145.50 /-	Rs. 98,11,289.50 /-	Rs. 17,25,856.00/-

MIDC/Fire Dept/ 1078 dated 12/07/06. M/s, Industrial Minerals & Chemical Co. Pvt. Ltd., had paid "Fire Protection & Scrutiny Fund Fees" of Rs. 91,32,822 /-vide receipt No. 1073/CH/5551/2017; Dated; 14/11/2017.

The undersigned reserves the right to amend any additional recommendations deemed fit during the stage wise inspection due to the statutory provisions amended from time to time and in the interest of the protection of the company.

Thanking you.

Yours faithfully,



(S. S. Warick)
Chief Fire Officer & Fire Advisor,
MIDC, MUMBAI 400 093,

Copy to The Executive Engineer, MIDC, Sub Division Mahape, for information. He is requested to recover the Balance fees mentioned in column no. (iv) of above table before issuing work commencement certificate/plan approval.



INDUSTRIAL MINERALS AND CHEMICAL COMPANY PVT. LTD.

Corporate Identity Number: U24100MH1968PTC014142

Registered Office: E Block, Voltas Premises, T. B. Kadam Marg, Chinchpokli, Mumbai - 400 033, India
Tel: +91 22 6661 4444 • Fax: +91 22 6661 4452 • Email: trilsec@tatarealty.in

12th December 2019

To, The Forest Officer, Forest Department, Teen-Hath Naka, Louise Wadi, Thane (West), Thane

Subject

Application for Wildlife NOC with reference to Thane creek flamingo sanctuary

Reference: :

Application for Environmental Clearance (EC) for "Intellion IT Park" located at

Plot no. 23, 23 (pt), 24 and 24 (pt) TTC Industrial Area, MIDC - Mahape, Dist. -

Thane, Maharashtra.

Dear Sir,

This is with reference to above mentioned subject we are developing "Intellion IT Park" located at TTC Industrial Area, MIDC – Mahape, Dist. Thane. We have submitted Application for obtaining Environmental Clearance from SEIAA, Maharashtra.

We would like to bring to your notice that, our projects falls within 10 Km radius from the Thane Creek Flamingo Sanctuary. The project is in well-developed locality and also separated from Thane Creek Flamingo Sanctuary by other urban settlement.

We are submitting herewith our application for grant of Wildlife NOC for the above-mentioned project.

Please do the needful and oblige.

Thanking you,

Yours faithfully

For INDUSTRIAL MINERALS & CHEMICAL CO. PVT. LTD.

AUTHORIZED SIGNATORY

Encl.: Google image of the project site

13/12/019 ज्या कर्तांच ज्या कर्तांचार विभागीय वन अधिकारी, मुंबई कांदळवन संधारण घटक यांचे कार्यालय विकास वालावलकर बंगला रूम नं. बी/68, पहिला मजला, कामगार नगर, कुर्ला (पूर्व) कुर्ला (पू.) 400 024 फोन नं. 022-25220097



OFFICE OF THE DIVISIONAL FOREST OFFICR,

Vikas Valavalkar Bonglow, B/68, 1st floor,

Kamgar nagar, kurla (E)

Kurla €-400 024

Email Id-dfommcu@gmail.com

विषय:- Application for Wildlife NOC with reference to Thane creek flamingo sanctuary.

जा.क्र./कक्ष-९/जिमन/ २५।५ /सन २०१९-२०, कुर्ला- मुंबई-४०० ०२४, दिनांक:- २८/०२/२०२०.

प्रिति,

Insustrial Minerals And Chemical company pvt.ltd

E Block, Voltas Premises,

T.B.Kadam MARG,

Chinchpokli, Mumbai- 40 033.

संदर्भ:- आपल्याकडील पत्र दिनांक.१८/०२/२०२० रोजीचे पत्र.

उपरोक्त विषयांन्वये आपणांकडून मौजे महापे, ठाणे येथील प्रस्तावीत प्रकल्पाच्या बांधकामाकरिता या विभागाकडून ना- हरकत प्रमाणपत्राची मागणी केलेली आहे.

त्याअनुषंगाने आपणास कळिवण्यात येते की, संदर्भ क्र. २ अन्वये मा. सर्वोच्च न्यायालयानी दिलेल्या आदेशानुसार ठाणे खाडी फ्लेमिंगो अभयारण्याचे समोचतालचे १०.०० कि.मी. परीघाचे क्षेत्र हे मानवी पर्यावरण संवेदनशील क्षेत्र म्हणून घोषित आहे. त्यामुळे आपला प्रकल्म्प या क्षेत्रात येत आहे. त्यामुळे आपणास नियमानुसार राज्य / राष्ट्रीय वन्यजीव मंडळाची विहीत प्रपत्रात या विभागामार्फत प्रस्ताव सादर करुन परवानगी घेणे आवश्यक राहील यांची नोंद घ्यावी.

विभागीय वन अधिकारी मुंबई कांदळवन संधारण घटक

प्रतिलिपी- मा. अपर प्रधान मुख्य वनसंरक्षक, कांदळवन कक्ष, मुंबई यांना माहितीसाठी सविनय सादर.

INDUSTRIAL MINERALS AND CHEMICAL COMPANY PVT. LTD.

Corporate Identity Number: U24100MH1968PTC014142

Tel.: +91 22 6629 4000 • Fax: +91 22 6610 0520 • E-mail: trilsec@tata.com Registered Office: Elphinstone Building, 2nd Floor, 10 Veer Nariman Road, Fort, Mumbai 400 001

Corporate Environmental Responsibility

In accordance with the circular issued by Ministry of Environment, Forest and Climate Change (MoEF & CC) dated May 01, 2018 and subsequent circular of June 19, 2018 on Corporate Environment Responsibility we hereby submit out plan as below;

A. Basic Information of the Project

No.	Description	Details		
1	Name of the Project	"IMCC IT Park"		
2	Location of the project	Plot No.23, 23 (PT.) 24 & 24(PT), TT Industrial Area, MIDC – Mahape, Dist		
3	Project type (green/brown field)	Thane, Maharashtra. Green field		
4	Cost of the project (Phase 1) as mentioned in CS (Rupees in Crore)	Rs. 300 Crore		
5	Any previous EC and Completion certificate of the part of the project before May 01, 2018, if yes give the details with date and reference number	NA		
6	Cost of the part completed project (as per details given at Sr.No.5)	NA		
7	Effective cost of the project (Phase 1) for CER consideration (4-6)	Rs. 300 Crores		
8	Applicable norms in terms of % of the project cost for CER and amount for (Phase 1)	Rs. 4.5 Crores (1.5%)		
9	Expected duration in years for completion of the project (Phase 1)	3 years		
10	Implementing Agency Identified (NGO/Trust/ULB) give name and details.	Will be identified in consultation with Govt. Authorities		
11	Please attached agreement with implementing agency	Will submits at appropriate stage		

B. CER Activities Proposed: (please propose as per the suggested list given in table below)

Sr. No.	Description	Details No		
1	Any issues raised during the public hearing, social			
	need assessment, R&R plan, EMP, etc			
2	If Yes Please give details	Not applicable		
3	CER activities proposed to be from suggested	We propose to undertake few of the		
	activities as infrastructure creation for drinking	following CER activities:		
	water supply, sanitation, health, education, skill	CCTV cameras in school &		
	development, roads, cross drains, electrification	Hospital, Sanitation, Education, skill		
	including solar power, solid waste management	development, Renewal Energy		
	facilities, scientific support and awareness to local	Generation, Plantation, Air quality		
	farmers to increase yield of crop and fodder, rain	monitoring etc in Rural areas in		
	water harvesting, soil moisture conservation	consultation with Govt. Authorities.		
	works, avenue plantation, plantation in			

	community areas, community level sewage treatment plant, solid waste (composter or Biogas plants), air quality monitoring, research activities on environmental aspects, training programmes on waste management including skill development, studies related to environmental aspects for town/city/village, pilot projects on clean energy/environment, etc	
4	Consent of implementing agency (NGO etc.) and local authority to accept the CER in case of environmental infrastructure project	
5	Year wise activity indicating the detail of plan and cost (as applicable for duration of the project) attach separate sheet with Gnat Chart which will be useful for monitoring.	
	First Year (indicate year)	Rs. 1 Crore
	Second Year	Rs. 1.5 Crores
	Third Year	Rs. 2 Crores

We undertake to complete the work with our CER commitment as per this plan.

and Utentica

(Signature of Project Proponent)

Place: Mumbai

Date:4th December 2018

INDUSTRIAL MINERALS AND CHEMICAL COMPANY PVT. LTD.

Corporate Identity Number: U24100MH1968PTC014142

Tel.: +91 22 6629 4000 • Fax: +91 22 6610 0520 • E-mail: trilsec@tata.com Registered Office: Elphinstone Building, 2nd Floor, 10 Veer Nariman Road, Fort, Mumbai 400 001

7th Junhary 2019

To, The District Collector, Thane Collector Office, Court Naka, Thane

Subject

Contribution towards CER for the "IMCC IT PARK" on plot bearing Plot No. 23, 23 (PT), 24 & 24 (PT), TTC Industrial Area, MIDC- Mahape, Dist. -

Thane, Maharashtra.

Reference

Office Memorandum regarding Corporate Environment Responsibility (CER) dt. 1st May 2018 by Ministry of Environment, Forest and Climate Change

(MoEF & CC), New Delhi.

Respected Sir,

With reference to above mentioned subject, we are developing a IMCC IT PARK development project at plot bearing Plot No. 23, 23 (PT), 24 & 24 (PT), TTC Industrial Area, MIDC- Mahape, Dist. - Thane, Maharashtra that is under process for Environmental Clearance NOC.

As per the guidelines given by the MoEF & CC we are required to provide upto 1.5% of the Capital Investment towards CER. As per the circular, District Collector can add or delete activities as per the requirement of the District for CER.

We have identified certain activities to be carried out in immediate neighborhood which when implemented shall be beneficial to the environment and the general public at large.

The activities are broadly classified under the following heads -

1. CCTV Cameras in School & Hospital

2. Sanitation, Education, Renewal Energy Generation

3. Plantation, Air Quality Monitoring etc

We intend to spend approximately Rs. 4.5 Crores on the above activities detailed as below -

Sr. No.	Description	Amount (Rs in Crs)
1	CCTV Cameras in School & Hospital	1.00
2 -	Sanitation, Education & Renewal Energy Generation	2.50
3	Plantation, Air Quality Monitoring etc	1.00
	Tôtal Amount (Excl. Taxes)	4.50

We request you to kindly evaluate the above plan and grant your consent to undertake these activities under CER,

Thanking you,

Yours Faithfully,

For IMCC Ltd.

S.S.Mhade

Authorized Signatory

अति विशेष

MAHARASHTRA INDUSTRIAL DEVELOPMENT CORPORATION

(A Government of Maharashtra Undertaking)



No.EE/SPA/23, 23 Part, 24 & 24 Part/ D35970 /of 2019, Office of the Executive Engineer & Special Planning Authority, MIDC Dn. No. II Mahape. Date:-10/10/2019.

To, M/s. Industrial Mineral and Chemical Company Pvt. Ltd. Plot No. 23, 23 Part, 24 & 24 Part, TTC Industrial Area, Rabale Navi-Mumbai.

Sub: COMMENCEMENT CERTIFICATE

Sir,

With reference to your architect's online submission through SWC vide tracking I.D. No. SWC/14/521/20190909/656522 & complied on 07/10/2019 for grant to sanction of commencement certificate to carry out development work and Building Permit under section 45 of MR&T.P. Act, 1966 to erect Proposed Construction of Factory Building on Plot No. 23, 23 Part, 24 & 24 Part in T.T.C. Indl. Area, the commencement/ Building permit is granted subject to the following condition & for total B.U.A. as per the approval to the plans attached.

- 1. The land vacated in consequence of the enforcement of the set-back rule PART of the public street.
- 2. No new building or PART thereof shall be occupied or allowed to be occupied or use or permitted to be used by any person until occupancy permission has been granted.
- 3. The commencement certificate/building permit shall remain valid period of one year commencing from the date of its issue.
- 4. This permission does not entitle you to develop the land which does not vest in you.
- 5. Minimum two trees in plots of 200.00 sqm. & such No. of trees at the rate of one tree per 100.00 sqm. for plots more than 200.00 sqm. in area shall be planted & protected.
- 6. In case of group housing, minimum two trees per tenement shall be planted and protected.
- 7. The PARTy should inform the commencement of work as per the approval issued by this office.
- 8. Temporary labour camps, Toilet blocks & Water tanks within the site are allowed only during the phase of construction period of 2 years only.
- 9. The work of construction of temporary structure shall be executed under qualified structural engineer/Architect.
- 10. Allottee has to pay temporary construction fees at the rate of Rs. 50/- per Sqm. of such covered area of temporary structures.
- 11. Equal amounts as fees should be paid as deposit, which will be refundable at the end of the two years, or on completion of project whichever is earlier after removal of by the Allottee / Licensee / Lessee / Owner.
- 12. Failure to remove such temporary sheds will be liable for forfeiture of the deposit and any such failure continuing beyond stipulated period shall be liable for imposition of penalty which will be 3 times the rate of Rs. 50/- per Sqm.
- 13. It is requested to kindly submit letter of Intent (LOI) as per IT Policy & environmental clearance as per Environmental Policy.

Your's faithfully posts
Maruti S

Col. - 18 - 6-coursed of Anabase 20.

Maruti S

Kalkutaki

Fig. 1-1 - 19 - 6-coursed of Anabase 20.

Kalkutaki

Fig. 1-1 - 6-coursed of Anabase 20.

Fig. 1-1 - 6-

Copy submitted to:

- 1. The Collector, District Thane, for information.
- 2. The Municipal Commissioner, N.M.M.C. for information.
- 3. The Chief Fire Officer, MIDC, Andheri for information.

Copy f.w.c.'s to

- 1. The Regional Officer, MIDC Mahape, for information.
- 2. Architect M/s. Bhaskar S. Yamasanwar for information & further needful please.

MAHARASHTRA INDUSTRIAL DEVELOPMENT CORPORATION

(A Government of Maharashtra Undertaking)



No EE/SPA/23, 23 Part, 24 & 24 Part / D35970 /of 2019.
Office of the Executive Engineer,
MIDC Dn. II, Mahape, Navi Mumbai.
Date: - 10/10/2019.

To, M/s. Industrial Mineral and Chemical Company Pvt. Ltd. Plot No. 23, 23 Part, 24 & 24 Part TTC Industrial Area, Rabale Navi-Mumbai.

Sub:-TTC Industrial Area.

Plan Approval for proposed Fresh Building plan on Plot No.

23, 23 Part, 24 & 24 Part in TTC Industrial Area.

Ref.:- 1. Tracking Id: SWC/14/521/20190909/656522. Complied on 07.10.2019.

Dear Sir,

You have submitted application for Approval to Building Plan for proposed structure. Above applications are examined and following approvals are hereby granted...

A] Building Plan Approval

Since you have paid following

I) Development charges, amounting to Rs. 1,31,05,597.82 vide receipt no. MCH/6936 dt.09/09/2019 & MCH/7267 dt. 03/10/2019 Labour Cess amounting to Rs. 1,69,61,780.00 vide receipt no. MCH/6936 dt.09/09/2019 & MCH/7267 dt. 03/10/2019 & Scrutiny fees amounting to Rs. 1,50,000.00 vide receipt no. MCH/6936 dt.09/09/2019 & MCH/7267 dt. 03/10/2019, Fire protection charges Rs. 1,05,27,513.50 vide receipt no. MCH/6936 dt.09/09/2019 & MCH/7267 dt. 03/10/2019.

The set of plans, received from you vide your letter cited above, is hereby approved subject to acceptance and follow up of following conditions by you.

- You had submitted plans and drawings for <u>2099.72</u> m² of plinth area for the plot area of <u>192320.00</u> m², at present this office has approved plans for total up to date <u>38208.74</u> m². of built up area. This office has approved <u>01</u> Nos. of drawing details of which are mentioned on the accompanying statement.
- 2) In addition, to this approval the plot holder shall obtain approval for plans from other requisite authorities as per necessity, such as from :-

The building plans needs to be got approved from:

- i) Directorate of Industrial Safety & Health.
- ii) Any other Govt. authorities which may be mandatory.

Certificate copies of plans along with a letter for approval from the above authorities in triplicate shall be submitted/to the DE & SPA, before starting the work.

This building plan approval is with respect to planning point of view and in accordance to MIDC's Development Control Rules, since MIDC is Special Planning Authority (SPA) for this Area.

- 3. In case of approval to the modified plans, The original approval to the drawings granted vide letter No. Nil from the Office Executive Engineer MIDC Dn. II, Mahape is treated as cancelled as the drawings approved now supersedes the previously approved drawings. You are requestyed to return the above cancelled drawings to this office for records and cancellation.
- 4. You will obtain Environment Clearance Certificate before Commencement of any construction activities, if applicable to their project as per the notification issued by MoEF, Govt. of India vide Notification issued by MoEF, New Delhi dtd.14. 09. 2006 and its subsequent amendments'.
- 5. You are requested to submit certified copies of above approvals from the concerned authorities to this office, in triplicate before any work is started OR within three months from the date of issue of this letter whichever is earlier.
- 6. For the sanitary block, overhead water storage tank shall be provided at the rate of 500 liter per W.C. or Urinal.
- 7. For necessary approach road to the plot from the edges of MIDC. Road, 900 mm dia CD works or a slab drain of required span and size shall be provided.
- 8. Temporary structures shall not be allowed except to during construction period (after obtaining prior approval from Executive Engineer.) and the same shall be demolished immediately after building work is completed.
- 9. During the period of construction, stacking of materials shall be done only in the area of plot allotted. In no case, material be stacked along MIDC, road land width/open plot area.
- 10. The marks demarcating boundary of the plot shall be preserved properly and kept in good condition and shown to dePARTment staff as and when required.
- 11. No tube well, bore well or open well shall be dug.
- 12. Plans for any future additions, alterations or extensions will have to be get approved from this office, as well as from concerned competent authority.
- 13. The present approval to the plans does not pertain to approval to the structural design, RCC members, foundations etc. It is only locational approval to the layout of various structures & floors with reference to the plot, in accordance to MIDC DCR.
- 14. In case any power line is passing through the plot, the plot holder should approach MSEDCL and obtain their letter specifying the vertical and horizontal clearance to be left and plan his structures accordingly.
- 15. The compound wall gate should open inside the plot and if the plot is facing on two or more sides of the road then gate shall be located at least 15 m. away from the corner of junction or roads.
- 16. Plot holders shall make his own arrangement for 24 hours of storage of water, as uninterrupted water supply cannot be guaranteed.
- 17. In case, water stream/ nallah is flowing through the allotted plot, the plot holder has to ensure that the maximum quantity of rain water that flows at the point of entry of stream is allowed to flow uninterruptedly through the plot and upto the point of out flow of the original stream. The points of entry and exit of the natural stream shall not be changed. The detailed plans section and design

- 18. for allowing maximum expected discharge of rain water through the plot have to be furnished to this office and no filling of plot and diversion of nalla is allowed unless a written permission is obtained from the Executive Engineer/SPA.
- 19. This permission stands cancelled, if no construction work is started within twelve months from the date of issue of this letter or the date given in the agreement to lease to start construction work whichever is earlier. The date of starting construction work and date of completion shall be informed to the Executive Engineer in charge immediately. The construction shall be completed within the given stipulated time limit as per the lease agreement.
- 20. Breach of any rules stipulated will render the plot -holder liable for action as provided in MIDC., Act 1961 (II of 1962 and regulations made there under) and also terms of lease agreement and schedule of penalties prescribed by the Corporation for this purpose.
- 21. This office is empowered to add, amend, vary or rescind any provisions of Building Rules & regulations from time to time as it may deem fit, and the plot-holder has to be abide by these rules and regulations.
- 22. As soon as the building work is completed, the plot-holder shall approach to the concerned Deputy Engineer/Executive Engineer, to get the work verified and building shall not be occupied unless building completion certificate and occupancy certificate is obtained from this office.
- 23. The plot-holder within a period of one year from the date of agreement to please, shall plant at least one tree per 100 Sq. m. of plot area along the periphery of the plot. In addition, he shall also plant one tree per 15 m. on the frontage of road or PART thereof inside the plot and maintain the trees so planted in good condition throughout the period of agreement to lease.
- 24. The basement if provided is to be used only for storage purpose. No. manufacturing activates are allowed, similarly toilet is not allowed at the basements.
- 25. The Name and plot number shall be displayed at main entrance of plot.
- 26. The plot holder shall construct ETP as per consent of MPCB & treat & dispose effluent as per MPCB Consent to establish & operate.
- 27. The plot holder shall ensure that, the foundation of the building / structure shall rest on the firm strata and not on made up / filled ground. The Architect and structural consultant appointed by the owner will be solely responsible for this condition.
- 28. MIDC issues permission for development of plots which are situated on river banks, adhering to the contents of the River Policy dt. 13th July 2009 and as per category of Industries. PIL No. 17 of 2011 is filed against this policy at the Hon'ble High Court Bombay. It is clarified that, grant of any permission by the MIDC to any new industry in industrial estate situated on river banks will be subject to any further orders which may be passed by Hon'ble High Court, Bombay under PIL No. 17 of 2011.
- 29. It is requested to kindly submit letter of Intent (LOI) as per IT Policy & environmental clearance as per Environmental Policy.

B] Drainage

i) Drainage Plan Approval (Internal Works)

The set of plans in triplicate received along with the letter under reference for the above work is scrutinized the proposal is approved subject to condition as follows:

The work of internal and external water supply and sanitary fittings etc for the above building shall be carried out through the a licensed plumber registered at local authority or of Environmental Engineering DePARTment, or Govt. of Maharashtra.

- 1) The work should be carried out as per specifications confirming to I.S.S. In case they are not covered under I.S.S. then standard practice allowed by Municipal Corporation / or Local Council shall be followed.
- 2) The wastewater from water closets and urinals shall be passed through a septic tank of standard design.
- 3) The present approval to the plans does not pertain to the design of septic tank, effluent treatment plant etc. It is only location approval to these structures with reference to the plot.
- 4) You will be allowed to join your effluent to MIDC's common effluent collection system only after obtaining of necessary N.O.C. from M.P.C. Board and actual commissioning of pretreatment activity the factory effluent will be allowed to connect to MIDC system
- 5) Overhead water tank shall be provided at the rate of 500 Litters per W.C./ Urinal provided.
- 6) The waste water from the closets and Urinals shall be passed through the septic tanks, which is to be adequate to meet the requirements of the persons working in the factory and process waste if any, prior to septic tank in series with suitable size of 100 mm dia sewer trap, inspection chamber with 80 mm dia vent pipe shall be provided.
- 7) All vent pipes shall be minimum 80 mm dia size.
- 8) All rain water down take pipes shall be minimum 100 mm dia and should be provided at the rate of 1 Nos. Per 25 Sq. m. of roof area.
- 9) All S.W. pipes shall be minimum of 150 mm dia size.
- 10) It should be seen that no overflow of water from the soak pit or any process waste enters in to adjoining property or road.
- 11) Rain water pipes are not to be connected to underground effluent collection system. Separate drainage system shall be provided for collection of Industrial and Domestic wastes. Manholes shall be provided at the end of collection system with arrangements for measurement of the flow.
- 12) In case any of the requirements, stated as above is violated by the plot holder then he is liable for disconnection of water supply and is liable for action provided under\ MIDC., Act and various regulations and as per provision in the lease agreement.
- 13) The completion of work as per above requirements, it shall be jointly, inspected by the concerned Deputy. Engineer, of MIDC and your representative who has designed and executed work, without which drainage completion certificate will not be issued.

14) The waste water after treatment shall be soaked in a soak pit, if sewer line is not available for the plot; whereas if effluent collection system, of MIDC is functioning, then effluent shall be connected to the same after getting drainage plans approved from this office. The effluent shall be out letted only after pretreatment confirming to the standards stipulated by Maharashtra Pollution Control Board of Govt. of Maharashtra and after obtaining their consent under water Act 1974, Air Act 1981, & Hazardous waste Rules 2008 and subsequent amendments.

Thanking you,

Yours faithfully, a clicated to the control of the

- **DA:-** 1. One Statement showing details of drawings and built up area approved.
 - 2. Copy of approved drawings/plans.

Copy submitted to

- > The collector, District Thane, thane for information.
- ➤ The Chief Fire officer , MIDC, Andheri, Mumbai-93.
- > The Municipal Commissioner, NNMC for information.
- > The Regional Officer, MIDC, Mahape information.

 Architect M/s Bhaskar S. Yamasanwar for information & further needful please.
- ➤ Guard File.

MAHARASHTRA INDUSTRIAL DEVELOPMENT CORPORATION

(A Government of Maharashtra Undertaking)

The statement is accompaniment to letter No.EE/SPA /23, 23 Part, 24 & 24 Part / D35970/ 2019, Dated. 10 /10/2019. issued by M.I.D.C. addressed to for Industrial Mineral and Chemical Company Pvt. Ltd. Plot No. 23, 23 Part, 24 & 24 Part in TTC Industrial Area.

M/s.

- 1) Fresh Plans:-
- 2) Allottees Name: M/s. Industrial Mineral and Chemical Company Pvt. Ltd., Plot No. 23, 23 Part, 24 & 24 Part in TTC Industrial Area.

Sr. No.	Drawing No. &Date	Name of Architects	Description	Stilt Area Sqm.	Podium-1	Podium-2	Podium-3	Podium-4	1 st Floor Area in sqm	2 nd Floor Area in sqm	3 rd Floor Plan
1	2	3	4	5	6	7	8	9	10	11	12
2.	2.0 Nos	M/s. Bhaskar S.	Now proposed:-	2099.72	24.67	59.33	59.40	59.40	4560.58	4560.58	4271.39
		Yamasanwar for Team one Architects (India)	Plan showing Stilt Floor Plan, podium 1,2,3 & 4, 1 st , 2 ^{nd,} 3 rd , 4 th ,	(3233.96							
		Pvt. Ltd. LIC No.	5 th ,6 th ,7 th & 8 th Floor Plan, Front	Free of FSI)							
		CA/88/11886.	Elevation, Area Diagram, Section,								
			Side Elevation, Layout Plan, Area								
			Calculation, Area Statement.	4th El Di	Eth El	Cth El	7th El	Oth El			
				4 th Floor Plan	5 th Floor	6 th Floor	7 th Floor	8 th Floor			T-4-1
					Plan	Plan	Plan	Plan			Total
		<u>I</u>	<u>J</u>	4560.58	4560.58	4560.58	4271.39	4560.58			38208.74
			Grant Total-				38208.74	m2			

Area of the plot . = 192320.00 m2
Less 10% for recerational Area = (-) 19232.00 m2
Net Plot Area = 173088.00 m2
Plinth Area = 2099.72

Ground coverage . = 5333.68 / 173088.00 = 0.03 < 0.50O.K.

Total Built -up area = 38208.74 m2

FSI consumed = 38208.74/ 173088.00 = 0.22 < 1.00 O.K.



Digitally signed by Maruti S Kalkutaki
DN: C=IN, o=Government Of Maharashtra,
ou=Maharashtra Industrial Development
Corporation, postalCode=400710, st=Maharashtra,
25.4.20=Dc360646667666782454655322=7bf41d358
bbb50b8d394cb81578ee5a7536,
25.4.4.5=03100281587D7484147508654578598899
DE84527D210034584D18E2DA6EFE54E0387,
serialNumber=e6228485b2cf184491b5878478ca1d
e0837059ccef209acd386016909e6a20, cn=Maruti S

Executive Engineer & SPA, MIDC Division No. II, Mahape.

MAHARASHTRA INDUSTRIAL DEVELOPMENT CORPORATION

(A Government of Maharashtra Undertaking)

No EE/MHP-2/ /of 20 Office of the Executive Engineer MIDC Dn No.-2, Mahape,... Mahape Date: 10 112-120 20

To,
M/s Industrial Mineral and Chemical Pvt. Ltd..,
Plot No. 23, 23 Part, 24 & 24 Part,
Rabale, TTC Industrial Area,
Navi Mumbai

Sub: - TTC Industrial Area.....Revalidation of approved Building Plan of factory building on Plot No. 23, 23 Part, 24 & 24

Part.

Ref: - 1) Your letter dt.14.09.2020.

Dear Sir,

With reference to your application for REVALIDATION of the approved building plan of Factory building on Plot No. 23, 23 Part, 24 & 24 Part, it is inform you that the building plans approved under this office letter No. EE&SPA/MHP(C)/ 23, 23 Part, 24 & 24 Part /D-35970 Dt. 10.10.2019 is validated for further One Year from the date of issue of earlier approval letter. "The terms & conditions of letter No. EE&SPA/MHP(C)/ 23, 23 Part, 24 & 24 Part /D-35970 Dt. 10.10.2019 will remain unchanged."

Thanking you.

Yours faithfully

Executive Engineer & Special Planning Authority MIDC Dn II (Civil), Mahape

Copy submitted to:

1. The Dy. Assessor & Collector, N.M.M.C., Rabale for information.

2. Chief Fire Officer, MIDC, Andheri, Mumbai for information

Copy f.w.c.'s to

3. The Regional Officer, MIDC Mahape, for information.

4. Architect, M/s. Team ONE Architects (I) Pvt. Ltd..

MCC-Bldg. N. I Revalidation of

MAHARASHTRA INDUSTRIAL DEVELOPMENT CORPORATION

(A Government of Maharashtra Undertaking)



No.EE/MHP-II/IFMS/ E75896 /of2021 Office of the Executive Engineer; MIDC, Division No.2 Mahape - Navi Mumbai. Date : 14/12/2021.

To.

M/s. Industrial Mineral and Chemical Company Pvt. Ltd., Plot No. 23, 23 Part, 24 & 24 Part, TTC Industrial Area, Navi Mumbai.

> Sub :- TTC Industrial Area..... Revalidation of approved building plan of factory building on plot No. 23, 23 Part, 24 & 24 Part.

Ref: 1) Plan Approval issued vide No. EE/SPA/MHP(C)/ 23, 23 Part, 24 & 24 Part/D-35970, dtd. 10/10/2019.

2) Your letter dtd. 14/09/2020

3) This office letter No. D27721, dtd. 10/12/2020.

4) Your letter dtd. 08/10/2021.

5) Area Manager, MIDC, vide letter No. MIDC/ROMHP/TTC/3189, dtd. 10/12/2021.

Sir.

This office has accorded the approval to plans on this plot, vide letter under reference at Sr. No. (1). On request from your side, vide letter under reference at Sr. No. (2), this office vide letter at Sr. No. (3), has further validated the Commencement Certificate for the period of one year i.e. from 11/10/2020 to 10/10/2021.

The corporation has granted the extension for development period of 20 months i.e. upto 08/05/2023, which communicated by Area Manager, vide letter under reference at Sr. No. (5), accordingly. As per your request vide letter under reference at Sr. No. (4), REVALIDATION for further period of approved building plan vide letter under reference at Sr. No. (1) of factory building on plot No. 23, 23 Part, 24 & 24 Part, from 11/10/2021 to 10/10/2022 is considered herewith. "The terms & conditions of letter No. EE /SPA/MHP(C)/ 23, 23 Part, 24 & 24 Part/D-35970, dtd. 10/10/2019 will remain unchanged".

Thanking you,

Rajaram

Rathod

Yours faithfully,

Executive Engineer & Special Planning Authority MIDC, Dn.-II, Mahape.

Copy submitted to :-

1. The Dy. Assessor & Collector, NMMC, Rabale, for information.

2. Chief Fire Officer, MIDC, Andheri, Mumbai for information. Copy f.w.c.'s to :-

1. The Regional Officer, MIDC, Mahape for information.

2. Architect M/s. Team ONE Architects (I) Pvt. Ltd.



MAHARASHTRA POLLUTION CONTROL BOARD

Tel: 24010706/24010437

Fax: 24023516

Website: http://mpcb.gov.in Email: cac-cell@mpcb.gov.in



Kalpataru Point, 2nd and 4th floor, Opp. Cine Planet Cinema, Near Sion Circle, Sion (E), Mumbai-400022

No:- Format1.0/CAC-CELL/UAN No.0000085051/CE-2009000093

Date: 02 09 2020

M/s. INDUSTRIAL MINERALS & CHEMICAL CO. PVT. LTD., "IMCC IT Park" Plot No.23, 23 (PT.) 24 & 24(PT), Plot No.23, 23 (PT.) 24 & 24(PT), TTC Industrial Area, MIDC, Mahape, Navi Mumbai, Dist.Thane.

> Sub: Consent to Establish for proposed Commercial Development project under L.S.I Red Category

Ref: 1. Environment Clearance accorded vide letter SEIAA-EC-0000002300 dtd. 15/01/2020.

2. Minutes of Consent Appraisal Committee meeting held on 04/08/2020.

Your application NO. MPCB-CONSENT-0000085051

For: Grant of Consent to Establish under Section 25 of the Water (Prevention & Control of Pollution) Act, 1974 & under Section 21 of the Air (Prevention & Control of Pollution) Act, 1981 and Authorization / Renewal of Authorization under Rule 6 of the Hazardous & Other Wastes (Management & Transboundry Movement) Rules 2016 is considered and the consent is hereby granted subject to the following terms and conditions and as detailed in the schedule I,II,III & IV annexed to this order:

- The Consent to Establish is granted for a period upto commissioning of project
- 2. The capital investment of the project is Rs.415.75 Crs. (As per C.A Certificate submitted by industry).
- 3. The Consent to Establish is valid for Proposed Commercial Development project named as M/s. INDUSTRIAL MINERALS & CHEMICAL CO. PVT. LTD., "IMCC IT Park" Plot No.23, 23 (PT.) 24 & 24(PT), Plot No.23, 23 (PT.) 24 & 24(PT), TTC Industrial Area, MIDC, Mahape, Navi Mumbai, Dist.Thane. on Total Plot Area of 1,92,320 SqMtrs for construction BUA of 65,033.75 SqMtrs as per EC granted dated 15/01/2020 including utilities and services

Sr.No	Permission Obtained	Plot Area (SqMtr)	BUA (SqMtr)
1	EC- dtd. 15/01/2020	192320.00	65033.75

Conditions under Water (P&CP), 1974 Act for discharge of effluent:

Sr N	o Description	Permitted (in CMD)	Standar	rds to Disposa
1.	Trade effluent	Nil	Nil	Nil
		The state of the s	10000	1,000
		(1		
		\//		
		~		

M/s. INDUSTRIAL MINERALS & CHEMICAL CO. PVT. LTD. "IMCC IT Park"/CE/UAN No.MPCB-CONSENT-0000085051

Page 1 of 8



Sr No	Description	Permitted	Standards to	Disposal
2.	Domestic effluent	219	As per Schedule - I	The treated effluent shall be 60% recycled for secondary purposes such as toilet flushing, air conditioning, cooling tower make up, firefighting etc. and remaining shall be connected to the sewerage system provided by local body

5. Conditions under Air (P& CP) Act, 1981 for air emissions:

Stack No.	Description of stack / source	Number of Stack	Standards to be achieved
S-1,S-2,S-3 D	G Sets 1500 KVA x 3	03	As per Schedule -II

6. Conditions under Solid Waste Rules, 2016:

Sr No	Type Of Waste	Quantity & UoM	Treatment	Disposal
1	Biodegradable waste	229 Kg/Day	Organic waste converter followed by Composting facility.	Used as Manure.
2	Non-Biodegradable waste	344 Kg/Day	Segregation	By Sale to Auth. Vendor
3	STP Sludge	33 Kg/Day	Filter press	Used as a Manure.
4	E- waste	344 Kg/M	Stored separately	By Sale to Auth. Vendor.

 Conditions under Hazardous & Other Wastes (M & T M) Rules 2016 for treatment and disposal of hazardous waste:

Sr No	Category No.	Quantity	UoM Treatment	Disposal
1	5.1 Used /spent oil	60	Ltr/A Storage	By sale to Auth. reprocessor.

- 8 This Board reserves the right to review, amend, suspend, revoke etc. this consent and the same shall be binding on the industry.
- 9 This consent should not be construed as exemption from obtaining necessary NOC/permission from any other Government agencies.
- 10 PP shall provide STP so as to achieve the treated domestic effluent standard for the parameter BOD-10 mg/lit.
- 11 The treated effluent shall be 60% recycled for secondary purposes such as toilet flushing, air conditioning, cooling tower make up, firefighting etc. and remaining shall be utilized on land for gardening.
- 12 PP shall install online monitoring system for BOD, TSS and flow at the outlet of STP with connectivity to MPCB Server.
- 13 PP shall submit BG of Rs. 25 Lakhs towards compliance of EC and Consent to Establish condition.
- 14 PP shall install organic waste digester along with composting facility/biodigester (biogas) with composting facility for the treatment of wet garbage.
- 15 PP shall obtain NOC from competent authority with reference to Thane creek flamingo sanctuary prior to commencement of the project and submit copy of the same to the Board Office.

M/s. INDUSTRIAL MINERALS & CHEMICAL CO. PVT. LTD. "IMCC IT Park"/CE/UAN No.MPCB-CONSENT-0000085051

Page 2 of 8



For and on behalf of the Maharashtra Pollution Control Board.

> (E. Ravendiran IAS), Member/Secretary

Received Consent fee of -

		Transaction/DR.No.	Date	Transaction Type
1	831500.00	5456976	26/12/2019 NE	FT

Copy to:

- 1. Regional Officer, MPCB, Navi Mumbai and Sub-Regional Officer, MPCB, Navi Mumbai
- They are directed to ensure the compliance of the consent conditions.
- 2. Chief Accounts Officer, MPCB, Sion, Mumbai

M/s. INDUSTRIAL MINERALS & CHEMICAL CO. PVT. LTD. "IMCC IT Park"/CE/UAN No.MPCB-CONSENT-0000085051

Page 3 of 8



SCHEDULE-I Terms & conditions for compliance of Water Pollution Control:

- A] As per your application, you have proposed to provide MBR based Sewage Treatment Plants (STPs) of combined capacity 295 CMD for treatment of domestic effluent of 219 CMD.
 - B] The Applicant shall operate the sewage treatment plant (STP) to treat the sewage so as to achieve the following standards prescribed by the Board or under EP Act, 1986 and Rules made there under from time to time, whichever is stringent.

Sr. No.	Parameters	Standards prescribed by Board
		Limiting Concentration in mg/l, except for pH
1.	BOD (3 days 27o C)	10
2.	Suspended Solids	20
3.	COD	50
4.	Residual Chlorine	1ppm

- C) The treated domestic effluent shall be 60% recycled for secondary purposes such as toilet flushing, air conditioning, cooling tower make up, firefighting etc. and remaining shall be utilized on land for gardening and connected to the sewerage system provided by local body.
- 2) The Board reserves its rights to review plans, specifications or other data relating to plant setup for the treatment of waterworks for the purification thereof & the system for the disposal of sewage or trade effluent or in connection with the grant of any consent conditions. The Applicant shall obtain prior consent of the Board to take steps to establish the unit or establish any treatment and disposal system or and extension or addition thereto.
- 3) The industry shall ensure replacement of pollution control system or its parts after expiry of its expected life as defined by manufacturer so as to ensure the compliance of standards and safety of the operation thereof.
- 4) The Applicant shall comply with the provisions of the Water (Prevention & Control of Pollution) Act,1974 and as amended, and other provisions as contained in the said act.

Sr. No.	Purpose for water consumed	Water consumption quantity (CMD)
1.	Industrial Cooling, spraying in mine pits or boiler feed	0.00
2.	Domestic purpose	247.00
3.	Processing whereby water gets polluted & pollutants are easily biodegradable	0.00
4.	Processing whereby water gets polluted & pollutants are not easily biodegradable and are toxic	0.00

5) The Applicant shall provide Specific Water Pollution control system as per the conditions of EP Act, 1986 and rule made there under from time to time.

M/s. INDUSTRIAL MINERALS & CHEMICAL CO. PVT. LTD. "IMCC IT Park"/CE/UAN No.MPCB-CONSENT-0000085051

Page 4 of 8



SCHEDULE-II Terms & conditions for compliance of Air Pollution Control:

 As per your application, you have proposed to provide the Air pollution control (APC)system and also proposed to erect following stack (s) and to observe the following fuel pattern-

Stack No.	Stack Attached To	APC System	Height in Mtrs.	Type of Fuel	Quantity & UoM
5-1	DG Set 1500 KVA	Acoustic enclosure	7.75	HSD	105 Ltr/Hr
S-2	DG Set 1500 KVA	Acoustic enclosure	7.75	HSD	105 Ltr/Hr
S-3	DG Set 1500 KVA	Acoustic enclosure	7.75	HSD	105 Ltr/Hr

The applicant shall operate and maintain above mentioned air pollution control system, so as to achieve the level of pollutants to the following standards.

Total Particular matter	Not to exceed	150 mg/Nm3

- 3) The Applicant shall obtain necessary prior permission for providing additional control equipment with necessary specifications and operation thereof or alteration or replacemenalteration well before its life come to an end or erection of new pollution control equipment.
- 4) The Board reserves its rights to vary all or any of the condition in the consent, if due to any technological improvement or otherwise such variation (including the change of any control equipment, other in whole or in part is necessary).
- 5) Conditions for utilities like Kitchen, Eating Places, Canteens:-
 - a) The kitchen shall be provided with exhaust system chimney with oil catcher connected to chimney through ducting.
 - b) The toilet shall be provided with exhaust system connected to chimney through ducting.
 - c) The air conditioner shall be vibration proof and the noise shall not exceed 68 dB(A).
 - d) The exhaust hot air from A.C. shall be attached to Chimney at least 5 mtrs. higher than the nearest tallest building through ducting and shall discharge into open air in such a way that no ruisance is caused to neighbors.



M/s. INDUSTRIAL MINERALS & CHEMICAL CO. PVT. LTD. "IMCC IT Park"/CE/UAN No.MPCB-CONSENT-0000085051

Page 5 of 8



SCHEDULE-IV

Conditions during construction phase

- A During construction phase, applicant shall provide temporary sewage and MSW treatment and disposal facility for the staff and worker quarters.
- During construction phase, the ambient air and noise quality shall be maintained and should be closely monitored through MoEF approved laboratory.
- Noise should be controlled to ensure that it does not exceed the prescribed standards. During night time the noise levels measured at the boundary of the building shall be restricted to the permissible levels to comply with the prevalent regulations.

General Conditions:

- 1 The applicant shall provide facility for collection of samples of sewage effluents, air emissions and hazardous waste to the Board staff at the terminal or designated points and shall pay to the Board for the services rendered in this behalf.
- The firm shall strictly comply with the Water (P&CP) Act, 1974, Air (P&CP) Act,1981 and Environmental Protection Act 1986 and Solid Waste Management Rule 2016, Noise (Pollution and Control) Rules, 2000 and E-Waste (Management & Handling Rule 2011.
- 3 Drainage system shall be provided for collection of sewage effluents. Terminal manholes shall be provided at the end of the collection system with arrangement for measuring the flow. No sewage shall be admitted in the pipes/sewers downstream of the terminal manholes. No sewage shall find its way other than in designed and provided collection system.
- 4 Vehicles hired for bringing construction material to the site should be in good condition and should conform to applicable air and noise emission standards and should be operated only during non-peak hours.
- 5 Conditions for D.G. Set
 - a) Noise from the D.G. Set should be controlled by providing an acoustic enclosure or by treating the room acoustically.
 - b) Industry should provide acoustic enclosure for control of noise. The acoustic enclosure/ acoustic treatment of the room should be designed for minimum 25 dB (A) insertion loss or for meeting the ambient noise standards, whichever is on higher side. A suitable exhaust muffler with insertion loss of 25 dB (A) shall also be provided. The measurement of insertion loss will be done at different points at 0.5 meters from acoustic enclosure/room and then average.
 - Industry should make efforts to bring down noise level due to DG set, outside industrial premises, within ambient noise requirements by proper sitting and control measures.
 - d) Installation of DG Set must be strictly in compliance with recommendations of DG Set manufacturer.
 - e) A proper routine and preventive maintenance procedure for DG set should be set and followed in consultation with the DG manufacturer which would help to prevent noise levels of DG set from deteriorating with use.
 - f) D.G. Set shall be operated only in case of power failure.
 - g) The applicant should not cause any nuisance in the surrounding area due to operation of D.G. Set.
 - h) The applicant shall comply with the notification of MoEFCC, India on Environment Protection) second Amendment Rules vide GSR 371(E) dated 17.05.2002 and its amendments regarding noise limit for generator sets run with diesel.

M/s. INDUSTRIAL MINERALS & CHEMICAL CO. PVT. LTD. "IMCC IT Park"/CE/UAN No.MPCB-CONSENT-0000085051

Page 7 of 8



Maharashtra Pollution Control Board 5f4f786ca6b21f06f7f1b356

- Solid Waste The applicant shall provide onsite municipal solid waste processing system & shall comply with Solid Waste Management Rule 2016 & E-Waste (M & H) Rule 2011.
- 7 Affidavit undertaking in respect of no change in the status of consent conditions and compliance of the consent conditions the draft can be downloaded from the official web site of the MPCB.
- 8 Applicant shall submit official e-mail address and any change will be duly informed to the MPCB.
- 9 The treated sewage shall be disinfected using suitable disinfection method.
- 10 The firm shall submit to this office, the 30th day of September every year, the environment statement report for the financial year ending 31st march in the prescribed Form-V as per the provision of rule 14 of the Environmental (Protection) Second Amended rule 1992.
- 11 The applicant shall obtain Consent to Operate from Maharashtra Pollution Control Board before commissioning of the project.

M/s. INDUSTRIAL MINERALS & CHEMICAL CO. PVT. LTD. "IMCC IT Park"/CE/UAN No.MPCB-CONSENT-0000085051

Page 8 of 8

TATA HOUSING

APPLICATION FORM AND MEDICAL HEIGHT REPORT

pTo be filled by User/ contractor engaged in height work

(Mandatory for personnel working at height of 2 meter and above the ground or floor)

Seria	al No.: Urrs	Date of application:
It can		ssue unless cancelled/withdrawn earlier by the issuing authority. plication to THDCL EHS Coordinator. In case of loss of the pass, actical test again.
1. F	ull Name of applicant (Block letters):	Dilco singh
2. P	resent address: Ghomsmili	V
3. D	ate of birth, if available: . a loul 2	oup.
4. A	ge and Sex: 19 male	
5. H	eight and weight: 167 cm and 0	kg.
6. Tr	ade of the applicant: PT hee	Lone
7. N	ame of Contractor:	
8. Cc	ontract work order No. :	
9. De	escription of present Job: PTh e	Upne
alwa Equip trans	ys wear the safety helmet, safety shoes pment and tie the life line whenever wo	ove information furnished by me is true and correct. I shall , safety harness and other required Personal Protective orking at height. I shall not misuse the height pass issued to me or come to duty or work at height / depth under influence of s while on duty.
		Diku simol
Date	: 2/11/23	Signature and Name of the applicant
Back	ground check (by THDCL EHS Coordinat	cor):
1	Previous employer detail	
2	Total work experience (in months)	Irmorty
3	Height work experience (in months)	12 mouts
4	Awareness about hazards & risk related to height work (Y/N)	Yes
5	Awareness about control measures to be implemented (Y/N)	yes .
Date		gnature and Name of TRIL/PMC/Contractor EHS Coordinator

TATA HOUSING

APPLICATION FORM AND MEDICAL HEIGHT REPORT

MEDICAL & PHYSICAL TEST

MEDICAL EXAMINATION:

1	Blood pressure	Pre: \18/ Ag mm of Hg.	Post: 124/84 mm of Hg.
2	Pulse rate	Pre:/ minute 848	Post: Pu / minute
3	Flat foot	Y 0	00-1
4	Epilepsy		
5	Vertigo		
6	Limping gait	1 NIAN	
7	Colour blindness	+(-)	
8	Hearing test	14	
9	Vision test	1111	
10	Height Fobia	66	

PHYSICAL EXAMINATION:

(The above applicant has appeared at the following practical test conducted in presence of doctor, EHS Coordinator and contractor supervisor and the results are given below)

Sr. No.	Test activity/ observation	Pass/ Fail& Remark
1	Wearing of required PPE's properly and anchoring the safety harness to the static lifeline	Pasi
2	Walking freely on the horizontal ramp with confidence	Pan
3	General physique & reflexes	loger
4	Any other Notifiable observation	140)

Physical & Medical Fitness: FIT/ UNFIT

He has been issued a height pass bearing Sr. No. MN

If found Unfit mention reason:

Date & time of Medical Test:

Name and Signature of Medical Officer

Registration No. and seal

FORM XI

[SEE RULE 233(C)]

CERTIFICATE OF MEDICAL EXAMINATION

1. Certificate Serial No	Date CR JULA
2.Name Di Eu	
3. Identification marks: (1) Mobeon (1) hauf	moloon Heck
4. Father's Name 2 amburut Sings	
5. Sex. Malle	Daylord
7. Date of birth, if available of office and / o	or certificate age1.9
I hereby certify that I have personally examined (name) of	who is desirous of being age as nearly as can be ascertained
8. Reason for—	
(1) refusal of certificate	
Signature/Left hand Thumb impression of	Reg. No. 20 Senature with Seal Medical Inspector/C.M.O.
building workers	Medical Inspector/C.M.O.
Note: 1. Exact details of cause of physical disability should be abilities should also be stated if disability is stated.	e clearly stated. 2. functional/productive

Name of project: 7 a ta intellion purk Name of the contractor: NECPL



Environmental Consultancy & Laboratory

Lab.Gazetted by MoEF&CC-Govt. of India

Lab. Accredited by NABL - ISO/IEC 17025:2017 [TC-5600, Valid until 03.08.2024 in the field of Testing]

QCI-NABET Accredited EIA Consulting Organization STP/ETP/WTP Project Management Consultants

ISO 9001: 2015 ISO 45001: 2018

Lab: Survey No. 93/A, Conformity Hissa No.2 G.V.Brothers Bldg., Bata Compound, Khopat, Near Flower Valley, Thane (West) - 400 601, Maharashtra, India. Tele: +91 22 2547 49 07 / +91 22 2547 62 17 Email: lab@ultratech.in Visit us at: www.ultratech.in

TEST REPORT

ISSUED TO:INDUSTRIAL MINERAL & CHEMICAL COMPANY PVT LTD

Plot No.23 Part, MIDC Trans Thane Creek, Zone A,

Industrial Area, Village-Savli, Ghansoli,

NaviMumbai - 400710

SAMPLE PARTICULARS

Sampling Plan Ref. No.:

Sampling Procedure Sample Registration Date

Date of Sampling

Time of Sampling

Analysis Starting Date

Analysis Completion Date Sample Lab Code

Ambient Air Temperature

C-65/04-2023

UT/LQMS/SOP/AA01A 27/04/2023

25/04/2023

14:30 Hrs. to 22:30 Hrs. 27/04/2023

29/04/2023 UT/ELS/C-463/04-2023

28.5°C to 34.3 °C

REPORT NO.

UT/ELS/REPORT/C-010/07-2023 **ISSUE DATE** 03/07/2023

YOUR REF.

REF. DATE

5500015783 09/02/2020 Agreement dt.-01/07/2023

AMBIENT AIR QUALITY MONITORING

Location Code

Sample Location

Steel Yard 2

Collected By ULTRA-TECH

Height of Sampler 1.0 Meter Sampling Duration: 08 Hours

Relative Humidity: 53.0 % to 66.0 %

Sr. No.	Test Parameter	Test Method	Test Result	Unit
1.	Sulphur Dioxide (SO ₂)	IS 5182 (Part 02) : 2001	12	μg/m³
2.	Oxides of Nitrogen (NO _x)	IS 5182 (Part 06) : 2006	23	μg/m³
3.	Particulate Matter (PM ₁₀)	EPA/625/R-96/010a Method IO-2.1	76	μg/m³
4.	Particulate Matter (PM _{2.5})	IS 5182 (Part 24) : 2019	26	μg/m³
5.	Carbon Monoxide (CO) †	IS 5182 (Part 10): 1999	1.3	mg/m³

†: Sampling Period 1 Hr.

Remark/ Statement Conformity:

The parameters tested above are found to be within 24 hourly TWA of National Ambient Air Quality Monitoring Standard (NAAQMS), Part III- Section IV. NAAQMS is provided as Annexure-I for your reference.(Turnover to find Annexure)

Sampling	Instrument Used	Make & Model	Calibration Status
Equipment	Respirable Dust Sampler	Make - Polltech; Model -PEM-RDS 8NL; Sr. No .3313	Valid up to - 03/10/2023
Details	Fine Dust Sampler	Make - Polltech; Model - PEM ADS 2.5/10μ; Sr. No. 18213	Valid up to - 06/01/2024

Note:

- Samples were collected by following laboratory's SOP (UT/LQMS/SOP/AA01A) based on CPCB Guidelines National Ambient Air Quality Monitoring Series: NAAQMS/2003-04 and respective test methods.
- This test report refers only to the sample tested.
- Monitoring area coming under Residential areas and observed values are relevant to sample collected only.
- This test report may not be reproduced in part, without the permission of this laboratory.
- Any correction invalidates this test report.
- Weather was Sunny & Clear during sampling period.

END OF REPORT -

THANE (W) INDIA IN-400 60

CONSULTANC

For ULTRA-TECH.

Meghan Patil (Authorized Signatory)

Page 1 of 1

H.O.: Unit No. 224,225,206, Jai Commercial Complex, Eastern Express Highway, Opp. Cadbury Factory, Khopat, Thane (W) 400 601, Maharashtra, India. Tel: +91-22+2538 01 98 / 2545 03 72 / 2544 62 51 Email: sales@ultratech.in

Pune: +91-20-29525517 - pune@ultratech.in Kochi: +91-048-44011173 / +91-9895200526 - kochi@ultratech.in

Kolkata: +033-40089145 / +91-9674488198 - kolkata@ultratech.in

ANNEXURE-I

NATIONAL AMBIENT AIR QUALITY STANDARDS, PART III-SECTION IV The Gazette of India with Effect from Wednesday, November 18, 2009/KARTIKA 27, 1931

		Time National Ambient Air Quality Standards		ir Quality Standards	
Sr. No.	Pollutants	Weighted Average	Industrial, Residential, Rural and Other Area	Ecological Sensitive Area (Notified by Central Government	
0.1	C. I. I. D 1 (CO.) / . 2	Annual*	50	20	
01.	Sulphur Dioxide (SO ₂), μg/m ³	24 Hours**	80	80	
02.	0.11(N)(NO.)/	Annual*	40	30	
02.	Oxides of Nitrogen (NO _x), µg/m ³	24 Hours**	80	80	
03	Particulate Matter (PM ₁₀), μg/m ³	Annual*	60	60	
03		24 Hours**	100	100	
04	Particulate Matter (PM _{2.5}), μg/m ³	Annual*	40	40	
04.		24 Hours**	60	60	
05.	Contrar Managida (CO) may (m3	08 Hours*	02	02	
05.	Carbon Monoxide (CO), mg/m ³	01 Hours**	04	04	

^{*} Annual arithmetic mean of minimum 104 measurements in a year at a particular site taken twice a week 24 hourly at uniform intervals.

NOTE: Whenever and wherever monitoring results on two consecutive days of monitoring exceed the limits specified above for the respective category, it shall be considered adequate reason to institute regular or continuous monitoring and further

^{** 24} hourly or 8 hourly or 1 hourly monitored values, as applicable, shall be complied with 98% of the time in a year. 2% of the time, they may exceed the limits but not on two consecutive days of monitoring.



Environmental Consultancy & Laboratory

Lab.Gazetted by MoEF&CC-Govt. of India

Lab. Accredited by NABL - ISO/IEC 17025:2017 [TC-5600, Valid until 03.08.2024 in the field of Testing]

QCI-NABET Accredited EIA Consulting Organization STP/ETP/WTP Project Management Consultants

ISO 9001: 2015 ISO 45001: 2018

Lab: Survey No. 93/A, Conformity Hissa No.2 G.V.Brothers Bldg., Bata Compound, Khopat, Near Flower Valley, Thane (West) - 400 601, Maharashtra, India. Tele: +91 22 2547 49 07 / +91 22 2547 62 17 Email: lab@ultratech.in Visit us at: www.ultratech.in

TEST REPORT

ISSUED TO:INDUSTRIAL MINERAL & CHEMICAL COMPANY PVT LTD

Plot No.23 Part, MIDC Trans Thane Creek, Zone A,

Industrial Area, Village-Savli, Ghansoli,

NaviMumbai - 400710

REPORT NO.

UT/ELS/REPORT/C-011/07-2023

ISSUE DATE YOUR REF.

AMBIENT AIR QUALITY MONITORING

03/07/2023 5500015783

REF. DATE

09/02/2020 Agreement dt.-01/07/2023

SAMPLE PARTICULARS

Sampling Plan Ref. No.:

C-65/04-2023

UT/LQMS/SOP/AA01A

27/04/2023

Location Code Sample Location

Near Worker Rest Room

Sample Registration Date Date of Sampling Time of Sampling

Sampling Procedure

25/04/2023 to 26/04/2023 23:00 Hrs. to 07:00 Hrs.

Analysis Starting Date

27/04/2023

Collected By

ULTRA-TECH

Analysis Completion Date Sample Lab Code

29/04/2023

Height of Sampler Sampling Duration:

1.0 Meter 08 Hours

Ambient Air Temperature

UT/ELS/C-464/04-2023 27.8°C to 32.8 °C

Relative Humidity:

53.0 % to 65.0 %

Sr. No.	Test Parameter	Test Method	Test Result	Unit
1.	Sulphur Dioxide (SO ₂)	IS 5182 (Part 02) : 2001	15	μg/m³
2.	Oxides of Nitrogen (NO _x)	IS 5182 (Part 06) : 2006	25	μg/m³
3.	Particulate Matter (PM ₁₀)	EPA/625/R-96/010a Method IO-2.1	80	μg/m³
4.	Particulate Matter (PM _{2.5})	IS 5182 (Part 24) : 2019	30	μg/m³
5.	Carbon Monoxide (CO) †	IS 5182 (Part 10): 1999	1.5	mg/m³

†: Sampling Period 1 Hr.

Opinions / Interpretations:

The parameters tested above are found to be within 24 hourly TWA of National Ambient Air Quality Monitoring Standard (NAAQMS), Part III- Section IV. NAAQMS is provided as Annexure-I for your reference.(Turnover to find Annexure)

Sampling	Instrument Used	Make & Model	Calibration Status
Equipment	Respirable Dust Sampler	Make - Polltech; Model -PEM-RDS 8NL; Sr. No .3313	Valid up to - 03/10/2023
Details	Fine Dust Sampler	Make - Polltech; Model - PEM ADS 2.5/10μ; Sr. No. 18213	Valid up to - 06/01/2024

Note:

- Samples were collected by following laboratory's SOP (UT/LQMS/SOP/AA01A) based on CPCB Guidelines National Ambient Air Quality Monitoring Series: NAAQMS/2003-04 and respective test methods.
- This test report refers only to the sample tested.
- Monitoring area coming under Residential areas and observed values are relevant to sample collected only.
- This test report may not be reproduced in part, without the permission of this laboratory.
- Any correction invalidates this test report.
- Weather was Sunny & clear during sampling period.

END OF REPORT -

INDIA PIN-400 601

CONSULTANCY

For ULTRA-TECH.

Meghan Patil (Anthorized Signatory)

Page 1 of 1

H.O.: Unit No. 224,225,206, Jai Commercial Complex, Eastern Express Highway, Opp. Cadbury Factory, Khopat, Thane (W) 400 601, Maharashtra, India. Tel: +91-22+2538 01 98 / 2545 03 72 / 2544 62 51 Email: sales@ultratech.in

Pune: +91-20-29525517 - pune@ultratech.in Kochi: +91-048-44011173 / +91-9895200526 - kochi@ultratech.in

Kolkata: +033-40089145 / +91-9674488198 - kolkata@ultratech.in

ANNEXURE-I

NATIONAL AMBIENT AIR QUALITY STANDARDS, PART III-SECTION IV The Gazette of India with Effect from Wednesday, November 18, 2009/KARTIKA 27, 1931

I COMPANY	14	Time	ir Quality Standards	
Sr. No.	Pollutants	Weighted Average	Industrial, Residential, Rural and Other Area	Ecological Sensitive Area (Notified by Central Government)
01.	C. I. I	Annual*	50	20
01.	Sulphur Dioxide (SO ₂), μg/m ³	24 Hours**	80	80
02.	Oxides of Nitrogen (NO _x), μg/m ³	Annual*	40	30
02.		24 Hours**	80	80
03	Province Late Matter (DM) / 2	Annual*	60	60
03	Particulate Matter (PM ₁₀), μg/m ³	24 Hours**	100	100
0.4	Particulate Matter (DM) - /2	Annual*	40	40
04.	Particulate Matter (PM _{2.5}), μg/m ³	24 Hours**	60	60
05.	Carbon Manavida (CO) ma/m3	08 Hours*	02	02
03.	Carbon Monoxide (CO), mg/m ³	01 Hours**	04	04

^{*} Annual arithmetic mean of minimum 104 measurements in a year at a particular site taken twice a week 24 hourly at uniform intervals.

NOTE: Whenever and wherever monitoring results on two consecutive days of monitoring exceed the limits specified above for the respective category, it shall be considered adequate reason to institute regular or continuous monitoring and further

^{** 24} hourly or 8 hourly or 1 hourly monitored values, as applicable, shall be complied with 98% of the time in a year. 2% of the time, they may exceed the limits but not on two consecutive days of monitoring.



Environmental Consultancy & Laboratory

Lab.Gazetted by MoEF&CC-Govt. of India

Lab. Accredited by NABL - ISO/IEC 17025:2017 [TC-5600, Valid until 03.08.2024 in the field of Testing]

QCI-NABET Accredited EIA Consulting Organization STP/ETP/WTP Project Management Consultants

ISO 9001 : 2015 ISO 45001 : 2018

Lab: Survey No. 93/A, Conformity Hissa No.2 G.V.Brothers Bldg., Bata Compound, Khopat, Near Flower Valley, Thane (West) - 400 601, Maharashtra, India. Tele: +91 22 2547 49 07 / +91 22 2547 62 17 Email: lab@ultratech.in Visit us at: www.ultratech.in

TEST REPORT

ISSUED TO:INDUSTRIAL MINERAL & CHEMICAL COMPANY PVT LTD

Plot No.23 Part, MIDC Trans Thane Creek, Zone A,

Industrial Area, Village-Savli, Ghansoli,

NaviMumbai - 400710

REPORT NO. : UT/ELS/REPORT/C-012/07-2023

ISSUE DATE : 03/07/2023

YOUR REF. : 5500015783

REF. DATE: 09/02/2020 Agreement dt.-01/07/2023

: Near Project Site Office

SAMPLE PARTICULARS :

Sampling Plan Ref. No.:

: C-

C-65/04-2023

UT/LQMS/SOP/AA01A

Sample Registration Date

27/04/2023

Date of Sampling Time of Sampling

Sampling Procedure

26/04/2023 07:30 Hrs. to 15:30 Hrs.

Analysis Starting Date

27/04/2023

Analysis Completion Date Sample Lab Code Ambient Air Temperature 29/04/2023

: UT/ELS/C-465/04-2023 : 28.5°C to 34.3 °C Collected By

Location Code

Sample Location

Height of Sampler :

: ULTRA-TECH er : 1.0 Meter

: 03

Sampling Duration: 08 Hours

AMBIENT AIR QUALITY MONITORING

Relative Humidity: 53.0% to 68.0 %

Sr. No.	Test Parameter	Test Method	Test Result	Unit
1.	Sulphur Dioxide (SO ₂)	IS 5182 (Part 02) : 2001	11	μg/m³
2.	Oxides of Nitrogen (NO _x)	IS 5182 (Part 06) : 2006	22	μg/m³
3.	Particulate Matter (PM ₁₀)	EPA/625/R-96/010a Method IO-2.1	74	μg/m³
4.	Particulate Matter (PM _{2.5})	IS 5182 (Part 24): 2019	25	μg/m³
5.	Carbon Monoxide (CO) †	IS 5182 (Part 10): 1999	1.1	mg/m³

†: Sampling Period 1 Hr.

Opinions / Interpretations:

The parameters tested above are found to be within 24 hourly TWA of National Ambient Air Quality Monitoring Standard (NAAQMS), Part III- Section IV. NAAQMS is provided as Annexure-I for your reference.(Turnover to find Annexure)

Sampling	Instrument Used	Make & Model	Calibration Status
Equipment	Respirable Dust Sampler	Make - Polltech; Model -PEM-RDS 8NL; Sr. No .3313	Valid up to - 03/10/2023
Details	Fine Dust Sampler	Make - Polltech; Model - PEM ADS 2.5/10μ; Sr. No. 18213	Valid up to - 06/01/2024

Note:

- Samples were collected by following laboratory's SOP (UT/LQMS/SOP/AA01A) based on CPCB Guidelines National Ambient Air Quality Monitoring Series: NAAQMS/2003-04 and respective test methods.
- 2. This test report refers only to the sample tested.
- 3. Monitoring area coming under Residential areas and observed values are relevant to sample collected only.
- 4. This test report may not be reproduced in part, without the permission of this laboratory.
- 5. Any correction invalidates this test report.
- 6. Weather was Sunny during sampling period.

- END OF REPORT -

THANE (W) OF INDIA PIN-400 601 3

For ULTRA-TECH,

Meghan Patil Authorized Signatory)

Page 1 of 1

H.O.: Unit No. 224,225,206, Jai Commercial Complex, Eastern Express Highway, Opp. Cadbury Factory, Khopat, Thane (W) 400 601, Maharashtra, India.

Tel: +91-22+2538 01 98 / 2545 03 72 / 2544 62 51 Email: sales@ultratech.in

Pune: +91-20-29525517 - pune@ultratech.in Kochi: +91-048-44011173 / +91-9895200526 - kochi@ultratech.in

Kolkata: +033-40089145 / +91-9674488198 - kolkata@ultratech.in

ANNEXURE-I

NATIONAL AMBIENT AIR QUALITY STANDARDS, PART III-SECTION IV The Gazette of India with Effect from Wednesday, November 18, 2009/KARTIKA 27, 1931

		Time	National Ambient Air Quality Standards			
Sr. No.	Pollutants	Weighted Average	Industrial, Residential, Rural and Other Area	Ecological Sensitive Area (Notified by Central Government)		
0.1	C. I. I. D I. (00.) / . 2	Annual*	50	20		
01.	01. Sulphur Dioxide (SO ₂), μg/m ³	24 Hours**	80	80		
02.	0.:1	Annual*	40	30		
02.	Oxides of Nitrogen (NO _X), µg/m ³	24 Hours**	80	80		
03	P. di la Matta (PM) - (-3	Annual*	60	60		
03	Particulate Matter (PM ₁₀), μg/m ³	24 Hours**	100	100		
04.	David Law Martin CDM 2 - 4-3	Annual*	40	40		
04.	Particulate Matter (PM _{2.5}), μg/m ³	24 Hours**	60	60		
or.	Conhan Manavida (CO) ma /m3	08 Hours*	02	02		
05.	Carbon Monoxide (CO), mg/m ³	01 Hours**	04	04		

^{*} Annual arithmetic mean of minimum 104 measurements in a year at a particular site taken twice a week 24 hourly at uniform intervals.

NOTE: Whenever and wherever monitoring results on two consecutive days of monitoring exceed the limits specified above for the respective category, it shall be considered adequate reason to institute regular or continuous monitoring and further

^{** 24} hourly or 8 hourly or 1 hourly monitored values, as applicable, shall be complied with 98% of the time in a year. 2% of the time, they may exceed the limits but not on two consecutive days of monitoring.



Environmental Consultancy & Laboratory

Lab.Gazetted by MoEF&CC-Govt. of India

Lab. Accredited by NABL - ISO/IEC 17025:2017 [TC-5600, Valid until 03.08.2024 in the field of Testing]

QCI-NABET Accredited EIA Consulting Organization STP/ETP/WTP Project Management Consultants

ISO 9001: 2015 ISO 45001: 2018

Lab: Survey No. 93/A, Conformity Hissa No.2 G.V.Brothers Bldg., Bata Compound, Khopat, Near Flower Valley, Thane (West) - 400 601, Maharashtra, India. Tele: +91 22 2547 49 07 / +91 22 2547 62 17 Email: lab@ultratech.in Visit us at: www.ultratech.in

TEST REPORT

ISSUED TO:INDUSTRIAL MINERAL & CHEMICAL COMPANY PVT LTD

Plot No.23 Part, MIDC Trans Thane Creek, Zone A,

Industrial Area, Village-Savli, Ghansoli,

NaviMumbai - 400710

Date of Monitoring

SAMPLE PARTICULARS Sampling Plan Ref. No.

: C-65/04-2023 25/04/2023

REPORT NO. **ISSUE DATE**

UT/ELS/REPORT/C-013/07-2023 03/07/2023

YOUR REF.

5500015783

09/02/2020 Agreement dt.-01/07/2023

NOISE LEVEL QUALITY MONITORING

Sample Lab Code

REF. DATE

: UT/ELS/C-466/04-2023

Survey Done By

ULTRA-TECH

Sr.	Location	Noise Level Reading in dB(A)						
No.	Location	Time (Hrs)	Day dB(A)	Time (Hrs)	Night dB(A)			
01.	Near Main Gate	15:00 to 15:05	54.2	22:00 to 22:05	44.2			
02.	Project Site Office	15:10 to 15:15	53.8	22:10 to 22:15	43.6			
03.	At Safety Office Near Assembly Point	15:20 to 15:25	52.5	22:20 to 22:25	41.2			
04.	Steel Yard 1	15:30 to 15:35	53.3	22:30 to 22:35	43.7			
05.	Steel Yard 2	15:40 to 15:45	51.8	22:40 to 22:45	42.5			
06.	Workman Rest Room	15:50 to 15:55	52.6	22:50 to 22:55	41.3			

Opinions / Interpretations:

The Noise Pollution (Regulation And Control) Rules, 2000: Is Provided as Annexure II for Your Reference.

(Turnover to find Annexure).

Note:

- 1. Monitoring area coming under Residential Area.
- 2. Noise level monitored is an average for period as stated above, the permissible sound pressure level is to be determined with respect to the total time a workman is being exposed (continuously or a number of short term exposures per day) in Hrs.

Sampling Equipment	Instrument Used	Make & Model	Calibration Status
Details	Sound Level Meter	Make - Casella; Model - CEL-633C; Sr. no. 2382959	Valid up to - 11/12/2023

Note:

- 1. This test report refers only to the monitoring conducted.
- 2. This test report may not be reproduced in part, without the permission of this laboratory.

3. Any correction invalidates this test report.

- END OF REPORT -

For ULTRA-TECH.

Meghan Patil (Authorized Signatory)

Page 1 of 1

USULTANCY

H.O.: Unit No. 224,225,206, Jai Commercial Complex, Eastern Express Highway, Opp. Cadbury Factory, Khopat, Thane (W) 400 601, Maharashtra, India. Tel: +91-22+2538 01 98 / 2545 03 72 / 2544 62 51 Email: sales@ultratech.in

> Pune: +91-20-29525517 - pune@ultratech.in Kochi: +91-048-44011173 / +91-9895200526 - kochi@ultratech.in Kolkata: +033-40089145 / +91-9674488198 - kolkata@ultratech.in

ANNEXURE-II

THE NOISE POLLUTION (REGULATION AND CONTROL) RULES, 2000

(The Principal Rules were published in the Gazette of India, vide S.O. 123(E), dated 14.2.2000 and subsequently amended vide S.O. 1046(E), dated 22.11.2000, S.O. 1088(E), dated 11.10.2002, S.O. 1569 (E), dated 19.09.2006 and S.O. 50 (E) dated 11.01.2010 under the Environment (Protection) Act, 1986.)

SCHEDULE

(See rule 3(1) and 4(1))

Ambient Air Quality Standards in respect of Noise

Area Codo	Cotocom of Avec / Zone	Limits in 4B(A) Leq		
Area Code	Category of Area / Zone	Day Time	Night Time	
Α	Industrial Area	75	70	
В	Commercial Area	65	55	
С	Residential Area	55	45 40	
D	Silence Zone	50		

Note:

- 1. Day time shall mean from 6.00 a.m. to 10.00 p.m.
- 2. Night time shall mean from 10.00 p.m. to 6.00 a.m.
- 3. Silence zone is an area comprising not less than 100 meters around hospitals, educational institutions, courts, religious places or any other area which is declared as such by the competent authority.
- 4. Mixed categories of areas may be declared as one of the four above mentioned categories by the competent authority.
- * dB(A) Leq denotes the time weighted average of the level of sound in decibels on scale A which is relatable to human hearing.

A "decibel" is a unit in which noise is measured.

"A", in dB(A) Leq, denotes the frequency weighting in the measurement of noise and corresponds to frequency response characteristics of the human ear.

Leq: It is energy mean of the noise level over a specified period.

• CONSTRUCTION ACTIVITIES

The maximum noise levels near the construction site should be limited to 75 dB(A) Leq(5 min.) in industrial areas and to 65 dB(A) Leq(5 min.) in other areas.

• THE PERMISSIBLE LEVELS FOR NOISE EXPOSURE FOR WORK ZONE

(The Model Rules Of The Factories Act, 1948)

Peak sound pressure level in dB	Permitted number of impulses or impact/day
140	100
135	315
130	1000
125	3160
120	10000

Notes:

- 1. No exposure in excess of 140 dB peak sound pressure level is permitted.
- 2. For any peak sound pressure level falling in between any figure and the next higher or lower figure as indicated in column 1,the permitted number of impulses or impacts per day is to be determined by extrapolation on a proportionate basis.

Total time exposure (continuous or a number of short term exposures per day) in Hrs	Sound Pressure Level in dB(A)
8	90
4	93
2	96
1	99
1/2	102
1/8	108
1/16	111
1/32 (2 minutes) or less	114

Notes:

- 1. No exposure in excess of 115 dB(A) is to be permitted.
- 2. For any period of exposure falling in between any figure and the next higher or lower figure as indicated in column 1,the permissible sound pressure level is to be determined by extrapolation on a proportionate basis



Environmental Consultancy & Laboratory

Lab.Gazetted by MoEF&CC-Govt. of India

Lab. Accredited by NABL - ISO/IEC 17025:2017 [TC-5600, Valid until 03.08.2024 in the field of Testing]

QCI-NABET Accredited EIA Consulting Organization

STP/ETP/WTP Project Management Consultants

ISO 9001: 2015 ISO 45001: 2018

Lab: Survey No. 93/A, Conformity Hissa No.2 G.V.Brothers Bldg., Bata Compound, Khopat, Near Flower Valley, Thane (West) - 400 601, Maharashtra, India. Tele: +91 22 2547 49 07 / +91 22 2547 62 17 Email: lab@ultratech.in Visit us at: www.ultratech.in

TEST REPORT

ISSUED TO:INDUSTRIAL MINERAL & CHEMICAL COMPANY PVT LTD

Plot No.23 Part, MIDC Trans Thane Creek, Zone A,

Industrial Area, Village-Savli, Ghansoli,

NaviMumbai - 400710

REPORT NO.

UT/ELS/REPORT/C-014/07-2023

ISSUE DATE YOUR REF.

03/07/2023 5500015783

REF. DATE

09/02/2020 Agreement dt.-01/07/2023

SAMPLE PARTICULARS

Sampling Plan Ref. No.

Sampling Procedure :

Sample Registration Date Date & Time of Sampling

Analysis Starting Date

Analysis Completion Date

Sample Collected By Sample Lab Code

C-65/04-2023 UT/LQMS/SOP/W01A 27/04/2023

> 26/04/2023 at 11:00 Hrs. 27/04/2023 05/05/2023

: **ULTRA TECH** HT/FLS/C-467/04-2023 WATER SAMPLE ANALYSIS

Sample Type **Drinking Water**

Sample Location At Project Site Near Main Gate

Sample Quantity & **Packing Details**

2 L in Plastic Container and 100ml in

Sterile Corning Bottle.

Sr. No.	Test Parameter	Test Method	Test Result	Unit	Standard Limits
	PARAMETERS:-				[13 10300 . 2012]
1.	Turbidity	IS 3025 (Part 10) 1984	BDL[DL=0.1]	NTU	1
	PARAMETERS:-			10	1
2.	pH	IS 3025 (Part 11) 2022	7.1		6.5 - 8.5
3.	Electrical Conductivity	APHA 23rd Ed. 2510 B	166	μS/cm	0.0 - 0.0
4.	Total Dissolved Solids	IS 3025 (Part 16) 1984	108	mg/L	500
5.	Total Hardness as CaCO ₃	IS 3025 (Part 21) 2009	64	mg/L	200
6.	Total Alkalinity as CaCO₃	IS 3025 (Part 23) 1986	60	mg/L	200
7.	Phenolphthalein Alkalinity as CaCO ₃	IS 3025 (Part 23) 1986	BDL[DL=1]	mg/L	
8.	Sulphate as SO ₄ ² -	APHA 23rdEd. 4500- SO42- E	12	mg/L	200
9.	Phosphate as PO ₄ 3P	APHA 23rd Ed. 4500 P D E	BDL [DL=0.01]	mg/L	200
10.	Chlorides as Cl-	IS 3025 (Part 32) 1988	20	mg/L	250
11.	Ammonical Nitrogen as NH ₃ -N	APHA 23rd Ed. 4500- NH3- F	BDL [DL=0.01]	mg/L	0.5
12.	Nitrates as NO ₃ -N	IS 3025 (Part 34) 1988	0.5	mg/L	45
13.	Calcium Hardness as CaCO ₃	IS 3025 (Part 40) 1991	36	mg/L	43
14.	Calcium as Ca	IS 3025 (Part 40) 1991	14	mg/L	75
15.	Magnesium as Mg	IS 3025 (Part 46) 1994	7	mg/L	30
16.	Potassium as K	APHA 23rd Ed. 3500 K	0.9	mg/L	
17.	Sodium as Na	APHA 23rd Ed. 3500 Na	12	mg/L	
18.	Iron as Fe	IS 3025 (Part 53) 2003	BDL [DL=0.06]	mg/L	0.3
19.	Lead as Pb	IS 3025 (Part 47) 1994	BDL [DL=0.6]	mg/L	0.01
20.	Fluoride as F-	APHA 23rd Ed. 4500-F-B.D	BDL[DL=0.2]	mg/L	1.0
	OGICAL PARAMETERS:			mg/ L	1.0
21,	Total Coliform	IS 1622: 1981	BDL[DL=2]	MPN/100 ml	0
22.	F.Coli	IS 1622: 1981	BDL[DL=2]	MPN/100 ml	0
23.	E.Coli	IS 1622: 1981	Absent	- In 11/100 III	Absent
	DL - Detection Limit	The second secon	Hosene	DDI Deleven	Detection Limit

The given sample confirms with standard specifications wherever applicable as per IS 10500:2012 for above analyzed parameters.

PIN-400 60

CONSULTANC

Note:

1. Samples was collected using laboratory's SOP (UT/LQMS/SOP/W01A) based on CPCB's Guide Manual: Water & Wastewater Analysis, APHA 23rd Edition and IS3025 (Part 1).

2. This test report refers only to the sample tested.

3. This test report may not be reproduced in part, without the permission of this laboratory.

4. Any correction invalidates this test report

- END OF REPOR

Meghan Patil (Authorized Signatory)

Page 1 of 1

H.O.: Unit No. 224,225,206, Jai Commercial Complex, Eastern Express Highway, Opp. Cadbury Factory, Khopat, Thane (W) 400 601, Maharashtra, India. Tel: +91-22+2538 01 98 / 2545 03 72 / 2544 62 51 Email: sales@ultratech.in

Pune: +91-20-29525517 - pune@ultratech.in Kochi: +91-048-44011173 / +91-9895200526 - kochi@ultratech.in

Kolkata: +033-40089145 / +91-9674488198 - kolkata@ultratech.in



Environmental Consultancy & Laboratory

Lab.Gazetted by MoEF&CC-Govt. of India

Lab. Accredited by NABL - ISO/IEC 17025:2017 [TC-5600, Valid until 03.08.2024 in the field of Testing]

QCI-NABET Accredited EIA Consulting Organization STP/ETP/WTP Project Management Consultants

ISO 9001: 2015 ISO 45001: 2018

Lab: Survey No. 93/A, Conformity Hissa No.2 G.V.Brothers Bldg., Bata Compound, Khopat, Near Flower Valley, Thane (West) - 400 601, Maharashtra, India. Tele: +91 22 2547 49 07 / +91 22 2547 62 17 Email: lab@ultratech.in Visit us at: www.ultratech.in

TEST REPORT

ISSUED TO:INDUSTRIAL MINERAL & CHEMICAL COMPANY PVT LTD

:

:

:

:

Plot No.23 Part, MIDC Trans Thane Creek, Zone A.

Industrial Area, Village-Savli, Ghansoli,

NaviMumbai - 400710

REPORT NO.

UT/ELS/REPORT/C-015/07-2023

ISSUE DATE

03/07/2023

YOUR REF.

SOIL QUALITY MONITORING

5500015783

At Project Site

REF. DATE

09/02/2020 Agreement dt.-01/07/2023

Surface Soil (at 15cm depth)

SAMPLE PARTICULARS

Sampling Plan Ref. No.

Sampling Procedure

Sample Registration Date

Date & Time of Sampling **Analysis Starting Date**

Analysis Completion Date Sample Collected By Cample Lab Code

C-65/04-2023 UT/LQMS/SOP/S01A

27/04/2023 26/04/2023 at 11:30Hrs.

27/04/2023 05/05/2023 **ULTRA TECH**

IIII /EL C /O / / CO /O / COCO

Sample Type

Sample Location

Sample Quantity & **Packing Details**

1kg In Plastic Bag Contained in Zip Lock

Sr. No.	Test Parameter	Test Methods	Test Result	Unit
1.	Moisture Content	IS:2720 (Part 2): 1973	5.9	%
2.	Bulk Density	UT/LQMS/SOP/S03	1099	kg/m³
3.	Organic Matter	IS:2720 (Part 22): 1972	0.9	%
4.	Total Organic Carbon	IS:2720 (Part 22): 1972	0.5	%
5.	pH [1:2.5 Soil:Water Extract]	IS:2720 (Part 26): 1987	7.4	-
6.	Conductivity(1:2soil:Water Extract)	IS:14767- 2000	1.148	mS/cm
7.	Sodium as Na (Water Extractable)	UT/LQMS/SOP/S19	231	mg/kg
8.	Magnesium as Mg (Water Extractable)	UT/LQMS/SOP/S22	74	mg/kg
9.	Chlorides as Cl- (Water Extractable)	UT/LQMS/SOP/S23	136	mg/kg
10.	Sulphate as SO ₄ ²⁻ (Water Extractable)	UT/LQMS/SOP/S24	205	mg/kg
11.	Sodium Adsorption Ratio	UT/LQMS/SOP/S26	1.0	(meq/kg)1/2
12.	Cation Exchange Capacity	UT/LQMS/SOP/S18	25.9	meq/100g
13.	Water Holding Capacity	UT/LQMS/SOP/S12	54.8	%
14.	Available Boron as B (Available)	UT/LQMS/SOP/S27	0.8	mg/kg
15.	Phosphorous as P ₂ O ₅ (Available)	UT/LQMS/SOP/S28	65	kg/ha
16.	Potassium as K ₂ O (Available)	UT/LQMS/SOP/S29	162	kg/ha
17.	Nitrogen as N (Available)	UT/LQMS/SOP/S30	145	Kg/ha
18.	Iron as Fe	UT/LQMS/SOP/S35&S37	76584	mg/kg
19.	Zinc as Zn	UT/LQMS/SOP/S35&S37	78	mg/kg

Remark/ Statement of Conformity:

NII.

Note:

1. Samples were collected by following laboratory's SOP (UT/LQMS/SOP/S01A) based on Methods Manual: Soil Testing in India by DA&FW, MoA, GOI.

2. This test report refers only to the sample tested.

3. This test report may not be reproduced in part, without the permission of this laboratory.

4. Any correction invalidates this test report

END OF REPORT

For ULTRA TECH

Meghan Patil thorized Signatory)

Page 1 of 1

CONSULTANCY

H.O.: Unit No. 224,225,206, Jai Commercial Complex, Eastern Express Highway, Opp. Cadbury Factory, Khopat, Thane (W) 400 601, Maharashtra, India.

Tel: +91-22+2538 01 98 / 2545 03 72 / 2544 62 51 Email: sales@ultratech.in

Pune: +91-20-29525517 - pune@ultratech.in Kochi: +91-048-44011173 / +91-9895200526 - kochi@ultratech.in

Kolkata: +033-40089145 / +91-9674488198 - kolkata@ultratech.in



nvironmental Consultancy & Laboratory Approved by MoEF&CC (Govt. of India)



AMBIENT AIR QUALITY MONITORING ANALYSIS REPORT

		TEST RE	EPORT		
					Date - 20/04/2023
Sample/Report No.	GE/LAB/A	AAQ/NE&CPL1			
Name Of Customer	M/s. Nyat	i Engineers & Co	onsultants F	Pvt Ltd	
Address Of Customer	C/o. Tata	Realty & Infrast	ructure, Gha	ansoli,	
		strial Area, Thar			
Sample Drawn By	Vendor or	n 13/04/2023	Sample R	eceived On	14/04/2023
Start of Analysis	15/04/202	23	End Of An	alysis	17/04/2023
Monitoring For	Ambient A	Air Monitoring	Sampling	Location	Near Main Gate
Sampling Duration	24 Hrly		Receptor I		2.00 meter from G.L.
Ambient Temperature	Max- 38.9	⁰ C, Min-24.5 ⁰ C	Relative H	lumidity	Max- 73.2%, Min-67.4%
Limits	National A	Ambient Air Qua	lity Standar	ds Vide GS	R 826(E)16.11.2009
Parameters	Unit	Result	Limits	Methods Of Analysis	
General Parameters					
Particulate matter	μg/m³	74.25	100		R-96/010a(Compendium
less than 10 micron	μg/π	74.20	100		D-2.1): 2017
Particulate matter	μg/m³	44.46	60		lethod Aerosol Science
less than2.5 micron		_			/I 35(4)339-342: 2017
Sulphur Dioxide	μg/m ³	30.49	80	`	part II) 2001,Reaff: 2017
Oxides of Nitrogen	μg/m ³	35.17	80	,	part VI) 2006,Reaff:2017
Carbon Monoxide	mg/m ³	0.62	2.0		part X) 1999,Reaff: 2014
Lead	μg/m³	BDL	1		oart XXII) 2004,Reaff:2014
Ozone	μg/m ³	17.06	100	٠,	oart IX) 1974, Reaff: 2014
Ammonia	μg/m ³	BDL	400		d Edition Method No. 401
Benzene	μg/m³	BDL	5		part XI) 2006, Reaff- 2017
Benzo (a) Pyrene -	ng/m³	BDL	1	IS 5182 (I	Part 12):2004,Reaff: 2014
Particulate Phase only					
Arsenic	ng/m ³	BDL	6		d Edition Method No. 822
Nickel	ng/m ³	BDL	20	APHA 2nd	d Edition Method No. 822

• BDL: - Below Detection Limits

•Remarks: - Monitoring Results are well within the limits prescribed by NAAQS.

For **GREEN ENVIRO**





Authorized Signatory

- **Note –** 1. Results relate only to the sample tested.
 - 2. Test report shall not be reproduced except in full, without written approval of the laboratory
 - 3. This report, in full or in part, shall not be used for advertising or legal action.

- Regd.Office: Sr.No.167/2B & 168/2B, Plot No.7,
 Wireless Colony, Aundh, Pune 411007.
- ▶ Laboratory: Sr.No.45A/1-4A/4. "PARSHURAM", Eliphiston Road, Bopodi, Pune - 411003.
- info@mygreenenviro.com, krchavan@mygreenenviro.com
- www.mygreenenviro.com
- 020-25817978 M: +91 8208539774 / 9767684521 9881460031 / 9881081846 / 9370025564



invironmental Consultancy & Laboratory Approved by MoEF&CC (Govt. of India)



AMBIENT AIR QUALITY MONITORING ANALYSIS REPORT

		TEST RE	PORT				
					Date - 20/04/2023		
Sample/Report No.	GE/LAB/A	AQ/NE&CPL2					
Name Of Customer	M/s. Nyat	i Engineers & Co	onsultants F	vt Ltd			
Address Of Customer		C/o. Tata Realty & Infrastructure, Ghansoli, TTC Industrial Area, Thane – 400710					
Sample Drawn By		Vendor on 13/04/2023 Sample Received On 14/04/2023					
Start of Analysis	15/04/202		End Of An		17/04/2023		
Monitoring For	Ambient A	Air Monitoring	Sampling I	,	Near Safety Office		
Sampling Duration	24 Hrly		Receptor I		2.00 meter from G.L.		
Ambient Temperature	Max- 38.5	⁰ C, Min-24.2 ⁰ C	Relative H	umidity	Max- 73.6%, Min-67.7%		
Limits	National A	Ambient Air Qua	lity Standar	rds Vide GSR 826(E)16.11.2009			
Parameters	Unit	Result	Limits	Methods Of Analysis			
General Parameters							
Particulate matter less than 10 micron	μg/m³	70.53	100		R-96/010a(Compendium D-2.1): 2017		
Particulate matter less than2.5 micron	μg/m³	40.24	60	USEPA M	Tethod Aerosol Science // 35(4)339-342: 2017		
Sulphur Dioxide	μ g /m³	27.03	80	IS 5182 (part II) 2001,Reaff: 2017		
Oxides of Nitrogen	μ g /m ³	31.20	80	IS 5182 (part VI) 2006,Reaff:2017		
Carbon Monoxide	mg/m ³	0.58	2.0	IS 5182 (part X) 1999,Reaff: 2014		
Lead	μ g /m³	BDL	1	IS 5182 (p	oart XXII) 2004,Reaff:2014		
Ozone	μ g /m ³	16.84	100	IS 5182 (p	oart IX) 1974, Reaff: 2014		
Ammonia	μg/m³	BDL	400	APHA 2nd	d Edition Method No. 401		
Benzene	μg/m³	BDL	5	IS 5182 (part XI) 2006, Reaff- 2017			
Benzo (a) Pyrene - Particulate Phase only	ng/m³	BDL	1	IS 5182 (I	Part 12):2004,Reaff: 2014		
Arsenic	ng/m ³	BDL	6	APHA 2nd	d Edition Method No. 822		
Nickel	ng/m ³	BDL	20	APHA 2nd	d Edition Method No. 822		

• BDL: - Below Detection Limits

•Remarks: - Monitoring Results are well within the limits prescribed by NAAQS.

For **GREEN ENVIRO**





Authorized Signatory

- Note 1. Results relate only to the sample tested.
 - 2. Test report shall not be reproduced except in full, without written approval of the laboratory
 - 3. This report, in full or in part, shall not be used for advertising or legal action.

- Regd.Office: Sr.No.167/2B & 168/2B, Plot No.7, Wireless Colony, Aundh, Pune 411007.
- ▶ Laboratory: Sr.No.45A/1-4A/4. "PARSHURAM", Eliphiston Road, Bopodi, Pune - 411003.
- info@mygreenenviro.com, krchavan@mygreenenviro.com
- www.mygreenenviro.com
- 020-25817978 M: +91 8208539774 / 9767684521 9881460031 / 9881081846 / 9370025564



invironmental Consultancy & Laboratory Approved by MoEF&CC (Govt. of India)



AMBIENT AIR QUALITY MONITORING ANALYSIS REPORT

		TEST RE	PORT				
					Date - 20/04/2023		
Sample/Report No.	GE/LAB/A	AQ/NE&CPL3					
Name Of Customer	M/s. Nyat	i Engineers & Co	onsultants F	vt Ltd			
Address Of Customer		C/o. Tata Realty & Infrastructure, Ghansoli, TTC Industrial Area, Thane – 400710					
Sample Drawn By		n 13/04/2023			14/04/2023		
Start of Analysis	15/04/202		End Of An		17/04/2023		
Monitoring For		Air Monitoring	Sampling	-	Near Store Cabin		
Sampling Duration	24 Hrly	All Mornitoring	Receptor I		2.00 meter from G.L.		
Ambient Temperature	,	⁰ C, Min-24.4 ⁰ C			Max- 73.4%, Min-67.6%		
Limits				ds Vide GSR 826(E)16.11.2009			
Parameters	Unit	Result	Limits	Methods Of Analysis			
General Parameters	Offic	Nesun	Lillits	Wellious	Of Allalysis		
Particulate matter	0			FPA/625/	R-96/010a(Compendium		
less than 10 micron	μg/m³	64.12	100	Method IO-2.1): 2017			
Particulate matter less than2.5 micron	μg/m³	35.97	60	USEPA M	Tethod Aerosol Science M 35(4)339-342: 2017		
Sulphur Dioxide	μg/m³	23.86	80		part II) 2001,Reaff: 2017		
Oxides of Nitrogen	μg/m ³	27.45	80	IS 5182 (part VI) 2006,Reaff:2017		
Carbon Monoxide	mg/m ³	0.51	2.0	IS 5182 (part X) 1999,Reaff: 2014		
Lead	μg/m ³	BDL	1		oart XXII) 2004,Reaff:2014		
Ozone	μg/m ³	14.82	100	IS 5182 (oart IX) 1974, Reaff: 2014		
Ammonia	μg/m ³	BDL	400	APHA 2nd	d Edition Method No. 401		
Benzene	μ g /m ³	BDL	5	IS 5182 (part XI) 2006, Reaff- 2017			
Benzo (a) Pyrene - Particulate Phase only	ng/m³	BDL	1	IS 5182 (I	Part 12):2004,Reaff: 2014		
Arsenic	ng/m³	BDL	6	APHA 2nd	d Edition Method No. 822		
Nickel	ng/m ³	BDL	20	APHA 2nd	d Edition Method No. 822		

• BDL: - Below Detection Limits

•Remarks: - Monitoring Results are well within the limits prescribed by NAAQS.

For **GREEN ENVIRO**





Authorized Signatory

- **Note** 1. Results relate only to the sample tested.
 - 2. Test report shall not be reproduced except in full, without written approval of the laboratory
 - 3. This report, in full or in part, shall not be used for advertising or legal action.

- Regd.Office: Sr.No.167/2B & 168/2B, Plot No.7, Wireless Colony, Aundh, Pune 411007.
- ▶ Laboratory : Sr.No.45A/1-4A/4. "PARSHURAM", Eliphiston Road, Bopodi, Pune - 411003.
- info@mygreenenviro.com, krchavan@mygreenenviro.com
- www.mygreenenviro.com
- 020-25817978 M: +91 8208539774 / 9767684521 9881460031 / 9881081846 / 9370025564





Environmental Consultancy & Laboratory Approved by MoEF&CC (Govt. of India)

AMBIENT AIR QUALITY MONITORING ANALYSIS REPORT						
		TEST RE	PORT			
					Date - 20/04/2023	
Sample/Report No.	GE/LAB/A	GE/LAB/AAQ/NE&CPL4				
Name Of Customer	M/s. Nyat	i Engineers & Co	onsultants F	vt Ltd		
Address Of Customer		Realty & Infrast strial Area, Thar				
Sample Drawn By	Vendor or	n 13/04/2023	Sample Re	eceived On	14/04/2023	
Start of Analysis	15/04/202	23	End Of An	alysis	17/04/2023	
Monitoring For	Ambient A	Air Monitoring	Sampling I	_ocation	Near DG Area	
Sampling Duration	24 Hrly		Receptor Height 2		2.00 meter from G.L.	
Ambient Temperature	Max- 38.3	⁰ C, Min-24.1 ⁰ C	Relative Humidity Max- 7		Max- 73.8%, Min-67.9%	
Limits	National A	Ambient Air Qua	lity Standar	ds Vide GS	R 826(E)16.11.2009	
Parameters	Unit	Result	Limits	Methods Of Analysis		
General Parameters				1		
Particulate matter less than 10 micron	μg/m³	67.72	100		R-96/010a(Compendium D-2.1): 2017	
Particulate matter less than 2.5 micron	μg/m³	38.30	60		Tethod Aerosol Science // 35(4)339-342: 2017	
Sulphur Dioxide	μ g /m³	25.85	80	IS 5182 (part II) 2001,Reaff: 2017	
Oxides of Nitrogen	μ g /m³	29.36	80	IS 5182 (part VI) 2006,Reaff:2017	
Carbon Monoxide	mg/m ³	0.55	2.0	IS 5182 (part X) 1999,Reaff: 2014	
Lead	μ g /m³	BDL	1	IS 5182 (p	oart XXII) 2004,Reaff:2014	
Ozone	μ g /m³	15.71	100	IS 5182 (p	oart IX) 1974, Reaff: 2014	
Ammonia	μ g /m³	BDL	400	APHA 2nd	d Edition Method No. 401	
Benzene	μ g /m ³	BDL	5	IS 5182 (p	oart XI) 2006, Reaff- 2017	
Benzo (a) Pyrene - Particulate Phase only	na/m³	BDL	1	IS 5182 (F	Part 12):2004,Reaff: 2014	

• BDL: - Below Detection Limits

ng/m³

ng/m³

•Remarks: - Monitoring Results are well within the limits prescribed by NAAQS.

BDL

BDL

For **GREEN ENVIRO**

Particulate Phase only

Arsenic

Nickel





Authorized Signatory

- Note 1. Results relate only to the sample tested.
 - 2. Test report shall not be reproduced except in full, without written approval of the laboratory
 - 3. This report, in full or in part, shall not be used for advertising or legal action.

---End of the Report---

- Regd.Office: Sr.No.167/2B & 168/2B, Plot No.7, Wireless Colony, Aundh, Pune 411007.
- ▶ Laboratory : Sr.No.45A/1-4A/4. "PARSHURAM", Eliphiston Road, Bopodi, Pune - 411003.
- info@mygreenenviro.com, krchavan@mygreenenviro.com

APHA 2nd Edition Method No. 822

APHA 2nd Edition Method No. 822

www.mygreenenviro.com

6

20

020-25817978 M: +91 8208539774 / 9767684521 9881460031 / 9881081846 / 9370025564






Environmental Consultancy & Laboratory Approved by MoEF&CC (Govt. of India)

AMB	IENT NOISE MONITORING ANAL	YSIS REPORT		
	TEST REPORT			
Sample/Report No.	GE/LAB/ANM/NE&CPL1			
Name Of Customer	M/s. Nyati Engineers & Consultants	s Pvt Ltd		
Address Of Customer	C/o. Tata Realty & Infrastructure, C			
Report Date	20/04/2023			
Date Of Sampling	Vendor on 13/04/2023			
Date Of Analysis	14/04/2023			
Monitoring For	Ambient Noise Monitoring			
Sampling Location	Near Main Gate	Near Main Gate		
Limits*	Maharashtra Pollution Control Board has prescribed 55 dB(A) as an upper limit of Noise Level during day time & 45 dB(A) during Night time			
Time Of Sampling	1) Day time shall mean from 06:00 A.M. to 10:00 P.M. 2) Night time shall mean from 10:00 P.M. to 06:00 A.M			
	RESULTS OF ANALYSIS (DAY TIM	<u>⁄IE)</u>		
UNIT	READINGS	MPCB LIMITS		
dB(A)	53.5	55		
	RESULTS OF ANALYSIS (NIGHT	TIME)		
UNIT	READINGS	MPCB LIMITS		
dB(A)	43.2 45			
REMARK/OBSERVATION	NS: Monitoring results are well within the	e limits prescribed by MPCB.		

For **GREEN ENVIRO**





- **Note –** 1. Results relate only to the sample tested.
 - 2. Test report shall not be reproduced except in full, without written approval of the laboratory
 - 3. This report, in full or in part, shall not be used for advertising or legal action.
 - ---End of the Report---
- Regd.Office: Sr.No.167/2B & 168/2B, Plot No.7,
 Wireless Colony, Aundh, Pune 411007.
- ▶ Laboratory: Sr.No.45A/1-4A/4. "PARSHURAM", Eliphiston Road, Bopodi, Pune - 411003.
- info@mygreenenviro.com, krchavan@mygreenenviro.com
- www.mygreenenviro.com
- 020-25817978 M: +91 8208539774 / 9767684521 9881460031 / 9881081846 / 9370025564






Environmental Consultancy & Laboratory Approved by MoEF&CC (Govt. of India)

AMB	IENT NOISE MONITORING ANA	LYSIS REPORT			
	TEST REPORT				
Sample/Report No.	GE/LAB/ANM/NE&CPL2				
Name Of Customer	M/s. Nyati Engineers & Consultant	ts Pvt Ltd			
Address Of Customer	C/o. Tata Realty & Infrastructure, 0 TTC Industrial Area, Thane – 4007	· · · · · · · · · · · · · · · · · · ·			
Report Date	20/04/2023				
Date Of Sampling	Vendor on 13/04/2023				
Date Of Analysis	14/04/2023				
Monitoring For	Ambient Noise Monitoring				
Sampling Location	Labour Colony	Labour Colony			
Limits*	Maharashtra Pollution Control Board has prescribed 55 dB(A) as an upper limit of Noise Level during day time & 45 dB(A) during Night time				
Time Of Sampling	1) Day time shall mean from 06:00 A.M. to 10:00 P.M. 2) Night time shall mean from 10:00 P.M. to 06:00 A.M				
	RESULTS OF ANALYSIS (DAY TI	ME)			
UNIT	READINGS	MPCB LIMITS			
dB(A)	50.2 55				
	RESULTS OF ANALYSIS (NIGHT	TIME)			
UNIT	READINGS	MPCB LIMITS			
dB(A)	40.1 45				
REMARK/OBSERVATION	NS: Monitoring results are well within the	e limits prescribed by MPCB.			

For **GREEN ENVIRO**







- 2. Test report shall not be reproduced except in full, without written approval of the laboratory
- 3. This report, in full or in part, shall not be used for advertising or legal action.

- Regd.Office: Sr.No.167/2B & 168/2B, Plot No.7, Wireless Colony, Aundh, Pune - 411007.
- ▶ Laboratory: Sr.No.45A/1-4A/4. "PARSHURAM", Eliphiston Road, Bopodi, Pune - 411003.
- info@mygreenenviro.com, krchavan@mygreenenviro.com
- www.mygreenenviro.com
- 9881460031 / 9881081846 / 9370025564








AMB	IENT NOISE MONITORING ANA	LYSIS REPORT			
	TEST REPORT				
Sample/Report No.	ample/Report No. GE/LAB/ANM/NE&CPL3				
Name Of Customer	M/s. Nyati Engineers & Consultar	nts Pvt Ltd			
Address Of Customer	C/o. Tata Realty & Infrastructure, TTC Industrial Area, Thane – 400	· · · · · · · · · · · · · · · · · · ·			
Report Date	20/04/2023				
Date Of Sampling	Vendor on 13/04/2023				
Date Of Analysis	14/04/2023				
Monitoring For	Ambient Noise Monitoring				
Sampling Location	Near Store Area	Near Store Area			
Limits*		Maharashtra Pollution Control Board has prescribed 55 dB(A) as an upper limit of Noise Level during day time & 45 dB(A) during Night time			
Time Of Sampling		1) Day time shall mean from 06:00 A.M. to 10:00 P.M. 2) Night time shall mean from 10:00 P.M. to 06:00 A.M			
	RESULTS OF ANALYSIS (DAY T	TIME)			
UNIT	READINGS	MPCB LIMITS			
dB(A)	52.1	55			
RESULTS OF ANALYSIS (NIGHT TIME)					
UNIT	READINGS	MPCB LIMITS			
dB(A)	41.7	41.7 45			
REMARK/OBSERVATION	NS: Monitoring results are well within th	e limits prescribed by MPCB.			

For **GREEN ENVIRO**







- **Note** 1. Results relate only to the sample tested.
 - 2. Test report shall not be reproduced except in full, without written approval of the laboratory
 - 3. This report, in full or in part, shall not be used for advertising or legal action.

- Regd.Office: Sr.No.167/2B & 168/2B, Plot No.7,
 Wireless Colony, Aundh, Pune 411007.
- ◆ Laboratory: Sr.No.45A/1-4A/4. "PARSHURAM", Eliphiston Road, Bopodi, Pune - 411003.
- info@mygreenenviro.com, krchavan@mygreenenviro.com
- www.mygreenenviro.com
- 020-25817978 M: +91 8208539774 / 9767684521 9881460031 / 9881081846 / 9370025564







AMBIENT NOISE MONITORING ANALYSIS REPORT				
	TEST REPORT			
Sample/Report No. GE/LAB/ANM/NE&CPL4				
Name Of Customer	M/s. Nyati Engineers & Consultants Pvt Ltd			
Address Of Customer	C/o. Tata Realty & Infrastructure, Ghansoli, TTC Industrial Area, Thane – 400710			
Report Date	20/04/2023			
Date Of Sampling	Vendor on 13/04/2023			
Date Of Analysis	14/04/2023			
Monitoring For	Ambient Noise Monitoring			
Sampling Location	Near DG Area			
Limits*	Maharashtra Pollution Control Board has prescribed 55 dB(A) as an upper limit of Noise Level during day time & 45 dB(A) during Night time			
Time Of Sampling 1) Day time shall mean from 06:00 A.M. to 10:00 P.M. 2) Night time shall mean from 10:00 P.M. to 06:00 A.M				
RESULTS OF ANALYSIS (DAY TIME)				

RESULTS OF ANALYSIS (DAY TIME)

UNIT	READINGS	MPCB LIMITS
dB(A)	51.4	55

RESULTS OF ANALYSIS (NIGHT TIME)

UNIT	READINGS	MPCB LIMITS	
dB(A)	42.6	45	

REMARK/OBSERVATIONS: Monitoring results are well within the limits prescribed by MPCB.

For **GREEN ENVIRO**





Authorized Signatory

- Note 1. Results relate only to the sample tested.
 - 2. Test report shall not be reproduced except in full, without written approval of the laboratory
 - 3. This report, in full or in part, shall not be used for advertising or legal action.

- Regd.Office: Sr.No.167/2B & 168/2B, Plot No.7, Wireless Colony, Aundh, Pune 411007.
- ▶ Laboratory: Sr.No.45A/1-4A/4. "PARSHURAM", Eliphiston Road, Bopodi, Pune - 411003.
- info@mygreenenviro.com, krchavan@mygreenenviro.com
- www.mygreenenviro.com
- 020-25817978 M: +91 8208539774 / 9767684521 9881460031 / 9881081846 / 9370025564



Environmental Consultancy & Laboratory Approved by MoEF&CC (Govt. of India)



	SOIL ANALYSIS REPORT					
CLIENT'S NAME			M/s. Nyati Engineers & Consultants Pvt Ltd			
CLIEN	T'S ADDRESS		C/o. Tata Realty & Inf	rastructure, Ghansoli, Γhane – 400710		
Report	No: - GE/LAB/S/ NE&CPI	_1	Dated:- 20/04/2023			
Lab Re	ference No: GE/LAB/S/ N	E&CPL01	Date Of Sampling: - 1	13/04/2023		
Date O	f Analysis: - 14/04/2023		Details Of Sample- S	oil Sample		
Sample	e Collected By – Vendor		Sample Container –	Zip Lock Plastic Bag		
Locatio	n- On Site		Quantity of Sample R	Received - 2 Kg.		
			RESULTS OF ANALY	SIS		
Sr. No	Parameter	Unit	Result	Methods Of Analysis		
01	Appearance		Blackish	-		
02	Texture		I			
Α	Clay	%	58.39	Method manual soil testing		
В	Silt	%	28.72	Method manual soil testing		
С	Sand	%	6.91	Method manual soil testing		
D	Gravel	%	5.98	Method manual soil testing		
03	РΗ	Value	7.02	IS 2720 Part -26 1987 RA2002		
04	Moisture Content	%	11.64	IS 15106 2002		
05	Conductivity	Mmhos	2.015	IS 14767 : 2000		
06	Water Holding Capacity	%	13.74	IS 14765 2000		
07	Copper as Cu	mg/kg	BDL	IS 6092 Part- 5 1985		
08	Zinc as Zn	mg/kg	BDL	IS 6092 Part- 5 1985		
09	Lead as Pb	mg/kg	BDL	IS 6092 Part- 5 1985		



Page No – 1

- Regd.Office: Sr.No.167/2B & 168/2B, Plot No.7,
 Wireless Colony, Aundh, Pune 411007.
- ▶ Laboratory: Sr.No.45A/1-4A/4. "PARSHURAM", Eliphiston Road, Bopodi, Pune - 411003.
- info@mygreenenviro.com, krchavan@mygreenenviro.com
- www.mygreenenviro.com
- 020-25817978 M: +91 8208539774 / 9767684521 9881460031 / 9881081846 / 9370025564







	SOIL ANALYSIS REPORT				
Sr.No	Parameter	Unit	Result	Methods Of Analysis	
10	Cadmium as Cd	mg/kg	BDL	IS 6092 Part- 5 1985	
11	Iron as Fe	mg/kg	0.61	IS 6092 Part- 5 1985	
12	Manganese as Mn	mg/kg	BDL	IS 6092 Part- 5 1985	
13	Phosphorous as P	Kg/ha	1.90	IS 6092 (Part 3) 2004	
14	Total Nitrogen as N	mg/kg	1394	Method manual soil testing	
15	Potassium as k	mg/kg	201	IS 2799 -1980	
16	Sodium as Na	mg/kg	2.41	IS 2799 -1980	
17	Organic Carbon	%	3.05	IS 2720 Part -22 1972 RA 2010	
18	Calcium as Ca	%	1.28	IS 2409:1985	
19	Magnesium as Mg	%	BDL	IS 2409:1985	

• BDL - Below Detection Limits

For **GREEN ENVIRO**



Authorized Signatory



Page No - 2

Note – 1. Results relate only to the sample tested.

- 2. Test report shall not be reproduced except in full, without written approval of the laboratory
- 3. This report, in full or in part, shall not be used for advertising or legal action.

- Regd.Office: Sr.No.167/2B & 168/2B, Plot No.7, Wireless Colony, Aundh, Pune 411007.
- ▶ Laboratory: Sr.No.45A/1-4A/4. "PARSHURAM", Eliphiston Road, Bopodi, Pune - 411003.
- info@mygreenenviro.com, krchavan@mygreenenviro.com
- www.mygreenenviro.com
- 020-25817978 M: +91 8208539774 / 9767684521 9881460031 / 9881081846 / 9370025564



Environmental Consultancy & Laboratory Approved by MoEF&CC (Govt. of India)



WATER SAMPLE ANALYSIS REPORT				
CLIENT'S NAME	M/s. Nyati Engineers & Consultants Pvt Ltd			
CLIENT'S ADDRESS	C/o. Tata Realty & Infrastructure, Ghansoli, TTC Industrial Area, Thane – 400710			
Report No: - GE/LAB/W/ NE&CPL1	Dated:- 20/04/2023			
Lab Reference No: GE/LAB/W/ NE&CPL01	Date Of Sampling: - 13/04/2023			
Date Of Analysis: - 14/04/2023	Details of Sampling – Drinking Water			
Sample Collected By – Vendor	Sample Container – Sterilized Bottle			
Location- Office	Quantity of Sample Received - 2 Lit.			
	DECLII TO OF ANAL VOIC			

RESULTS OF ANALYSIS

Parameter	Unit	Result	Standard : (IS 10500:2012)	Methods Of Analysis
РH	Value	7.15	6.5 - 8.5	IS 3025 (Part II) 1983, Reaff: 2017
Total Dissolved Solids	mg/lit	69.2	500	IS 3025 (Part XVI) 1984, Reaff: 2017
Total Suspended Solids	mg/lit	1.19	Not Specified	IS 3025 (Part XVII) 1984, Reaff-2017
Colour		Colorless	Colorless	IS 3025 (Part IV) 1983
Odour		Odorless	Odorless	APHA 23 rd Edition (Part 2150B)
Turbidity	NTU	< 0.32	< 5	IS 3025 (Part X) 1984,Reaff: 2017
Total Hardness	mg/lit	25.84	200	IS 3025 (Part XXI) 2009, Reaff: 2019
Calcium Hardness	mg/lit	14.46	Not Specified	IS 3025 (Part 40) 1991, Reaff: 2019
Magnesium Hardness	mg/lit	11.38	Not Specified	IS 3025 (Part 46) 1994, Reaff: 2019
Most Probable	/100ml	Absent	0/100ml	IS: 1622 – 1981, Multiple tube
Number				technique
E. coli	/100ml	Absent	0-1/100ml	IS: 5887 -1 & IS15186:2002 Multiple tube technique



Page No - 1

- Regd.Office: Sr.No.167/2B & 168/2B, Plot No.7,
 Wireless Colony, Aundh, Pune 411007.
- ▶ Laboratory : Sr.No.45A/1-4A/4. "PARSHURAM", Eliphiston Road, Bopodi, Pune - 411003.
- info@mygreenenviro.com, krchavan@mygreenenviro.com
- www.mygreenenviro.com
- 020-25817978 M: +91 8208539774 / 9767684521 9881460031 / 9881081846 / 9370025564



ISO 9001:2015 Gertified ISO 14001:2015 Certified ISO 45001:2018 Certified

Approved by MoEF&CC (Govt. of India)

WATER SAMPLE ANALYSIS REPORT					
Parameter	Unit	Result	Standard: (IS10500:2012)	Methods Of Analysis	
Total Coliform	/100ml	Absent	0-1/100ml	IS:1622-1981,Multiple tube technique	
Total Viable Count	/100ml	Absent	0-1/100ml	IS: 5402 : 2012	
Fecal	/100ml	Absent	0-1/100ml	APHA 23 rd Edition Part 9230- B, Page 9-118	
Chloride	mg/lit	8.39	250	IS 3025 (Part 32) 1998, Reaff: 2019	
Sulphate	mg/lit	6.51	200	IS 3025 (Part 24) 1986, Reaff: 2019	
Total alkalinity	mg/lit	63.2	200	IS 3025 (Part 23) 1986, Reaff: 2019	
Fluoride	mg/lit	Absent	1.0	IS 3025 (Part 60) 2008	
Nitrates	mg/lit	Absent	45	APHA 23 rd Edition,(Part 4500-NO ₃ -B)	
Cyanide	mg/lit	Absent	0.05	APHA 23 rd Edition, (Part 4500-CN ⁻ C)	
Residual free chlorine	mg/lit	Absent	0.2	APHA 23 rd Edition, (Part 4500-CI B)	
Copper	mg/lit	Absent	Max 0.05	IS:3025 (Part 42) 1992, Reaff: 2019	
Mercury	mg/lit	Absent	Max 0.001	APHA 23 rd Edition, (Part 3500Hg)	
Cadmium	mg/lit	Absent	Max 0.003	APHA 23 rd Edition, (Part 3500-Cd)	
Lead	mg/lit	Absent	Max 0.01	IS 3025 (Part 47) 1994, Reaff: 2019	
Zinc	mg/lit	Absent	5.0	IS 3025 (Part 49) 1994, Reaff: 2019	
Coliform Organism	mg/lit	Absent	Not Specified	IS: 1622 – 1981	
Nickel	mg/lit	Absent	Max 0.02	IS 3025 (Part 54) 2003, Reaff: 2019,	
Polychlorinated biphenyls	mg/lit	Absent	0.0005	APHA 23 rd Edition, (Part 6431 B)	
Total chromium	mg/lit	Absent	Max 0.05	APHA 23 rd Edition, (Part 3111B)	
Total arsenic	mg/lit	Absent	Max 0.01	APHA 23 rd Edition, (Part 3500-As B)	
Aluminium	mg/lit	Absent	Max 0.03	APHA 23 rd Edition, (Part 3111 D)	



Page No – 2

- Regd.Office: Sr.No.167/2B & 168/2B, Plot No.7,
 Wireless Colony, Aundh, Pune 411007.
- ▶ Laboratory: Sr.No.45A/1-4A/4. "PARSHURAM", Eliphiston Road, Bopodi, Pune - 411003.
- info@mygreenenviro.com, krchavan@mygreenenviro.com
- www.mygreenenviro.com
- 020-25817978 M: +91 8208539774 / 9767684521 9881460031 / 9881081846 / 9370025564



Environmental Consultancy & Laboratory Approved by MoEF&CC (Govt. of India)



	WATER SAMPLE ANALYSIS REPORT					
Parameter	Unit	Result	Standard: (IS10500:2012)	Methods Of Analysis		
Ammonia (as total ammonia- N)	mg/lit	Absent	Not Specified	APHA 23 rd Edition,(Part 4500-NH 3C)		
Boron	mg/lit	Absent	Max 0.5	APHA 23 rd Edition, (Part 4500-B C)		
Silver	mg/lit	Absent	0.1	APHA 16 th Edition, (Part 324B)		
Sulphide	mg/lit	Absent	0.05	APHA 23 rd Edition, (part 4500-D)		
Mineral oil	mg/lit	Nil	0.05	IS 3025 (Part 39)		
Anionic detergents	mg/lit	Nil	Max 0.2	APHA 23 rd Edition, (Part 5540 C)		
Chloramines	mg/lit	Nil	Max 4.0	APHA 23 rd Edition, (Part 4500-Cl G)		
Selenium	mg/lit	Nil	Max 0.01	APHA 23 rd Edition,(Part 3500-Se C)		
DDT	μg/lit	Nil	1.0	APHA 23rd Edition, (Part 6630C)		
2,4 D	μg/lit	Nil	3.0	APHA 23rd Edition, (Part 6630C)		
Gamma-HCH (Lindane)	μg/lit	Nil	2.0	APHA 23rd Edition, (Part 6630C)		
Endosulfan	μg/lit	Nil	0.4	APHA 23rd Edition, (Part 6630C)		
Atrazine	μg/lit	Nil	2.0	APHA 23rd Edition, (Part 6630C)		
Reactive Silica	ppm	Nil	0.02	APHA 23 rd Edition, (Part 4500- SiO₂ D)		
Sodium	mg/lit	BDL	Not Specified	APHA 23 rd Edition, (Part 3500 Na B)		
Potassium	mg/lit	BDL	Not Specified	APHA 23 rd Edition, (Part 3500-K B)		
Phosphorous	mg/lit	BDL	Not Specified	IS 3025 (Part 31) 1988, Reaff – 2019		
Iron	mg/lit	Nil	0.3	IS 3025 (Part 53) 2003, Reaff – 2019		

For **GREEN ENVIRO**

• BDL: - Below Detection Limits



Authorized Signatory



Page No – 3

- **Note –** 1. Results relate only to the sample tested.
 - 2. Test report shall not be reproduced except in full, without written approval of the laboratory
 - 3. This report, in full or in part, shall not be used for advertising or legal action.

- Regd.Office: Sr.No.167/2B & 168/2B, Plot No.7,
 Wireless Colony, Aundh, Pune 411007.
- ▶ Laboratory: Sr.No.45A/1-4A/4. "PARSHURAM", Eliphiston Road, Bopodi, Pune - 411003.
- info@mygreenenviro.com, krchavan@mygreenenviro.com
- www.mygreenenviro.com
- 020-25817978 M: +91 8208539774 / 9767684521 9881460031 / 9881081846 / 9370025564



ISO 9001:2015 Certified ISO 14001:2015 Certified ISO 45001:2018 Certified

Environmental Consultancy & Laboratory Approved by MoEF&CC (Govt. of India)

SOURCE EMISSION MONITORING ANALYSIS REPORT					
CLIENT'S NAME M/s. Nyati Engineers & Consultants Pvt Ltd					
CLIENT'S ADDRESS	C/o. Tata Realty & Infrastructure, Ghansoli, TTC Industrial Area, Thane – 400710				
REPORT NO.	GE/LAB/A/ NE&CPL1				
DATED	20/04/2023				
LAB REFERENCE NO	GE/LAB/A/ NE&CPL01				
DATE OF SAMPLING	13/04/2023				
DATE OF ANALYSIS	14/04/2023				

RESULTS OF ANALYSIS

TEST DESCRIPTION	UNIT	RESULT	LIMITS	METHOD OF ANALYSIS
Nature of Sample		DG Stack Monitoring		
Test Location		DG Set - 320 KVA		
Duration Of Sampling	Min	20		
Material Of Stack		MS		
Stack Height From G.L.	Mtr	2.5	1	
Shape Of Stack		Round	1	
Fuel Consumption		Diesel/LDO	1	
Fuel Consumption	Lit/Hr	25-30		
Diameter	(M)	0.15		
Cross Sectional Area	(M^2)	0.0290		
Flue Gas Temperature	Deg C	76.5		
Average Velocity	M/Sec	7.34		
Gas Volume	NM³/Hr	691.8		
Total Particulate	Mg/NM ³	77.32	150	IS11255 (part 1)1985,2014

For **GREEN ENVIRO**





Authorized Signatory

- **Note –** 1. Results relate only to the sample tested.
 - 2. Test report shall not be reproduced except in full, without written approval of the laboratory
 - 3. This report, in full or in part, shall not be used for advertising or legal action.
 - ---End of the Report---
- Regd.Office: Sr.No.167/2B & 168/2B, Plot No.7,
 Wireless Colony, Aundh, Pune 411007.
- ▶ Laboratory : Sr.No.45A/1-4A/4. "PARSHURAM", Eliphiston Road, Bopodi, Pune - 411003.
- info@mygreenenviro.com, krchavan@mygreenenviro.com
- www.mygreenenviro.com
- 020-25817978 M: +91 8208539774 / 9767684521 9881460031 / 9881081846 / 9370025564



Environmental Consultancy & Laboratory Approved by MoEF&CC (Govt. of India)




	DG NOISE MONITORING ANALYSIS REPORT							
TEST REPORT								
Sample/Repo	ort No.	GE/LAB/DGNM/ NE&CPL2						
Name Of Cus	stomer	M/s. Nya	ati Engineers	& Consultants	s Pvt Ltd			
Address Of C	ustomer		•	frastructure, G Thane – 4007				
Report Dated		20/04/20)23					
Date Of Samp	oling	Vendor o	on 13/04/202	3				
Date Of Analy	/sis	13/04/20)23					
Monitoring Fo	r	DG Nois	e Monitoring					
Sampling Loc	ation	DG Set	– 320 KVA					
Limits*		 Maharashtra Pollution Control Board has prescribed in consent, acoustic enclosure / acoustic treatment of the room should be designed for minimum 25 dB (A) insertion loss or for meeting the ambient noise standard, whichever is on higher side. Maharashtra Pollution Control Board has prescribed 75 dB(A) as an upper limit of Noise Level during day time & 70 dB(A) during Night time 						
Time Of Sam	Time Of Sampling 1) Day time shall mean from 06:00 A.M. to 10:00 P.M. 2) Night time shall mean from 10:00 P.M. to 06:00 A.M RESULTS OF ANALYSIS							
				DINGS	Insertion	Loss <u>></u> 25 Db		
Description	Test Location	Unit		Night Time	Day Time	Night Time		

			REA	DINGS	Insertion Loss <u>></u> 25 Db		
Description	Test Location	Unit	Day Time	Night Time	Day Time	Night Time	
DG Set (320 KVA)	DG Set # 320 KVA Inside Acoustic Enclosure	dB(A)	99.6	95.5	26.4	00.0	
	DG Set # 320 KVA Outside Acoustic Enclosure from 0.5 meter away	dB(A)	73.5	69.2	26.1	26.3	

REMARK/OBSERVATIONS: All above Results are within MPCB Limits.

For **GREEN ENVIRO**





- Note 1. Results relate only to the sample tested.
 - 2. Test report shall not be reproduced except in full, without written approval of the laboratory
 - 3. This report, in full or in part, shall not be used for advertising or legal action.

- Regd.Office: Sr.No.167/2B & 168/2B, Plot No.7,
 Wireless Colony, Aundh, Pune 411007.
- ▶ Laboratory : Sr.No.45A/1-4A/4. "PARSHURAM", Eliphiston Road, Bopodi, Pune - 411003.
- info@mygreenenviro.com, krchavan@mygreenenviro.com
- www.mygreenenviro.com
- 020-25817978 M: +91 8208539774 / 9767684521 9881460031 / 9881081846 / 9370025564

< Ve

Vehicle search

Vehicle Number MH12VF1391

Owner Name *Y*T* *N*I*E*R* *

*O*S*L*A*T* *.* *.*

Registering Authority PUNE, Maharashtra

Vehicle Class Goods Carrier(LGV)

Fuel Type DIESEL

Emission Norm BHARAT STAGE VI

Vehicle Age 0 Years & 7 months

Vehicle Status ACTIVE

Tap to Check the Vehicle Impound and Seizure Document Status

Registration Date	27-Mar-2023
•	

Fitness Valid UpTo 26-Mar-2025

Tax Valid UpTo LTT

Insurance Valid UpTo 16-Mar-2024

PUCC Valid Upto 26-Mar-2024

Permit Valid UpTo 08-May-2028

Create Virtual RC

View Challan



Vehicle search

Vehicle Number MH12RT4754

Owner Name *I*I* *Y*T*

Registering Authority PUNE, Maharashtra

Vehicle Class Motor Car(LMV)

Fuel Type DIESEL

Emission Norm BHARAT STAGE IV

Vehicle Age 4 Years & 4 months

Vehicle Status ACTIVE

Tap to Check the Vehicle Impound and Seizure Document Status

Registration Date

Fitness Valid UpTo 30-Jun-2034

Tax Valid UpTo LTT

Insurance Valid UpTo 23-Dec-2023

PUCC Valid Upto 02-May-2024

Create Virtual RC

View Challan



STATE LEVEL ENVIRONMENT IMPACT ASSESSMENT AUTHORITY

Environment department, Room No. 217, 2nd floor, Mantralaya, Annexe, Mumbai- 400 032. Date: January 15, 2020

To.

M/s. INDUSTRIAL MINERALS & CHEMICAL CO. PVT. LTD.

at Plot No.23, 23 (PT.) 24 & 24(PT), TTC Industrial Area, MIDC - Mahape, Dist.- Thane, Maharashtra

Subject: Environment Clearance for "IMCC IT Park", MIDC, Mahape, Navi Mumbai Sir,

This has reference to your communication on the above mentioned subject. The proposal was considered as per the EIA Notification - 2006, by the State Level Expert Appraisal Committee-II, Maharashtra in its 120th meeting and recommend the project for prior environmental clearance to SEIAA. Information submitted by you has been considered by State Level Environment Impact Assessment Authority in its 184th meetings.

2. It is noted that the proposal is considered by SEAC-II under screening category Category 8(a) B2 as per EIA Notification 2006.

Brief Information of the project submitted by you is as below:-

1.Name of Project	"IMCC IT Park", MIDC, Mahape, Navi Mumbai				
2.Type of institution	Private				
3.Name of Project Proponent	M/s. INDUSTRIAL MINERALS & CHEMICAL CO. PVT. LTD.				
4.Name of Consultant	M/s. Ultra Tech				
5.Type of project	Commercial Development				
6.New project/expansion in existing project/modernization/diversification in existing project	New project				
7.If expansion/diversification, whether environmental clearance has been obtained for existing project	NA Ornmont of				
8.Location of the project	Plot No.23, 23 (PT.) 24 & 24(PT), TTC Industrial Area, MIDC - Mahape, Dist Thane, Maharashtra				
9.Taluka	Thane				
10.Village	Mahape				
Correspondence Name:	Mr. Santosh Mhadgut (Authorized Signatory)				
Room Number:					
Floor:	1st Floor				
Building Name:	E Block, Voltas Compound				
Road/Street Name:					
Locality:	Chinchpokli				
City:	Mumbai - 400033				
11.Whether in Corporation / Municipal / other area	Maharashtra Industrial Development Corporation (MIDC)				
	Received Commencement Certificate from MIDC				
12.IOD/IOA/Concession/Plan Approval Number	IOD/IOA/Concession/Plan Approval Number: Commencement Certificate No. EE/SPA/23, 23 Part, 24 & 24 Part/ D35970 /of 2019				
	Approved Built-up Area: 38208.74				

SEIAA Meeting No: 184 Meeting Date: December 30, 2019 (SEIAA-STATEMENT-0000001315) SEIAA-MINUTES-0000002884 SEIAA-EC-0000002300

f 14 | Sh

Shri. Anil Diggikar (Member Secretary SEIAA)

Page 1 of 14

13.Note on the initiated work (If applicable)	NA
14.LOI / NOC / IOD from MHADA/ Other approvals (If applicable)	NA
15.Total Plot Area (sq. m.)	192320.00 Sq. mt.
16.Deductions	1650.00 Sq. mt.
17.Net Plot area	190670.00 Sq. mt.
	FSI area (sq. m.): 38208.74 Sq. mt.
18 (a).Proposed Built-up Area (FSI & Non-FSI)	Non FSI area (sq. m.): 26825.01 Sq. mt.
	Total BUA area (sq. m.): 65033.75
	Approved FSI area (sq. m.): 38208.74 sq. mt.
18 (b).Approved Built up area as per DCR	Approved Non FSI area (sq. m.): 26825.01 sq. mt.
	Date of Approval: 10-10-2019
19.Total ground coverage (m2)	5333.68 Sq. mt.
20.Ground-coverage Percentage (%) (Note: Percentage of plot not open to sky)	2.7%
21.Estimated cost of the project	300000000



		22.F	Product	tion Details			
Serial Number	Product	Existing	(MT/M)	Proposed (MT/M)	Total (MT/M)		
1	Not applicable	Not app	plicable	Not applicable	Not applicable		
		23.Tota	l Wate	r Requirement			
	Source o	f water	MIDC				
	Fresh wa	ter (CMD):	214 KLD (F KLD)	For Domestic - 136 KLD, For	Cooling tower make up - 78		
	Recycled Flushing		For Flushir	ng - 111 KLD, For Cooling to	wer make up - 28 KLD		
	Recycled Gardenin	water - ng (CMD):	58	HOTAN			
	Swimmir make up		NA do	Tefoor Car			
Dry season:	Total Wa Requirer :	ter nent (CMD)	411 KLD		1		
	Fire figh Undergr tank(CM	ound water	200 KL				
	Fire figh Overhead tank(CM	d water	20 KL				
	Excess to	reated water	0 5				
	Source o	f water	MIDC/ Part	tly by Rain Water Harvesting	(RWH)		
	Fresh wa	ter (CMD):	111 KLD [Domestic: 136 KLD (91 form MIDC + 45 KLD from RWH) & Cooling tower make up: 20 KLD]				
	Recycled Flushing		For Flushing - 111 KLD, For Cooling tower make up - 86 KLD				
	Recycled Gardenii	water - ng (CMD):	NA				
VATOR OF THE	Swimmir make up		NA				
Wet season:	Total Wa Requirer :	nter ment (CMD)	308 KLD C C C C C C C C C C C C C C C C C C C				
	Fire figh Undergr tank(CM	ound water	200 KL				
	Fire figh Overhead tank(CM	d water	20 KL				
	Excess ti	reated water	0				
Details of Sv pool (If any)							

	24.Details of Total water consumed									
Particula rs	Consumption (CMD)			Loss (CMD)			Effluent (CMD)			
Water Require ment	Existing	Proposed	Total	Existing	Proposed	Total	Existing	Proposed	Total	
Domestic	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	
	Level of the Ground The Ground water level is between 0.62 mt. to 2.80 mt. below existing							v existing		
		water table	e:	ground leve	el					
		Size and no tank(s) and Quantity:		2 nos. of RV	VH tanks of	total capacit	y 200 KL.			
		Location o tank(s):	f the RWH	खेवव	TELEDY		7			
25.Rain V Harvestin		Quantity o pits:	f recharge	NA S	B	301:	34			
(RWH)	3	Size of rec	harge pits	NA		3	3			
	Budgetary allocation (Capital cost) :				Rs. 26.0 Lacs					
		Budgetary (O & M cos		Rs. 1.11 Lacs/annum						
		Details of if any:	UGT tanks	Location(s)	of the UGT t	ank(s): Unde	erground			
		15	122			D. A	ST.			
	Natural water drains of adequation drainage pattern: The storm water collected through the storm water drains of adequation and adequation drain.						adequate			
26.Storm drainage	water	Quantity o water:	f storm	3.95 m3/sec		Dru				
		Size of SW	D:	750 mm wide with slope 1:250						
					¥					
		Sewage ge in KLD:	neration	219	m	ni	. U.	F		
27.Sewage and		STP techno	ology:	MBR (Mem	brane Bio Re	eactor)				
		Capacity of (CMD):	f STP	1 STP of capacity 295 KL						
Waste w	_	Location & the STP:	area of	Partially Below ground						
		Budgetary (Capital co		Rs. 63.00 L	acs					
		Budgetary (O & M cos		Rs. 8.53 La	Rs. 8.53 Lacs/annum					

	28.Solid waste Management					
Waste generation in	Waste generation:	Excavated earth shall be partly reused for back filling on site and partly disposed to authorized landfill site				
the Pre Construction and Construction phase:	Disposal of the construction waste debris:	Construction waste shall be partly reused on the site and partly will be disposed to the authorized landfill site.				
	Dry waste:	344 Kg/day				
	Wet waste:	229 Kg/day				
Waste generation	Hazardous waste:	NA				
in the operation Phase:	Biomedical waste (If applicable):	NA				
	STP Sludge (Dry sludge):	33 Kg/day				
	Others if any:	E waste - 344 kg/month				
	Dry waste:	To authorized recyclers				
	Wet waste:	Treatment in Organic Waste Converters (OWC)				
	Hazardous waste:	NA NA				
Mode of Disposal of waste:	Biomedical waste (If applicable):	NA NA				
	STP Sludge (Dry sludge):	As manure				
	Others if any:	E waste - To Authorized recyclers				
	Location(s):	Lower stilt				
Area requirement:	Area for the storage of waste & other material:	41 Sq.mt.				
	Area for machinery:	12 Sq.mt.				
Budgetary allocation	Capital cost:	Rs. 9.00 Lacs				
(Capital cost and O&M cost):	O & M cost:	Rs. 1.62 Lacs/annum				

Government of Maharashtra

29.Effluent Charecterestics									
Serial Number	Parameters	Unit	Unit Inlet Effluent Outlet Effluent Charecterestics Charecterestics Effluent standards						
1	Not applicable	Not applicable	Not applicable	Not applicable					
Amount of e (CMD):	Amount of effluent generation (CMD): Not applicable								
Capacity of	the ETP:	Not applica	ble						
Amount of t recycled:	Amount of treated effluent recycled: Not applicable								
Amount of v	water send to the CETP:	Not applica	ble						
Membership	Membership of CETP (if require): Not applicable								
Note on ETI	Note on ETP technology to be used Not applicable								
Disposal of	Disposal of the ETP sludge Not applicable								



Government of Maharashtra

			30.Ha	zardous	Waste D	etails			
Serial Number	Desc	ription	Cat	UOM	Existing	Proposed	Total	Method of Disposal	
1	1 Not applicable a		Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	
•			31.St	acks em	ission De	etails			
Serial Number Section & units		Fuel Used with Quantity		Stack No.	Height from ground level (m)	Internal diameter (m)	Temp. of Exhaust Gases		
1			-	- ^-					
			32.De	tails of I	uel to b	e used			
Serial Number	Ty	pe of Fuel	W	Existing	fefor	Proposed		Total	
1		4). sc	16.	37	202	ス		
33.Source of	Fuel	N.	7 9 4			18/1	2		
34.Mode of	Transporta	tion of fuel to	site		io.	30	73		
		\mathcal{A}	70		38	- 3	13		
		田		35.Ei	nergy		压		
		Source of supply:	power	Maharashtı	ra State Elec	tricity Distri	bution Comp	any Limited (MSEDCL)	
		During Co Phase: (De Load)	nstruction emand						
		DG set as back-up de constructi	uring	As per requirement					
		During Opphase (Conload):							
Pow require		During Opphase (Delload):		2832 KW					
		Transform	er:	2# 1000 KVA Dry type cast resin Transformer with 1# Space for 1000 KVA Transformer 1# 1600 KVA Dry type cast resin Transformer with 1#Space provision for 1600 KVA Transform				e cast resin	
		DG set as back-up do operation	uring	3 Nos. of DG set of capacity 1500 KVA each					
		Fuel used:		Diesel	uu				
		Details of tension lir through thany:	e passing	NA					

Energy saving by non-conventional method:

- Use of LED lights for Internal Lighting
- Use of LED lights for External Lighting
 Use of Energy efficient Pumps as per ECBC Guidelines (Domestic Plumbing + STP)
 Use of High COP chiller as per ECBC Guidelines
- Use of Low Losses Transformers as per ECBC Guidelines
- Solar PV Cells with installed capacity of 285 KW

SEIAA Meeting No: 184 Meeting Date: December 30, 2019 (SEIAA-STATEMENT-0000001315) **SEIAA-MINUTES-0000002884** SEIAA-EC-0000002300

Page 7 of 14

		3	6.Detail calculati	ons & % of savin	g:	
Serial Number	Е	nergy Cons	ervation Measures	Saving %		
1		Overall	Energy saving		23%	
2		Energy sa	ving due to Solar		6%	
		37	.Details of pollut	ion control Syste	ms	
Source	Ex	isting pollu	tion control system	Pro	posed to be installed	
Sewage					STP	
Solid waste				Or	ganic waste converter	
Budgetary (Capital		Capital co	Rs. 185.00	Lacs		
O&M		O & M cos	t: Rs. 2.50 La	cs/annum		
38	.Envir	onmen	tal Manageme	ent plan Budg	etary Allocation	
		a)	Construction pha	se (with Break-u	ıp):	
Serial Number	Attril	butes	Parameter	Total Cost p	per annum (Rs. In Lacs)	
1	Air Envi	ronment	Water for Dust Suppression	3200	2.16	
2	Air Envi	ronment	Air and Noise Monitoring: On site Sensors	T.	0.50	
3	Air Envi	ronment	Air and Noise Monitoring: By outside MoEF & CC Approved Laboratory		0.22	
4	Water En	vironment	Drinking water analysis	THE TOP	0.18	
5	Land Env	rironment	Site Sanitation		1.67	
6	Health &	Hygiene	Disinfection- Pest Control	W	1.20	
7	Health &	Hygiene	Health Check Up		4.50	
		_ b) Operation Phas	e (with Break-up):	
Serial Number	Comp	onent	Description	Capital cost Rs. In Lacs	Operational and Maintenance cost (Rs. in Lacs/yr)	
1		NOISE NMENT	Ambient Air quality & Noise Monitoring - On site sensors	No set up cost is involved as already considered Construction Phase	0.50	
2		NOISE NMENT	Ambient Air quality & Noise Monitoring - By outside MoEF & CC Approved Laboratory	No set up cost is involved	0.22	
3		NOISE NMENT	Cost for DG Stack Exhaust Monitoring - 3 nos. of stacks	No set up cost is involved	0.14	
4	AIR & ENVIRO	NOISE NMENT	Cost for Plantation : RG area on ground	109.98	1.20	

SEIAA Meeting No: 184 Meeting Date: December 30, 2019 (SEIAA-STATEMENT-0000001315) SEIAA-MINUTES-0000002884 SEIAA-EC-0000002300

Page 8 of 14

Shri. Anil Diggikar (Member Secretary SEIAA)

5	WATER ENVIRONMENT - Waste water treatment	Cost for sewage Treatment Plant	45.00	7.50
6	WATER ENVIRONMENT - Cost for water & waste water Monitoring	On site sensors	18.00	1.00
7	WATER ENVIRONMENT - Cost for water & waste water Monitoring	By outside MoEF & CC Approved Laboratory	No set up cost is involved	0.03
8	WATER ENVIRONMENT - Water Conservation (Rain Water Harvesting System)	Cost for RWH tanks	20.00	1.00
9	WATER ENVIRONMENT - Water Conservation (Rain Water Harvesting System)	Cost for treatment unit for Rain Water collected in tanks	6.00	0.02
10	WATER ENVIRONMENT - Water Conservation (Rain Water Harvesting System)	Cost for Rainwater Monitoring	No set up cost is involved	0.09
11	LAND ENVIRONMENT - Solid Waste Management	Cost for Treatment of biodegradable garbage in OWC	9.00	1.54
12	LAND ENVIRONMENT - Solid Waste Management	Environmental Monitoring	No set up cost is involved	0.08
13	ENERGY CONSERVATION	Use of renewable energy - Solar system	185.00	2.50

39.Storage of chemicals (inflamable/explosive/hazardous/toxic substances)

Description	Status	Location A	Storage Capacity in MT	Maximum Quantity of Storage at any point of time in MT	Consumption / Month in MT	Source of Supply	Means of transportation
Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable	Not applicable

40.Any Other Information

No Information Available

SEIAA Meeting No: 184 Meeting Date: December 30, 2019 (SEIAA-STATEMENT-0000001315) SEIAA-MINUTES-0000002884 SEIAA-EC-0000002300

Page 9 of 14

Shri. Anil Diggikar (Member Secretary SEIAA)

CRZ/ RRZ clearance obtain, if any:	NA
Distance from Protected Areas / Critically Polluted areas / Eco-sensitive areas/ inter-State boundaries	NA
Category as per schedule of EIA Notification sheet	Category 8(a) B2
Court cases pending if any	No
Other Relevant Informations	NA NA
Have you previously submitted Application online on MOEF Website.	Yes
Date of online submission	19-04-2018

3. The proposal has been considered by SEIAA in its 184th meeting & decided to accord environmental clearance to the said project under the provisions of Environment Impact Assessment Notification, 2006 subject to implementation of the following terms and conditions:

Specific Conditions:

I	PP to submit Approved plan
II	PP to obtain the NoC from the National High Speed Rail Corporation Ltd (NHSRCL), if required.
III	PP to upload the civil aviation NoC.
IV	PP to upload the CFO NoC. Also PP to abide the all conditions laid in the CFO NoC dated 25/9/2019.
V	PP to ensure that RG should be intact even during future development also.
VI	The PP to get NOC from competent authority with reference to Thane creek flamingo sanctuary if the project site falls within 10 Km radius from the said sanctuary boundary. The planning authority to ensure fulfilment of this condition before granting CC.
VII	PP to submit CER prescribed by MoEF&CC circular dated 1.5.2018 relevant to the area and people around the project or Environment Department may direct PP to undertake CER work in identified area, as identified by Environment Department.
VIII	PP to ensure that CER plan gets approved from Municipal Commissioner/District Collector.
IX	PP Shall comply with Standard EC conditions mentioned in the Office Memorandum issued by MoEF& CC vide F.No.22-34/2018-IA.III dt.04.01.2019.
X	SEIAA decided to grant EC for -FSI: 38208.74 m2, Non-FSI: 26825.01 m2 and Total BUA:65033.75 m2 (Plan Approval no-EE/SPA/23, 23(Pt), 24, 24 (Pt)/D35970/2019, Date-10.10.2019)

General Conditions:

I	E-waste shall bedisposed through Authorized vendor as per E-waste (Management and Handling) Rules, 2016.
п	The Occupancy Certificate shall be issued by the Local Planning Authority to the project only after ensuring sustained availability of drinking water, connectivity of sewer line to the project site and proper disposal of treated water as per environmental norms.
Ш	This environmental clearance is issued subject to obtaining NOC from Forestry & Wild life angle including clearance from the standing committee of the National Board for Wild life as if applicable & this environment clearance does not necessarily implies that Forestry & Wild life clearance granted to the project which will be considered separately on merit.
IV	PP has to abide by the conditions stipulated by SEAC& SEIAA.

Shri. Anil Diggikar (Member Secretary SEIAA)

v	The height, Construction built up area of proposed construction shall be in accordance with the existing FSI/FAR norms of the urban local body & it should ensure the same along with survey number before approving layout plan & before according commencement certificate to proposed work. Plan approving authority should also ensure the zoning permissibility for the proposed project as per the approved development plan of the area.
VI	If applicable Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.
VII	All required sanitary and hygienic measures should be in place before starting construction activities and to be maintained throughout the construction phase.
VIII	Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.
IX	The solid waste generated should be properly collected and segregated. dry/inert solid waste should be disposed off to the approved sites for land filling after recovering recyclable material.
X	Disposal of muck during construction phase should not create any adverse effect on the neighboring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.
XI	Arrangement shall be made that waste water and storm water do not get mixed.
XII	All the topsoil excavated during construction activities should be stored for use in horticulture / landscape development within the project site.
XIII	Additional soil for leveling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.
XIV	Green Belt Development shall be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/ Agriculture Dept.
XV	Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
XVI	Construction spoils, including bituminous material and other hazardous materials must not be allowed to contaminate watercourses and the dumpsites for such material must be secured so that they should not leach into the ground water.
XVII	Any hazardous waste generated during construction phase should be disposed off as per applicable rules and norms with necessary approvals of the Maharashtra Pollution Control Board.
XVIII	The diesel generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environments (Protection) Rules prescribed for air and noise emission standards.
XIX	The diesel required for operating DG sets shall be stored in underground tanks and if required, clearance from concern authority shall be taken.
XX	Vehicles hired for bringing construction material to the site should be in good condition and should have a pollution check certificate and should conform to applicable air and noise emission standards and should be operated only during non-peak hours.
XXI	Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.
XXII	Fly ash should be used as building material in the construction as per the provisions of Fly Ash Notification of September 1999 and amended as on 27th August, 2003. (The above condition is applicable only if the project site is located within the 100Km of Thermal Power Stations).
XXIII	Ready mixed concrete must be used in building construction.
XXIV	Storm water control and its re-use as per CGWB and BIS standards for various applications.
XXV	Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices referred.
XXVI	The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.
XXVII	The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the MPCB and Environment department before the project is commissioned for operation. Discharge of this unused treated affluent, if any should be discharge in the sewer line. Treated effluent emanating from STP shall be recycled/refused to the maximum extent possible. Discharge of this unused treated affluent, if any should be discharge in the sewer line. Treatment of 100% gray water by decentralized treatment should be done. Necessary measures should be made to mitigate the odour problem from STP.
XXVIII	Permission to draw ground water and construction of basement if any shall be obtained from the competent Authority prior to construction/operation of the project.

XXIX	Separation of gray and black water should be done by the use of dual plumbing line for separation of gray and black water.
XXX	Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.
XXXI	Use of glass may be reduced up to 40% to reduce the electricity consumption and load on air conditioning. If necessary, use high quality double glass with special reflective coating in windows.
XXXII	Roof should meet prescriptive requirement as per Energy Conservation Building Code by using appropriate thermal insulation material to fulfill requirement.
XXXIII	Energy conservation measures like installation of CFLs /TFLs for the lighting the areas outside the building should be integral part of the project design and should be in place before project commissioning. Use CFLs and TFLs should be properly collected and disposed off/sent for recycling as per the prevailing guidelines/rules of the regulatory authority to avoid mercury contamination. Use of solar panels may be done to the extent possible like installing solar street lights, common solar water heaters system. Project proponent should install, after checking feasibility, solar plus hybrid non-conventional energy source as source of energy.
XXXIV	Diesel power generating sets proposed as source of backup power for elevators and common area illumination during operation phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low sulphur diesel. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.
xxxv	Noise should be controlled to ensure that it does not exceed the prescribed standards. During nighttime the noise levels measured at the boundary of the building shall be restricted to the permissible levels to comply with the prevalent regulations.
XXXVI	Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
XXXVII	Opaque wall should meet prescriptive requirement as per Energy Conservation Building Code, which is proposed to be mandatory for all air-conditioned spaces while it is aspiration for non-air-conditioned spaces by use of appropriate thermal insulation material to fulfill requirement.
XXXVIII	The building should have adequate distance between them to allow movement of fresh air and passage of natural light, air and ventilation.
XXXIX	Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings.
XL	Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.
XLI	Six monthly monitoring reports should be submitted to the Regional office MoEF, Bhopal with copy to this department and MPCB.
XLII	Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. As agreed during the SEIAA meeting, PP to explore possibility of utilizing excess treated water in the adjacent area for gardening before discharging it into sewer line No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement in Para 2. Prior certification from appropriate authority shall be obtained.
XLIII	Wet garbage should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. Local authority should ensure this.
XLIV	Local body should ensure that no occupation certification is issued prior to operation of STP/MSW site etc. with due permission of MPCB.
XLV	A complete set of all the documents submitted to Department should be forwarded to the Local authority and MPCB.
XLVI	In the case of any change(s) in the scope of the project, the project would require a fresh appraisal by this Department.
XLVII	A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.
XLVIII	Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes and year-wise expenditure should reported to the MPCB & this department.
XLIX	The project management shall advertise at least in two local newspapers widely circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at Website at http://ec.maharashtra.gov.in.

L	Project management should submit half yearly compliance reports in respect of the stipulated prior environment clearance terms and conditions in hard & soft copies to the MPCB & this department, on 1st June & 1st December of each calendar year.
LI	A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.
LII	The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM. SO2, NOx (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.
LIII	The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.
LIV	The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.



Government of Maharashtra

Shri. Anil Diggikar (Member Secretary SEIAA)

- 4. The environmental clearance is being issued without prejudice to the action initiated under EP Act or any court case pending in the court of law and it does not mean that project proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP Act.
- 5. In case of submission of false document and non-compliance of stipulated conditions, Authority/ Environment Department will revoke or suspend the Environment clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.
- 6. The Environment department reserves the right to add any stringent condition or to revoke the clearance if conditions stipulated are not implemented to the satisfaction of the department or for that matter, for any other administrative reason.
- 7. Validity of Environment Clearance: The environmental clearance accorded shall be valid as per EIA Notification, 2006, and amendments by MoEF&CC Notification dated 29th April, 2015.
- 8. In case of any deviation or alteration in the project proposed from those submitted to this department for clearance, a fresh reference should be made to the department to assess the adequacy of the condition(s) imposed and to incorporate additional environmental protection measures required, if any.
- 9. The above stipulations would be enforced among others under the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and rules there under, Hazardous Wastes (Management and Handling) Rules, 1989 and its amendments, the public Liability Insurance Act, 1991 and its amendments.
- 10. Any appeal against this Environment clearance shall lie with the National Green Tribunal (Western Zone Bench, Pune), New Administrative Building, 1stFloor, D-, Wing, Opposite Council Hall, Pune, if preferred, within 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.

Shri. Anil Diggikar (Member Secretary SEIAA)

Copy to:

- 1. SHRI JOHNY JOSEPH, CHAIRMAN-SEIAA
- 2. SHRI UMAKANT DANGAT, CHAIRMAN-SEAC-I
- 3. SHRI M.M.ADTANI, CHAIRMAN-SEAC-II
- 4. SHRI ANIL .D. KALE. CHAIRMAN SEAC-III
- 5. SECRETARY MOEF & CC
- 6. IA- DIVISION MOEF & CC
- 7. MEMBER SECRETARY MAHARASHTRA POLLUTION CONTROL BOARD MUMBAI
- 8. REGIONAL OFFICE MOEF & CC NAGPUR
- 9. MAHARASHTRA STATE ELECTRICITY DISTRIBUTION CO. LTD

Maharashtra

Shri. Anil Diggikar (Member Secretary SEIAA) Particulars

Net Profit / (Loss) for the period (before tax and

Net Profit / (Loss) for the period (before tax after

Net Profit / (Loss) for the period (after tax and

Total Comprehensive Income for the period (Comprising profit / (loss) for the period after tax

and other comprehensive income after tax)

Other Equity (as per last audited balance sheet)

Earning per share (EPS) FV of Rs.10/- each

respective meeting held on 30th June 2020

Particulars

Total income from operations

Paid-up equity share capital (face value of Rs. 10/- each)

(a) Basic (in Rs.)

NOTES:

Place: Mumbai

Date : 30th June, 2020

(b) Diluted (in Rs.)

Net Profit / (Loss) for the period before tax

Net Profit / (Loss) for the period after tax

(after Exceptional and / or Extraordinary items)

(after Exceptional and / or Extraordinary items)

Total Comprehensive Inocme for the period

(Comprising profit /(Loss) for the period (after

Earnings per share (EPS) (not annualised)

and the Company webside (www.daikaffil.com)

specified under Section 133 of the Companies Act, 2013.

date reviewed figures upto third quarter of the relevant financial year.

tax and Other comprehensive income (after tax)

Date: 30/06/2020

Total Income (Net)

exceptional items)

exceptional items)

(not annualised) i) Basic EPS

(ii) Diluted EPS

Place: Mumbai Date: 30th June, 2020

Paid up Equity Share Capital

(Face value r10 per share)

PUBLIC NOTICE

Notice is hereby given that I have been instructed to investigating the title of land owners 1) Maniram Yadav Patil, (2) Kamlakar Yadav Patil, (3) Vijav Yadav Patil & (4) late Suresh Yadav Patil, all residing at Nandgaon through Tarapur, Tal./Dist. Palghar in respect of schedule of

Any person or persons having any claim against or in respect of the land bearing Gut No. 870, admeasuring 0-07-0 hap., out of 0-03-0 hap land in share of late Suresh Yadav Patil through his son Yogesh Suresh Patil, situated lying being at village Nandgaon through Tarapur or any part thereof by way of sale, exchange, mortgage, charge, gift, trust, maintenance, possession, tenancy, inheritance, lease, lien, right of way acquisition, requisition or otherwise howsoever are hereby requested to make the same known in writing along with supporting documents to the undersigned at my office at First Floor, Shrikan Dandekar Building, Near Lokmanya Hotel, Mahim Road, Palghar, Tal./Dist. Palghar within a period of 7 days from the date of publication of the Notice failing which, claims, if any, shall be deemed to have been waived and / or abandoned and the said land title clearance certificate will be given to said owner for purpose of his housing bank loan. Any claims without supporting documents will not be entertained.

> Mr. Sanjay H. Patil Advocate, Palghar

> > Quarter Ended

(6.83)

(6.83)

(6.83)

(6.83)

215.72

NA

(0.32)

(0.32)

(Audited) (Unaudited)

31 Mar 2020 | 31 Dec 2019 | 31 Mar 2019 | 31 Mar 2020 | 31 Mar 2019

0.12

(5.24)

(5.24)

(5.24)

(5.24)

215.72

(0.24)

(0.24)

NA

WESTERN MINISTIL LIMITED

CIN: L28932MH1972PLC015928

REGD OFFICE: Mittal Tower, 'A' Wing, 16th Floor, Nariman Point, Mumbai - 400021 Tel: 022-40750100 | Fax: 022-22044801 | Email:info@westernministil.com

EXTRACT STATEMENT OF STANDALONE AUDITED FINANCIAL RESULTS FOR THE QUARTER AND YEAR ENDED MARCH 31, 2020

(3.25)

(3.25)

(3.25)

(3.25)

NA

(0.15)

(0.15)

3) The above results were reviewed and recommended by the Audit Committee and approved by the Board of Directors at their

DAIKAFFIL

CHEMICALS INDIA LIMITED

Refer note

no.2

386.64

55.76

53.80

43.39

600.00

0.90

0.90

The above audited financial results have been prepared in accordance with the Indian Accounting Standards

The Audited Financial Results for the quarter and year ended 31st March, 2020 have been reviewed and

recommended by the Audit Committee and taken on record in its meeting held on 30th June, 2020 and subsequently approved by the Board of Directors in its meeting held on 30th June, 2020. The statutory

auditors have audited the financial results for the year ended 31st March, 2020 as required under Regulation

Figures for the quarters ended 31st March, 2020 and 31st March, 2019 as reported in these financial results

are balancing figures between the audited figures in respect of the full financial year and published year to

The Company has only one reportable business segment of Manufacturing and trading in Chemicals and Dyestuff, which in the context of Indian Accounting Standard (Ind AS) - 108 is the only reportable segment.

The above is an extract of the detailsed format of the Quarterly Financial Results filed with Stock Exchange under Regulation 33 of the SEBI (Listing Obligations and Disclosure Requirements) Regulations, 2015. The full format Quarterly Financial Results are available on the Stock Exchange webside.(www.bseindia.com)

33 of the SEBI (Listing Obligations and Disclosure Requirements) Regulations, 2015, as amended.

The figures of the previous period(s) have been regrouped / reclassified wherever necessary.

Quarter ended

31.03.2020 | 31.03.2019 | 31.03.2020 | 31.03.2019

Audited

1,656.95

150.04

108.19

97.78

600.00

1.80

1.80

For and on behalf of the Board

Refer note

457.67

49.48

39.03

34.03

600.00

0.57

Regd. Office : E-4, M.I.D.C., Tarapur, Dist-Palghar, Maharashtra - 401506

Office: 52, Nariman Bhavan, Nariman Point Mumbai - 400021

CIN NO: L24114MH1992PLC067309

Statement of Standalone Audited Financial Results for the

quarter and year ended 31st March, 2020

Note: 1) This statement has been prepared in accordance with the Companies (Indian Accounting Standards) Rules, 2015 (Ind AS) prescribed under Section 133 of the Companies Act, 2013 and other recognised accounting practices and policies to the 2) The above is an extract of the detailed format of Quarterly / Annual Financial Results filed with the stock exchange under Regulation 33 of SEBI (Listing Obligations and Disclosure Requirements) Regulations, 2015. The full format of the Quarterly, Annual Financial Results are available on Stock Exchange website viz. www.bseindia.com and Company's website

PUBLIC NOTICE is hereby given that MR. AJA' NAVNITLAL SHAH was the member and wner of Unit No. A/36, Ground Floor, Akurl ndustrial Premises Co-op Soc Ltd., Akurl Road, Kandivali (East), Mumbai - 400 101 MR. AJAY NAVNITLAL SHAH the owner an

ithout making any nomination. ny person/s who has/have anv claim righ itle and interest in the said Unit No. A/36 by way of sale, gift, exchange, mortgage, charge ase, lien, succession, or in any other manne whatsoever should intimate the same to the undersigned within a period of 15 days from the date of publication of this notice at the ddress provided hereunder, with copies o uch documents and other proofs in suppor f his/her/their claims in the said Unit No /36. In case no objections are received within aforesaid time, it shall be presumed that here are no claimants and my clients shall be ree to deal with said Unit.

SMITA R. GHADI Advocate, High Court, Bomba Shop No. 76/EMP75/ Phase 4, Thaku Village, Kandivali (East), Mumbai - 400101

(Rs.In Lacs)

(14.84)

(14.84)

(14.84)

(14.84)

215.72

(588.99)

(0.69)

P. S. Parikh

DIN: 00106727

(Amount In Lakhs

Audited

1,730.01

122.37

86.06

78.55

600.00

1.43

1.43

Director

Year Ended

Year Ended

(Audited) (Audited) (Audited)

(15.43)

(15.43)

(16.14)

(16.14)

(605.12)

(0.75)

(0.75)

For and on behalf of the Board of Directors

For Western Ministil Limited

FORM G

SHREE RAJIV LOCHAN OIL EXTRACTION LIMITED gd. Office : 27/3, Jawahar Nagar, Near Agrasen Bhawan, Raipur - 49200 hone: + 91-771-2225441, 2537846 CIN: L15143CT1994PLC005981

otal income from operations
et Profit / (Loss) for the period (before Tax,
xceptional and/or Extraordinary items#)
et Profit / (Loss) for the period before tax (after
xceptional items and /or Extraordinary items#)
et Profit / (Loss) for the period after tax
fiter Exceptional and/or Extraordinary items#)
otal Comprehensive Income for the period
Comprising Profit / (Loss) for the period (after tax)
and Other Comprehensive Income (after tax)]
muits Share Capital

n the websites of the Stock Exchange(s) www.bseindia.com and the listed entity at www.bseindia.com and the listed entity at www.bseindia.com and the listed entity at www.bseindia.omprehensive income or any other relevant financial item(s) due to change(s) in accounting policies Exceptional and/or Extraordinary items adjusted in the Statement of Profit and Loss in accordano policiable.

quity Share Capital eserves (excluding Revaluation Reserve) nown in the Audited Balance Sheet of the revious year)

evious year) rnings Per Share (of Rs.10/- each) for ntinuing and discontinued operations)

Basic:
 Diluted:

+ 91-771-2225441, 2037 04th Clint. L. 107-305.

Annexure - 1 Format for Newspaper Publishing Purpose (Standalone)
(See Regulation 47 (1) (b) of the SEBI (LODR) Regulations, 2015) (Rugest in Current Year to Correspon

1 Mar. 20

3.79

3.79

2.67

NA

301.5

191.4

0.06 0.06

3 months ended in th

11.92

11.92

8.83

NA

301.5

186.52

31 Mar. 20 previous year 31 Mar. 19

6.6

6.6

4.88

NA

301.5

191.4

For on behalf of Boa Shree Rajiv Lochan Oil Extraction L Sd/- Harish Raheja, Managing Direc

INVITATION FOR EXPRESSION OF INTEREST (Under Regulation 36A (1) of the Insolvency and Bankruptcy (Insolvency Resolution Process for Corporate Persons) Regulations, 2016 For the attention of Prospective Resolution Applicants of M/s SRI ADHIKARI

	BROTHERS TELEVIS	ION NETWORK LIMITED
	RELEVANT	PARTICULARS
1.	Name of the corporate debtor	SRI ADHIKARI BROTHERS TELEVISION NETWORK LIMITED
2.	Date of incorporation of corporate debtor	19/12/1994
3.	Authority under which corporate debtor is incorporated / registered	Registrar of Companies (ROC), Mumbai
4.	Corporate identity number / limited liability identification number of corporate debtor	L32200MH1994PLC083853
5.	Address of the registered office and principal office (if any) of corporate debtor	6th Floor, Oberoi Chambers, Obero Complex, Next to Laxmi Industrie: Estate, Oshiwara, New Link Andheri West Mumbai 400053
	Insolvency commencement date of the corporate debtor	20th December, 2019
	Date of invitation of expression of interest	1st July, 2020
8.	Eligibility for resolution applicants under section 25(2)(h) of the Code is available at:	Send an email at sriadhikaribrothers@kanchansobha.com
9.	Norms of ineligibility applicable under section 29A are available at:	Send an email at sriadhikaribrothers@kanchansobha.com
10.	Last date for receipt of expression of interest	31st July, 2020
11.	Date of issue of provisional list of prospective resolution applicants	10th August, 2020
12.	Last date for submission of objections to provisional list	16th August, 2020
13.	Date of issue of final list of prospective resolution applicants	25th August, 2020
14.	Date of issue of information memorandum, evaluation matrix and request for resolution plans to prospective resolution applicants	16th August, 2020
15.	Manner of obtaining request for resolution plan, evaluation matrix, information memorandum and further information	By email to sriadhikaribrothers@ kanchansobha.com after signing the non disclosure agreement
	Last date for submission of resolution plans	14th September, 2020
17.	Manner of submitting resolution plans to resolution professional	By email to sriadhikaribrothers@kanchansobha.com (password proected and hardcopy in a sealed envelope to thaddress of Resolution Professional as mentioned in point No. 21
18.	Estimated date for submission	14th October, 2020

kanchansobha.com 23. Date of publication of Form G 1st July, 2020 Vijendra Kumar Jain For Sri Adhikari Brothers Television Network Limite Date : 1st July, 2020 Place: Mumbai Resolution professional IBBI/IPA-001/IP-P00721/2017-2018/11253

22. Further Details are available at Send an email at sriadhikaribrothers@

उत्तर पश्चिम रेलवे

मडल रेल प्रबन्धक इजीनियरिंग उत्त पश्चिम रेलवे, जोधपुर द्वारा भारत के राष्ट्रपरि के लिये एवं उनकी ओर से ई—निविदा के माध्यम से प्रचलित नियमों के अन्तर्गत निर्धारित प्रपत्रों में निविदा निम्न कार्यों के त्रए क्रमानसार आमंत्रित की जाती है ई-निविदाँ सूचना स. 2020-21: 64, कार्य का नाम व स्थानः Supply of 1,00,000/- cum stone ballast (Machine Crushed) 65mm Gauge as per revised specification of RDSO track ballast and specification of RDSO track ballast and loading the same into Railway Wagons/ Hoppers at ballast Depot Parihara under ADEN/Degana of Jodhpur Division. अनुमानित लागत रूपये: Rs. 5,89,75,000.00, बयाने की राशि रूपये: Rs. 4,44,900.00, निविदा सूचना संख्या 2020—21/64 निविदा प्रस्तुत करने की तिथि 21.07.2020 को 15.00 बजे तक है। वेबसाईट का विवरण जहाँ पर <u>ई—निविदा</u> देखी व भरी जा सकती है—

हमें f E /NWRailways पर फॉलो करें

www.ireps.gov.in

Caprolactam Chemicals Limited Reg. Off.: B-31, MIDC, Mahad, Dist Raigad, 40230 CIN No. L24110MH1988PLC049683

E-mail: caprolactam@gmail.com; website: www.cap **Extract of Standalone audited Financial** Results for the year Ended March, 2020

-		•	(Rs. In Lakhs)
	Qut. Ended	Year Ended	Year Ended
PARTICULARS	31.03.2020	31.03.2020	31.03.2019
	Audited	Audited	Audited
Total Income from Operations (net)	103.836	656.966	526.049
Net Profit / (Loss) from ordinary activities after Tax	(36.478)	125.797	64.419
Net Profit / (Loss) for the Period after Tax (after Extra Ordinary Items)	(67.164)	95.111	50.164
Equity Share Capital (Face Value Rs. 10/- per share)	460.000	460.000	460.000
Reserves (excluding Revaluation Reserves as shown in the Balancesheet of Previous Year) *		(110.403)	(205.515)
Earnings Per Share (before and after extra Ordinary items) (of ₹ 10/- each)		_	
Basic #	(1.460)	2.068	1.091
Diluted #	(1.460)	2.068	1.091

Note - 1) The above is an extract of the detailed format of Quarterly & yearly audited Financial Results Filed with the Stock Excahnge under Regulation 33 of the SEBI (Listing Obiligations and Disclosure Requirements) Regulations 2015. The full format of the Quarterly & yearly audited Financial Results are available on www.bseindia.com and on the Company website www.caprolactam.co.in

The above audited Financial Results were reviewed by the Audit Committee and approved by the Board of Directors at the meeting held on June 30, 2020. The Statutory Auditors have carried out Limited Review of the above Financial Results

Z S Bhanushali (Chairman Cum Managing Director)

Place : Mahad Dated : June 30, 2020 (DIN NO. 00663374)

KARVYIII FINANCE

Karvy Financial Services Limited CIN: U67190MH2001PLC227379

Registered office address: 705 and 706, 7th Floor, Hallmark Business Plaza, Sant Dnyaneshwar Marg, Opposite Guru Nanak Hospital, Bandra (East), Mumbai - 400 051 Tel. No.: 022 4019 2700, Website: www.karvyfinance.com

	· · · · · · · · · · · · · · · · · · ·												
Ex	Extract of Standalone Audited Financial Results For The Year Ended March 31, 2020												
	(All amounts in ₹ Lakhs, except per share data)												
Sr.	Particular Particular	For the	year ended										
No		March 31, 2020	March 31, 2019										
		(Audited)	(Audited)										
1	Total Income from Operations	1,660.78	5,618.49										
2	Net profit / (loss) for the period (before Tax, Exceptional and/or Extra Ordinary items)	(31,588.44)	2,888.41										
3	Net profit / (loss) for the period before Tax (after Exceptional and / or Extra Ordinary items)	(31,588.44)	2,888.41										
4	Net profit/(loss) for the period after Tax (after Exceptional and / or Extra Ordinary items)	(31,588.44)	1,868.13										
5	Total Comprehensive Income for the period [Comprising profit/ (loss) for the period (after tax) and Other Comprehensive Income (after tax)]	(31,589.76)	1,878.02										
6	Paid-up equity share capital	7,825.00	7,825.00										
7	Reserves (excluding "revaluation reserve")	(351.32)	31,187.79										
8	Net worth	7,473.68	39,012.79										
9	Paid-up debt capital/Outstanding debt	8,491.75	12,041.61										
10	Debt-equity ratio	1.14	0.31										
11	Earnings per equity share [nominal value of share: ₹ 10]												
	Basic	(40.37)	2.39										

Notes

Diluted

Date: - 29.06.2020

Debenture Redemption Reserve

- The above is an extract of the detailed format of yearly financial results filed with BSE Limited under Regulation 52 of the SEBI (Listing Obligations and Disclosure Requirement) Regulations, 2015. The full format of the yearly finacial results are available on the Company's website i.e. http://www.karvyfinance.com and on the website of the Stock Exchange i.e. www.bseindia.com.
- For the items referred in sub-clauses (a), (b), (d) and (e) of the Regulation 52 (4) of the SEBI (Listing and Other Disclosure Requirements) Regulations, 2015, the pertinent disclosures have been made to the BSE Limited and can be accessed on the URL (http://www.karvyfinance.com).
- The Company, being an NBFC, is not required to create DRR in respect of privately placed debentures in terms of Rule 18(7)(b)(iii)(B) of the Companies (Share Capital and Debenture) Rules, 2014.

For and on behalf of Board of Directors

(40.37)

Not Applicable Not Applicable

Karvy Financial Services Limited Sabyasachi Rath

2.39

CEO DIN: 07899850

IORTH WESTERN RAILWAY

of resolution plan to Adjudicating Authority

the resolution professional

20. Name. Address and e-email of

the resolution professional, as

Address and email to be used

for correspondence with the

resolution professional

19. Name and registration number of Mr. Vijendra Kumar Jain

approval

E-Tender Notice निविदा संख्या : MKN/Const.-I/FL-DNA T-419150417. कार्य का नाम स्थान सहित Providing fabrication and assembling In Situ" Glued Insulated Rail Joint Between Degana (including) and Phulera (including) stations... Phulera-Degana doubling project... कार्य की ामानित लागत : Rs. 2.85.08.424.00 बर्याना राशि : Rs. 2,92,600,00, ई-निविदा समापन की अतिम तिथि एवं समय 21.07.2020, 15:00 बजे, वेबसाईट जहाँ पूर्ण ई-निविदा देखी व भरी जा सकती है

617-SP/20 Please join us on 🚹 📙 /NWRailways

PUBLIC NOTICE

Valson

Place : Mumbai

IBBI/IPA-001/IP-P00721/2017-2018/11253

401/402, Sai Trishul, Raviraj Oberoi Complex, Off New Link Road, Andheri West, Mumbai City, Maharashtra ,400053

1507, B Wing, One BKC, Bandra Kurla Complex, Bandra (E), Mumbai- 400 051

vkj310@gmail.com, sriadhikaribrothers@kanchansobha.com

Mr. Viiendra Kumar Jain

Resolution Professiona

vkj310@gmail.com

Mr. Vijendra Kumar Jain Resolution Professional

401/402, Sai Trishul, Raviraj Oberoi Complex, Off New Link Road, Andheri West, Mumbai City - Maharashtra, 400053.

Valson Industries Limited MANUFACTURER OF ART SILK SYNTHETIC YARN **AN ISO 9001 CERTIFIED COMPANY**

CIN No. L17110MH1983PLC030117

REGD.OFFICE: 28, Bldg No.6, Mittal Industrial Estate, Sir M. V. Road, Andheri (E), Mumbai 400059. Phone No : 40661000 Email : cs@valsonindia.com Website:www.valsc

nt of Audited Results for the Quarter and Year Ended 31/03/2020

				(Rs. in Lakhs)
Particulars	Quarter Ending	Corresponding 3 months ended in the previous year	Year to date figures for the current period ended	Year ended
	31-Mar-20	31-Mar-19	31-Mar-20	31-Mar-19
	(Audited)	(Audited)	(Audited)	(Audited)
Total Income from Operations (net)	2,134.45	2,433.98	9,210.44	10,532.65
Net Profit / (Loss) from ordinary activities after tax	17.37	10.07	70.57	219.24
Net Profit / (Loss) for the period after tax (after Extraordinary Items)	17.37	10.07	70.57	219.24
Equity Share Capital	766.08	766.08	766.08	766.08
Reserve (excluding Revaluation Reserves as shown in the Balance Sheet of previous year)	-	-	-	2296.09
Earnings Per Share (before extraordinary items) (of Rs. 10/-each):				
(a) Basic	0.23	0.15	0.92	2.89
(b) Diluted	0.23	0.15	0.92	2.89
Earnings Per Share (after extraordinary items) (of Rs. 10/-each):				
(a) Basic	0.23	0.15	0.92	2.89
(b) Diluted	0.23	0.15	0.92	2.89

Note: The above is an extract of the detailed format of quarter and year ended 31st March 2020 audited financial results filed with the Stock exchanges under Regulation 33 of the SEBI (Listing and Other Disclosures Requirements) Regulations, 2015. The full format of the Quarterly / Annual Financial Results are available on the Stock Exchange website (www.bseindia.com) and company website (www.valsonindia.com).

> For Valson Industries Ltd. Suresh N. Mutreia

Date: 30th June 2020 **Chairman & Managing Director**

M/s. UNIVERSAL ARTS LIMITED

CIN: L22300MH1995PLC091082
Regd. Office: Plot No. 45, Ganpati Bhavan, M.G.Road,Goregaon (W), Mumbai - 400 062. • Tel.: 2874 9001

	EXTRACT OF AUDITED CONSOLIDATED FINAL	NCIAL RESU	LTS FOR TH	E YEAR END	DED 31.03.20	20 (Rs. In lacs)
	Particulars	For the quarter ended 31.03.2020 (Audited)	Corresponding Quarter ended 31.03.2019 (Audited)	Preceding Quarter ended 31.12.2019 (Unaudited)	For the period ended 31.03.2020 (Audited)	For the period ended 31.03.2019 (Audited)
2		19.64 2.21	66.30 36.52	166.67 9.41	569.15 2.11	69.24 (4.96)
2	. ,	2.21	36.52	9.41	2.11	(4.96)
5	Equity Share Capital (Face Value Rs.10 per Share) Other Equity Excluding Revaluation Reserves as per	996.99	996.99	996.99	996.99	996.99
-	balance sheet of previous accounting year Barnings per share (Face Value Rs.10 per Share):	(286.84)	(281.89)	(286.84)	(286.84)	(281.89)
	(a) Basic (b) Diluted	0.02 0.02	0.37 0.37	0.02 0.02	0.02 0.02	N.A. N.A.

EXTRACT OF AUDITED STANDALONE FINANCIAL RESULTS FOR THE QUARTER ENDED 31.03.2020

	Particulars	For the quarter ended 31.03.2020 (Audited)	Corresponding Quarter ended 31.03.2019 (Audited)	Preceding Quarter ended 31.12.2019 (Unaudited)	For the period ended 31.03.2020 (Audited)	For the period ended 31.03.2019 (Audited)
1	Total income from Operations	15.77	65.92	166.53	565.14	67.66
2	Net Profit / (Loss) from continuing operations after tax	(0.24)	37.41	10.19	2.24	(2.48)
3	Net Profit / (Loss) from discontinued operations after Tax	-	-	-	-	-
4	Total Comprehensive Income for the period					
	(Comprising Profit / (Loss)	(0.24)	37.41	10.19	2.24	(2.48)
	and Other Comprehensive Income for the period)					
5		996.99	996.99	996.99	996.99	996.99
6	Reserves Excluding Revaluation Reserves as per					
	balance sheet of	(200.89)	(198.42)	(200.89)	(200.89)	(198.42)
	previous accounting year	,	, ,	, ,		,
7	Earnings per share (Face Value Rs.10 per Share):					
	(a) Basic	N.A.	0.38	0.02	0.02	N.A.
	(b) Diluted	N.A.	0.38	0.02	0.02	N.A.
_						

NOTES:

- The above is an extract of the detailed format of Quarterly / Annual Financial Results filed with the Stock Exchanges under Regulation 33 of the SEBI (Listing and Other Disclosure Requirements) Regulations, 2015. The full format of the Quarterly / Annual Financial results are available on the Stock Exchange websites. (URL: https://www.bseindia.com/)
- ii) The above results are in compliance of Indian Accounting Standards (INS AS) notified by the Ministry of Corporate Affairs. The results for the previous periods have been restated to comply with Ind AS and are comparable on like to like basis.
- iii) Statement of reconciliation of net PAT under IND AS and net PAT reported under previous Indian GAAP (IGAAP) for the previous periods is not applicable as there is no difference between net PAT under IND AS and net PAT as per IGAAP.

For and on behalf of the Board Manish Shah DIN: 00434171 Place: Mumbai Date: 29/06/2020 Managing Director

This is to inform to the general public that, the proposed construction of "Intellion IT Park Building No. 1", at plot no. 23, 23(pt), 24 & 24(pt), TTC Industrial Area, Off Thane-Belapur Road, Mahape MIDC, Navi Mumbai. Maharashtra By M/s. Industrial Minerals & Chemical CO. Pvt. Ltd. has been accorded Environmenta Department, SEIAA, Govt of Maharashtra vide letter no. SEIAA-EC 0000002300, dated: 15/01/2020 and copies of clearance letter are available with the Maharashtra Pollution Contro Board & may also be seen at the website at http://parivesh.nic.in

M/s. Industrial Minerals & Chemical CO. Pvt. Ltd. 1st floor, E-Block, Voltas Compound, Chinchpokli, Mumbai - 400 033.

Mumbai Regional Office: Horizon Building, 1st Floor, Ranade Road & Gokhale Road Junction, Gokhale Road (North), Dadar (West), Mumbai 400 028. Phone No. 022-24476008/57/58

E-AUCTION SALE NOTICE UNDER SARFAESI ACT, 2002 E-auction Sale Notice for Sale of Immovable Assets under the Securitisation and Reconstruction of Financial Assets and Enforcement of Security Interest Act, 2002 read with proviso to Rule 8(6) of the Security Interes

(Enforcement) Rules, 2002. Notice is hereby given to the public in general and in particular to the Borrower Company. Directors and Guarantors that the below described immovable property mortgaged to the Secured Creditor, the physical possession of which has been taken by the Authorized Officer of The Cosmos Co.Op. Bank Ltd., will be sold on basis of "As is where is", "As is what is", and "Whatever there is" for recovery of Bank dues as per the brief

particulars given hereunder:								
Name of Borrower Company, Directors & Guarantors	Demand Notice Date & Amount		Details of Secured Assets for Sale/		Reserve Price	Date & Time of Auction	Date & Time of Inspection	
Borrower Companyr:			piece and parcel of Industrial premises as detailed below:			₹ 2,03,51,000/-	21.07.2020	10.07.2020
M/s. Control Automation Projects		Sr. No.	Gala/Unit No. & Owner	Situated on Floor	Area (Sq.ft.)	(Rupees Two Crores	from	from
Pvt. Ltd.	₹ 9,21,40,859.46	1.	Gala No. 310 - Mr. Sanjay A. Sane & Mrs. Roshan S. Sane	Third	385 Carpet	Three Lakhs Fifty One	1.00 pm to	11.00 am to
	plus further interest	2.	Gala No. 311 - Mr. Sanjay A. Sane	Third	527 Built up	Thousand Only)	2.00 pm	4.00 pm
1. Mr. Sanjay Atmaram Sane	thereon	3.	Gala No. 312 - Mrs. Roshan S. Sane	Third	527 Built up	E.M.D.		
	Present outstanding as on 31.05.2020	4.	Gala No. 312 A - Mr. Sanjay A. Sane of			₹ 20,36,000/-		
Guarantors:	as 011 31.03.2020		M/s. Control Automation Projects Pvt Ltd	Third	527 Built up	(Rupees Twenty Lakhs		
1. Mr. Romir Sanjay Sane	₹ 6,00,00,723.53	All the a	above said Galas/Units which are situated in the building kn	own as "Alpine Indu	strial Premises	Thirty Six Thousand		
2.Mr. Vishwas Atmaram Sane 3.Mr. Rajeshkumar Manikchand	plus further interest		Soc.Ltd Standing on the piece of land situated at Marol Mil			Only)		
Shukla	& charges thereon		ge Marol situate at Andheri (East), Mumbai within Registr of Mumbai City and Mumbai Suburban and with lim			Did Ingramantal Value		
Silukia								
		Corpora						
			enant and common areas and facilities and together with the					
II .		to the r	espective Units/Galas also with fittings, fixtures and right	of ways, easemen	ts, parking and	Only)		ĺ

proportionate right in the land under the Building. Note: - 1) EMD forms are available with Authorised Officer.

Date: 01.07.2020

Place : Mumbai

2) Please contact for EMD payment details to Authorised Officer. 3) Last Date & Time of EMD and KYC Documents Submission: 20.07.2020 upto 4.00 pm.

For detailed terms and conditions of the sale, please refer to the link provided in Secured Creditor's website i.e. https://www.cosmosbank.com OR https://eauctions.samil.in.

General Manager & Authorised Officer Under SARFAESI ACT - 2002 The Cosmos Co-operative Bank Ltd.

अस्वीकृती

प्राथमिक्या प्रात्मिन हारिन्य केल्पाली हारिन्य हार्थावाण घरेषणा किला हार्या हारिन्य केल्पाली हारिन्य केल्पाली हारिन्य केल्पाली हारिन्य केल्पाली हार्या केल्पाली हार्या केल्पाली हार्या केल्पाली हार्या हारिन्य हार्या केल्पाली हार्या हार्या किला उत्पादन केल्पाली हार्या हार्या किला केल्पाली हार्या हार्या किला केल्पाली हार्या हार्

PUBLIC NOTICE

otice is hereby given to Public at large at the undersigned Mr. Ankit Kanak mapta is residing at 303, Kishos Smruti ation Road, Kalwa (W), Dist Thane 806056, Say that my Cousin, Colobologo, Say that ather Rajnikant J. Gandhi expired on 103/2000 at Tehrin Gartual. My mother S. Kamini Kamilesh Gandhi alise Ila anak Sampat expired on 16/09/2004 at umbai.

unter Saingle Ediption University of their Bank account in family depth of their Bank account in family of Bank of Barroda. If anyonel any person area any objection, claim should contact herean bear, bear and bear, for some for branch of E-Dena Bank, Borwial (IV), Junthal al 40092 / below Advocate Sid- Advocate R.K. Tiwari C-3000; Chandhar Hillis, C-1, 23. Lodha Marg, Achivel Road, Nallasopara (E), Dis Palphira 40120; Mob No. 9902669126 Jacks Mumhaii Dale 30062009.

मॅक्स हेल्थके अर इन्स्टिट्यूट लिमिटेड

सीआयएन : यु७२२००एमएच२००१पीएलसी३२२८५४ नॉदणी कार्यालय : १६७, मजला १, प्लॉट-१६७ ए, रेडीमनी मॅन्शन, हाँ. ॲनी बेझंट रोह. वस्की मंबई - ४०००१८

डी. अभी बहुट रिंड, खळा मुंबर - ४००१/६ क्लिप्स क्षेत्र क्षेत्र स्थान सुन्द - ४००१/६ क्लिप्स क्षेत्र स्थान है, या, जा बात्र त्या होण्या क्षेत्र रहे, वील्लाव्ह सिटी, फेब V, सेस्टर - ४२, गोल क्षेत्रेरी से, गुणाब, स्थाना १२२ ००२, भारत देमेल आमयी : investors@markhealthcare.com फेने : १९-२२-४६६० ४४४०, वैष्माहरे : www.markhealthcare.com

स्तान: ११.-२२-६६० ४४४०, वंबास्ट: www.marbealticane.com
स्वास्त्रांन पाट्टो कळिल्यात वेते की, कंपनी ऑपिनया, २०१३ ("अपिनिया") च्य करता १.०८
आणि ११.० सहावाता कंपनीत् (पिनयेट: ऑब ऑपिनया, २०१३ ("अपिनिया") च्य करता १.०८
और्ष्टि ११.० सहावाता कंपनीत् (पिनयेट: ऑब ऑपिनयांन्ट्रांन) रूपन, २०१५ ("रूपा"),
केट्रेट्टीयान ट्रेट्डर और करता स्थिपर (प्राप्त-) आणि कोळींच्ये आपित क्रेच्यानी कंपितिः
सुपारणा किंवा पूर्व अपिनवीमीताल काळी असन्त्राम इत प्रयोग्न कायने आणि माध्यानीच्या
सावुद्धीन्या संबंध हेल्यके आईनिट्यूडर (मिटेड: ("क्ष्त) १३० हेल्युडिन साव्यानायां ("ई)स्वास्तर पुरुषा
"सन्दान्त्र") याचा माध्यानी हिलां १९ रह्न, २०० च्या वेतीच्या पोटताल संपत्री ("स्वास्त वेता प्राप्त)
आहे.

नारण. अधिनियमाच्या संबंधित तरतुर्दीमुसार आणि दिनांक ८ एप्रिल २०२० रोजीचे जनरल सर्क्युलर क्र

गार. सभासदांनी ही सद्धा नोंद्र घ्यावी की, वरील एमसीए सर्क्यलरच्या अनुपालनामध्ये सदर सचनेतील ावर सभासटांच्या सहमती/असहमतीच्या पत्रव्यवहार फक्त ई-मतटान पटतीने घेण्या

्र.... पोस्टल बॅलटची सूचना कंपनीची वेबसाईट www.maxhealthcare.com वर आणि ई-मतदानावरील आरटीएची वेबसाईट www.instavote.linkintime.com. वर उपलब्ध आहे.

'पास्टल चर्ट्या सूचना क्षनीयां वस्त्रीर, www.mashasabinas.com ती ओणा व नेमदिनांवरात आरोदियों वेमाद्री स्थाप्त आरोदियां विश्वास ता स्थापता क्षार्य के स्थापता क्षार्य के स्थापता क्षार्य का स्थापता क्षार्य का स्थापता क्षार्य का स्थापता क्षार्य का स्थापता इ-सन्द भाग नाट्यू शकतात. इ-सन्द पत्याचा यशनवाण नाट्या झाल्याव संभासता सद्द भारत्व विरासार्टी ई-मत्त्रिक क्षणे क्या होण्यासात युक्त आयदी कह ई-मतदानासाटी प्रक्रिया आणि ई-सेवट्ट ऐस्प्रेमेची सांस्ट काँपी मिळेल कोण्यासाटी योकशीसाटी समास्त्र (mestors@machealthcare.com येथे कंपनीला किंवा helpdesk@linkintime.co.in येथे रिकट्स आणि ट्रान्फर एवंट यांना लिह्

भे से प्रचित्ता किया holpdeskiglishinime co.in मेथे रिसर्ग्य आणि ट्रान्यस एवंट यांना तिष्ठ स्वार्थ्या अप्तार होता. इंग्लंड अप्तार श्रीक्ष स्वार्थ्या संदर्भ मेश्वर अर्थे अप्तार्थ्या स्वार्थ्य स्वर्थ्य स्वर्य स्वर्य स्वर्थ्य स्वर्य स्

ग्रंडलाच्या आहेणानमा मॅक्स हेल्थकेअर इन्स्टिट्युट लि.

सदी/-सही/-रुची महाजन कंपनी सचिव, आणि अनुपालन अधिकारी सभासदस्य क्र. एफसीएस ५६७१ ठिकाण : नवी दिल्ली दिनांक : ३०.०६.२०२०

जाहीर नोटीस

हिना नं. सटर३-०८९००-२००७ टिनांक १० दिसेंसर २००७ क) सदर सदनिकेचे मुळप्रत शेर्अस स्टीफिकेट सिरीअल क्रमांक ३६ असा आहे.

७) सर स्वरिकेचे मुख्यत संस्था स्टिकिस्ट सिरीस्त इस्ति स्वर्ण ३६ आता आहे. उन स्वर स्विकेचे मुख्यत संस्था स्वर्ण स्वर्ण

मोबा : ९८२१११८६४

शानत्या तक्रशाचा दखल धतला जाणार नाहा. झानेश्यर एस. कावळे (एम.एससी, एलएलबी, एलएलएम) खकील उच्च न्यायालय, मुंचई शांती सेंटर, शॉप क्र. ७, सेक्टर-१७ वासी, नवी मुंबई २००५०२ मोंद क्र. एमएच/६१६/२०१४

а.	तपतील	संप्रणारे तीन महिने	संपणारे वर्ष	संप्रवारे तीन महिने
<u>ъ</u> .		39.03.7070	39.03.7070	
		लेखापरिक्षित	संख्यापरिक्षित	लेखापरिक्षित
ţ.	प्रकानातुन एकुण उत्पन्न (निध्यळ)	888.59	507.53	9.40
₹.	कालावधीसाठी निव्यस नफा/(शोटा)	1 1		
	(कर, अपवादारमक आणि/किंवा अनन्यसाधारण वावीपूर्वी)	(२८.५८)	\$.86	8.69
٩.	कालावधीसाठी करपूर्व निव्यळ नका/(शोटा)	1 1		
	(अरवादारमक आणि/किंवा अनन्वसाधारण वावीनंतर)	(२८.५८)	\$.86	8.69
۲.	कालावधीसाठी करोशर निव्यक्त नफा/(शोटा)	1 1		
	(अरवादारमक आणि/किंवा अनन्वसाधारण वावीनंतर)	(25.55)	7.8%	8.24
٠.	कालावधीसाठी एकुण सर्वसमावेशक उत्पन्न	1 1		
	(कालावधीसाठी करोशर नफा आणि करोशर इतर सर्वसमावेशक उत्पन्न धरून)	(25.55)	7.8%	8.64
ξ.	समभाग भांडवल	28.00	28.00	28.00
b.	राखीय (मागील वर्षांच्या ताळेबंदात दर्शयिल्याप्रमाणे	19.69	55.69	\$6.35
	पुनर्मृत्यांकित राखीय बनातून)	(\$2.03.2020	(\$2.03.2020	(\$2.03.2025
		रोजी)	रोजी)	रोजी)
٤.	प्रति भाग प्राप्ती (अनन्यसाधारण बाबीपुर्वी आणि नंतर)	1 1	- 1	
	(दर्शनी मृत्य र. १०/- प्रत्येकी)	1 1		
	मृतभूत :	(१२.३३)	1.07	2.03
	संस्थितः :	(१२.३३)	8,02	2,02

मंडळाच्या आदेशायस पुनित कमर्शिअन्स सिमिटेडसा नीरव पी. मेड व्यवस्थापकीय संचालक (डीआयएन : ००५१८६१:

ट्रेन्ट लिमिटेड कॉपॉरट आयडेन्टिटी नं. एल२४ काश्मरः आपदान्द्रया न. एलन्दरभ्ररुणायाच १९५२पीएलमी०८९६१ नींद्रणीकृत कायलियः बाँग्ने राज्या, २५ होगी मोदी स्ट्रीट, मुंबर्च - ४००००१. विषयिः कायलियः हेन्द्र राज्या, जीवलीक, त्यादि नं, सीटि, विके कोशयी बाँहे कुली संकुल, बाँहे पूर्व, मुंबर्च - ४०००५१, हुः (९१-२२) ६७०० ८०९०

र्च-मेलः

अनुसम्राची वार्षिक सर्वसाधारण समा (प्रतीर्ग) कंपनी अनुसम्राची वार्षिक सर्वसाधारण समा (प्रतीर्ग) कंपनीची अनुसम् कंपनीची अनुसम्राची प्रतीरम् मुक्तम, ६ अंगिस्ट, २०० से वी तू. ३.०० मा.प्र.ते. वा. लिहीडओ कंपनियां अन्य प्रतिक्री निव्यक्ति में मिला मार्चक होर्सेच, सम्याच्या कोलीड-१९ साथ गोगावा प्रतीव तथांव प्रेता संबंधित प्राधिकरणाच्या निर्देशांनुसार एनीएम बोताबून घेवती

रागचा प्रमुख्यां तथाडा याता कार्यकार प्राथमण्याण निरात्त्वाच्या एताएव वातावूर धवतां व्यांत,
बार्यात, व्यांत, व्यांत,

ट्रिन्यानंतर. दिन्यानंतर, माहिती वेशतत स्टॉक एक्सनेंव ऑफ हीडया तिमिटेड (www.nseindia.com) व बीएसई तिमिटेड www.bselindia.com) ज्या वेसासॉट्टन आणि त्याचप्रमाणे कंपनीची वेसासॅट www.west-de.com वर सुद्धा उपलब्ध आहे. टेन्ट तिमिटेड साठी ट्रेन्ट लिमिटेड स्प

एम. एम. सुरती कंपनी सेक्रेटरी

पुनित कमर्शिअल्स लिमिटेड सीआवर्ष : स्त ५१९०० ज्यान १५००

भुगिः । स्त ५१९०० एक्पय १९८४ चीएससी ०३४८८० १२२, ए टॉबर, भारत डायबंड बोर्स, बीकेसी, बांद्रे (पूर्व), मुंबई-४०००५१. mercials.com, इं-मेल : fatimad@punitcommercials.c एक्पा तिमाडी आणि चर्षाकरिता सेखापरिक्षित विसीच निष्कर्षांचा इतारा

📭 अजंता फार्मा लिमिटेड

(सीआवएन नं. एत्र१४२३०एमएच१९७९पीएतसा०२२०५९) नों. कार्यात्मवः 'अन्तंत इत्जम', चारकोग, कारिवती (पचिचा), मुंबई-१ दू.क्र. : ०२२-६६०६१००, फॅक्स क्र. : ०२२-६६०६१२०० जेन्सार्थन . i.e.

४१ व्या वार्षिक सर्वसाधारण सभेवावत माहिती

ाट्टारे सूचना रेण्यांत येते की : ^{गण्येण}ण बोलवणाऱ्या सूचनेत मांडलेले कामकाड करण्याकरिता कंनी अधिनियम, २०१३ च्या सर्वे े*े* — गणिण ग्रिक्सारिटीव औड एक्स्चेंब बोर्ड ऑफ हुत्ते सूचल स्थाप के की हैं।

उपयोग्य अंदरणाय पूर्वन पंडातेन समस्य सरणवारीय स्त्री आधिमा, २०१३ च्या वर्ष प्रयोग सहस्य अधिमान पूर्वन पंडातेन समस्य स्थापित प्राप्त हुन्दे आणि वर्ष अंदर्वन स्वत्य स्थापित स्था

ever-aerusi agreat ainute interez आणा जास्तर राज्य स्वस्था अंतिहरूवा संस्थादित अनुस्त्री क्षाप्त अफाकातांक्री का आणांक्री अफाकातांक्री क्षाप्त कर रहिन्दा उत्तरक का रिक्रीय उत्तरक का स्वार्थ अस्ति अस्त्र कर्मा क्षाप्त कर स्वार्थ कर स्वर्ध कर स्वर्ध कर स्वार्थ कर स्वार्थ कर स्वर्ध कर स्वर्ध कर स्वार्थ कर स्वर्ध कर स्व

सही/-

दिनांकः ३०/०६/२०२०

जाहीर सचना

जाहीर सूचना वर्त तम्मा ज्यांचेत्र असे कविष्णपात्र से स्वित्त स्वित्त असे कविष्णपात्र से स्वित्त स्वित्त स्वित्त स्वित्त स्वित्त इंतियत्त अवस्यी मार्क स्वत्य स्वत्य स्वित्त प्रतित्त स्वत्य मार्क्स स्वत्य स

आहेत आणि http://parivesh.nic.i या वेबसाईटवर देखील उपलब्ध आहे.

सही/-मे. इंडस्ट्रियल मिनरल्स अँड केमिकल कंपनी प्रा. लि. पहिला मजला, ई-ब्लॉक, व्होल्टास कंपाऊंड, विंचपोकळी,

मुंबई - ४०० ०३३. महाराष्ट्र.

SAVANI FINANCIALS LIMITED

14 e, Marol Co-op Indl. Estate, nbai 400059.

STATEMENT OF STANDALONE AUDITED FINANCIAL RESULTS FOR THE QUARTER AND YEAR ENDED ON 31ST MARCH, 2020 Audited Audited Audite

No.	raidculais	31st March 2020	31st March 2020	31st March 2019
1	Total Income from operations (net)	3.47	13.76	3.43
2	Net Profit / (Loss) from ordinary activities after tax	1.35	2.16	1.32
3	Net Profit / (Loss) after tax (after extraordinary items)	1,35	2.16	1.32
4	Equity Share Capital (Face Value of Rs.10/- each)	400.00	400.00	400.00
5	Reserves (excluding Revaluation Reserves as per balance sheet of			
6	previous accounting year) Earnings per share -	-	-	-
	before and after extraordinary items (not annualized) Basic and Diluted (Rs.)	0.03	0.05	0.03

DEEPA TRACY MANAGING DIRECTOR

मुल्लर अँड फिप्स (इंडिया) लि.

वॉदगी. कार्याला: २०४, माध्या विविद्धा, याद्रे-कुलां सुक्त, वाद्रे पूर्व, मूर्वई-४०० ०५१. १९ क्र.: ०२२-२४३२६८८५, कंसा: ०३२-२४२४२७६, संकेतसब्ब: www.malphico.co.in प्रोत्रास्त्र क: एलह.३०० एलस्य ११५०णीएलस्वि ०००८९ ३१ मार्च, २०२० रोजी संपनेस्था तिमाही आणि वर्षासाठी वित्तीय निष्कर्षाचा उतारा

							₹ लाखाः
अनु.	तपशिल		अवि	एकत्रित			
雍.		संपलेली	तिमाही	संपले	नी वर्ष	संपले	ले वर्ष
		39.03.7070	39.03.7099	39.03.7070	39.03.7099	39.03.7070	39.03.2089
		अलेखापरिक्षित	लेखापरिक्षित	अलेखापरिश्वित	लेखापरिश्चित	लेखापरिश्चित	लेखापरिश्वित
٩	प्रवर्तनातून एकूण उत्पन्न (निव्वळ)	90.05	64.06	40.00	३१३.९६	३१३.९६	383.98
2	कर, अपवादात्मक बाबींपूर्वी कालावधीसाठी निव्वळ	6.80	٤.३२	(१७.६०)	(३.७९)	(३.७९)	(३.७९)
	नफा/(तोटा)						
3	कालावधीसाठी करपूर्व, अपवादात्मक बाबीनंतर निव्वळ	6.80	٤.३२	(१७.६०)	(9.5%)	(3.68)	(३.७९
	नफा/(तोटा)	(0.84)	(२.१५)	(0.84)	१.०६	१.०६	8.01
8	कालावधीसाठी करोत्तर निव्वळ नफा	۷.02	४.१७	(१८.०५)	(२.७३)	(२.७३)	(२.७३
4	कालावधीसाठी एकूण सर्वसमावेशक उत्पन्न (कालावधीसाठी						
	नफा (करोत्तर) आणि इतर सर्वसमावेशक उत्पन्न (करोत्तर)	£2.40	£2.40	६ २.५०	६२.५०	६२.५०	£2.4
	धरून)						
ε	भरणा झालेले समभाग भांडवल (दर्शनी मूल्य रु. १०/-				(५५४.९४)	(५५४.९४)	(448.98
	प्रत्येकी)						
છ	प्रती समभाग प्राप्ती - ईपीएस (मूलभूत आणि सौम्बिकृत)	१.३६	१.०१	(२.८२)	(০.६१)	(০.६१)	(০.६१)
	(दर्शनी मूल्य रु. १०/- प्रति समभाग)	१.३६	१.०१	(२.८२)	(০.६१)	(০.६१)	(0.53)

टिपा:

.... २९ जन, २०२० रोजी ब्रालेल्या बैठकीमध्ये ३१ मार्च. २०२० रोजी संपलेल्या तिमाही/वर्षासाठीचे निष्कर्ष लेखापरिक्षण समितीने पनर्विलोकीत केले आणि संचालक मंडळाने

मंत्रु केले. वरील निष्कर्ष कंपनी अधिनियम, २०१३ च्या क्लम ११३ अंतर्गत विहित कंपनीज (इंडियन अकाऊंटींग स्टैंडईस) रूत्स, २०१५ (इंड एएस) सह वाचता त्याअंतर्गत जारी संबंधित बीरात निष्मेष कोती आधानमा, १८६२ च्या करना, १८६३ वराण तमाहार नियम आणि भारता संस्तामाराण्ये निर्माश्च तोचा तानांचारा आर्था राज्य क्षात्र कर करता आहे. तिमाही तमाहित्य अधि आराता आहे. सेवी (सिरिंग औड अरा डिस्सोबर विश्वायायेश) भाष्ट्रियास २०१५ च्या पहुंच ३ अंतर्गत उत्तरा आहे. तिमाही त्यार्थिक सिर्माण सेवार स्टॉक एसमिवरानी बनायों (www.besindi.com) आणि करोगी सेवारिकास्थ (www.mulphico.com) यर देखील उपलब्ध आहे.

मळर औंद्र फिप्स (इंडिया) लि. करिता सही/-

मिलन दलाल ठिकाण: मुंबई दिनांक: २९ जून, २०२० संचालक हीआयणन क. ०००६२४५३

जाहीर सूचना
माठे अशीत की. बेहुत किशोर होया आणि सी. विनाशी
किशोर होया ज्यांण लगा १/६५ औ. अगटरी पाळ,
प्रदेशवादी, थिए। वाजार, मुंखं - ४०००२ शांनी
माठितव्यक्तम सुक्रम चाढ़िद देवाओं की आहे. है। सीमात प्रदेशवादी, थिए। वाजार, मुंखं - ४०००२ शांनी
माठितव्यक्तम सुक्रम चाढ़िद देवाओं की आहे. है। सीमात प्रदेशवादीस, प्रोज्यस्यी कमाने, प्रोणायर श्री नैकी।
सिन्तिमाता माठ्य प्रयोग तथा जो अस्तिनी चीपाल कालील तिहित्साम माठ्य प्रयोग तथा जो अस्तिनी चीपाल

पर उपाय क्र. ५.५ (प्रतितिशि) आर्गत प्राचेश्वी १. ५०/ व दोआं आप्रा मिळकांचीर सर्व दे मान आणि योग्या वर्षः/दिसंकः ३० च्ह्र., ०२० सही अंड. अतिसर, रक्ता प्रचित्त क्रम न्याय चुनिद क्र. १. तकावरका, स्वित्ति, क्रम द्वार्थः १५ व्या चित्रः १८ तकावरका, स्वित्ति, स्वारं (१) मुंबर्ट चित्रिः, स्वारं (१) मुंबर्ट सेन्सिं, स्वारं (१) मुंबर्ट सेन्सं १८८२०१११४४४/ १९६०६११

NRB BEARINGS

एनआरबी बेअरिंग्ज लिमिटेड

सीआयएन:एल२९१३०एमएच१९५६पीएलसी०१३२५१ नों. कार्यालय : धन्नुर, १५, सर पी. एम. रोड, फोर्ट, मुंबई-४०० ००१.

द्.क्र. : ०२२-२२६६४५७०/२२६६४९६०/२२६६४९९८ फॅक्स क्र. : ०२२-२२६६०४९२, वेबसाईट : www.nrbl

३१ मार्च, २०२० रोजी संपलेल्या तिमाही आणि वर्षासाठी वित्तीय निष्कर्षाचा उतारा

	अलिप्त				एकत्रित					
	संपलेली तिमाही	संपलेली तिमाही	संपलेली तिमाही	संपलेली वर्ष	संपलेली वर्ष	संपलेली तिमाही	संपलेली तिमाही	संपलेली तिमाही	संपलेली वर्ष	संपलेली वर्ष
तपशिल	३१.०३.२०२० अलेखापरीक्षित	३१.१२.२०२० अलेखापरीक्षित	३१.०३.२०२० अलेखापरीक्षित	३१.०३.२०२० लेखापरीक्षित	३१.०३.२०१९ लेखापरीक्षित	३१.०३.२०२० अलेखापरीक्षित	३१.१२.२०१९ अलेखापरीक्षित	३१.०३.२०१९ अलेखापरीक्षित	३१.०३.२०२० लेखापरीक्षित	३१.०३.२०१९ लेखापरीक्षित
१ प्रतर्वनातून एकूण उत्पन्न	१७,८११	१७,७००	२१,३४१	७५,१९६	98,036	१८,७५२	१८,३०८	२१,९६६	७७,५९५	९६,५०२
२ कालावधीसाठी निव्वळ नफा (कर, अपवादात्मक आणि/किंवा अनन्यसाधारण बार्बीपूर्वी) ३ कालावधीसाठी करार्व निव्वळ नफा (अपवादात्मक आणि/किंवा	1900	१,०८८	१,४३९	४,१६३	१२,६१४	٩٥٥	१,३१९	१,९८७	४,६८३	१४,०५६
अनन्यासाधारण बाबीनंतर)	1900	8,066	8.838	४,१६३	१४,२६८	566	8,388	१,९८७	४,६८३	१५,७१०
४ कालावधीसाठी करोत्तर निश्वळ नका (अपवादात्मक आणि/किंवा अनन्य साधारण वार्वीनंतर)	892	688	१,१७३	2.984	9,200	888	१,०५२	8.290	3,388	१०,९९०
५ एकूण सर्वसामावेशक उत्पन्न (करोत्तर)	(488)	788	35	(806)	(१३६)	(५१३)	₹,04₹ १ ७५	(११६)	(444)	(१९३)
६ भरणा झालेले समभाग भांडवल (संपूर्ण भरणा झालेले प्रत्येकी रु. २/- मूल्याचे) ७ ताळेबंदानसार राखीव (पुनर्मूल्यांकीत राखीव वगळून)	१,९३८	१,९३८	१,९३८	१,९३८ ४३,९५९	१,९३८ ४५,४६२	१,९३८	१,९३८	१,९३८	१,९३८ ४३,७५२	१,९३८ ४५,११४
 ताळबदानुसार राखाव (पुनम्-त्याकात राखाव वगळून) प्रति समभाग प्राप्ती (अनन्यसाधारण बाबींपूर्वी व नंतर) प्रत्येकी रु. २/ - चे) 										
मुल्यभृत	०.५१	0.66*	१.२१ [#]	3.08	१०.१९	0.83#	8.00 ⁴⁸	۲.३३ [®]	3.38	११.१७
सौम्बिकृत	०.५१%	۰.۵۵	१.२१ [#]	3.08	१०.१९	0.83*	₹.0७ [®]	۶.३३ [‡]	३.३१	११.१७

. २८ चुन, २०१० रोजी झालेल्या त्यांच्या संबंधित बैठकांमध्ये लेखा परीक्य समितीने वरील निष्कर्य पूर्विलाकीत केले आणि त्यानंतर संचालक मंडळाने ते मंजूर केले. निष्कर्षाना कंपनी अधिनियम, २०१३ च्या कलम १३३ अंतर्गत विश्ति कंपनीच (ईड एएस) रूलम, २०१५ वांकरनीच (ईडियन अकाउंटीण स्टैंडई) (अचेडमेंट) रूलस २०१६ नुसार बनवले आहे.

१८९४- पुरा चनाच्या १५ । १९९४ - १९९४ के ११ मार्च २०१९ रोजी संपत्तन्या तिमादीसाठीची आकडेवारी द्वा त्या तारखेस संपत्तन्या वर्षासाठी लेखारारीक्षत आकडेवारी आणि लेखारारीक्षकांनी मर्याटित पनविलोकन केलेल्या संबंधित आर्थिक वर्षाच्या तिसन्या तिमाही अखेरीसच्या तारखेरपँत वर्षच्या आकडेवारी दरम्यानच्या तौलानिक आकडेवारी आहेत

्रभागण वासामक अच्छावा असता. भूत रे एमिल, २०११ तीमा संपत्तेच्या बद्धा क्रमा अम्बादासक प्राप्त ११६ ''माडेप्डा' चा अक्तंब केला आणि विशीय निष्कांबर कोणवाही त्यवणीय पिणान हातेला नाही. ३२ गर्च, २०११ तीमा संपत्तेच्या वर्षा हरणान अमबादासक प्राप्त माम्ब निष्कातीच्या विकीयतेत अभिवय आहे. १२ तांब १२ फेबुबर्सा, २०१४ वीमा संपत्तिच्या त्यांच्या बैठकतेत प्रत्येकी इ. २ हर्सनी मूलांच्या केम्सवर इ. ०.०८ च्या अंतीय सामांशायो घोषणा संपातक मंडाजने केसी. कंपनीच्या वार्षिक सर्वसाधाण समेत ३१ मार्च, २०११ तेत्री संपत्तेच्या विसीय वर्षाती संबधित प्रति होअस इ. २.६ चा लामां (अतिक) घोषणा केसी. टीप: बंगीन उतारा स्थाने संभी (तिर्दिण अंग्ड अदा डिस्नतोज्य रिक्शास्ट्रम्) ऐप्युनेतन, २०१५ च्या रेपुनेतन ३३ अंगरित स्टॉक एक्क्वेसकडे साद केलेती तिमाही/वर्षिक वित्तीय निष्कर्ताच्या तप्त्रीतावर विवयणाया एक उतारा आहे. तिमाही/वर्षिक वित्तीय निष्कर्ताच्या वीएसां भी http://www.trbbearings.com/ या उत्तरप्त्र आहे.

(श्रीमती) हर्षवीन झवेरी उपाध्यक्ष आणि व्यवस्थापकीय संचालक